




- NOTES:
1. SEE ARCH'L DRAWINGS FOR SIZE AND LOCATION OF OPENINGS.
 2. PROVIDE MINIMUM OF 4" OF BEARING EACH SIDE OF OPENING.
 3. REINFORCING SHALL PROJECT A MINIMUM OF 16" INTO BEARING.
 4. MINIMUM MASONRY COMPRESSIVE STRENGTH, f'_m , SHALL BE 1500 P.S.I.
 5. CAST-IN-PLACE CONCRETE LINTELS SHALL BE PROVIDED AT OPENINGS ADJACENT TO CONCRETE COLUMNS OR THE COLUMNS

