




REVISION: _____
NO. DESCRIPTION

ENGINEER _____
VICTOR RAMOS P.E. LIC No: 87496
7700 N KENDALL DR, SUITE 706, MIAMI FL 33156
(786) 830-3551

Victor Ramos
Digitally signed
by Victor Ramos
Date: 2025.05.19
14:01:51 -04'00'

THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY VICTOR RAMOS, P.E. ON THE DATE AND/OR TIME STAMP SHOWN USING A DIGITAL SIGNATURE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED BY A 3RD PARTY CERTIFICATE AUTHORITY ON ANY ELECTRONIC COPY.

DESIGNER: _____



PROJECT: _____

NEW CONCRETE SWIMMING POOL & SPA

ADDRESS: _____

6200 SW 123RD TERRACE, MIAMI, FL 33156

PROJECT DATE: 5.9.2025
DRAWING BY: MR
CHECKED: FD

SHEET TITLE: _____

STRUCTURAL PLAN

SHEET No: _____



A.1

STRUCTURAL NOTES:

- ALL POOL CONCRETE SHALL DEVELOP A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF $f_c=3,500$ PSI.
- ALL PILE CONCRETE SHALL DEVELOP A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF $f_c=5,000$ PSI.
- ALL REINFORCING STEEL SHALL HAVE A MINIMUM YIELD STRENGTH OF $F_y=60,000$ PSI.
- ALL DECK CONCRETE (WHEN INSTALLED UNDER THESE PLANS) SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF $f_c=2,500$ PSI.
- THE DESIGN OF THIS PROJECT HAS INCORPORATED A RATIONAL DESIGN APPROACH BASED ON ACCEPTED ENGINEERING PRINCIPLES.
- ALL REINFORCING STEEL SPLICES SHALL BE 24" IN LENGTH FOR #3 BARS AND 30" FOR #4 UNLESS OTHERWISE NOTED ON PLANS.
- ALL REINFORCING STEEL HOOKS SHALL DEVELOP A LENGTH OF 9" FOR #3 BARS AND 11" FOR #4 BARS UNLESS OTHERWISE NOTED ON PLANS.
- DEVELOPMENT FOR REINFORCING STEEL SHALL BE 18" FOR #3 BARS AND 24" FOR #4 BARS UNLESS OTHERWISE NOTED ON PLANS.
- A 3" MINIMUM CLEAR CONCRETE COVER SHALL BE PROVIDED.

FLOOR AND WALL CONCRETE SCHEDULE FOR SWIMMING POOL		
THICKNESS	REINFORCEMENT	
WALL	6"	#3@9" VERTICAL & HORIZONTAL
FLOOR	8"	#3@6" BOTTOM EACH WAY

FLOOR AND WALL CONCRETE SCHEDULE FOR SPA		
THICKNESS	REINFORCEMENT	
WALL	10"	#3@6" VERTICAL & HORIZONTAL BOTH FACES
FLOOR	8"	#3@6" BOTTOM EACH WAY



COMPLYING WITH ANSI/APSP 5.6 FLOOR SLOPES

- (A) RISER HEIGHT MUST BE UNIFORM (TOP & BOTTOM MAY VARY) (12" MAX)
(B) CONTRASTING TILE AT EDGE (OPTIONAL)
(C) TREADS SHALL HAVE SLIP-RESISTANT SURFACES-ANSI/APSP-ICC-5.6.1.5





ITEM	FLOTATION ANALYSIS CALCULATION	ELEVATION	UNITS
A	TOP OF POOL WALL ELEVATION (NGVD)	11.37	FT
B	DISTANCE FROM TOP OF WALL TO WATER LEVEL	0.33	FT
C	DEPTH OF POOL AT SHALLOW END	3	FT
D	DEPTH OF POOL AT DEEP END	5	FT
E	SLAB THICKNESS	0.67	FT
F	ELEVATION OF POOL BOTTOM	5.37	FT
G	FLOOD CRITERIA (NGVD) ZONE X (ELEV.=N/A)	8	FT
H	INITIAL WATER HEAD= G-F	2.63	FT
I	LESS HYDROSTATIC RELIEF VALVE (FBC 1618.24)	2	FT
J	ADJUSTABLE WATER HEAD H-I	0.63	FT
K	WATER WEIGHT	62.4	LB/FT3
L	UPLIFT PRESSURE= J x K	39.104	PSF
(UP) POOL UPLIFT PRESSURE AREA = L x M		53,963.52	POUND

M	POOL AREA	1380.00	SQ.FT
N	CONCRETE'S VOLUME OF SIDE WALL (BOTH)	276.00	FT3
O	CONCRETE'S VOLUME OF SHALLOW END WALL	30.00	FT3
P	CONCRETE'S VOLUME OF DEEP END WALL	50.00	FT3
Q	CONCRETE'S VOLUME OF BOTTOM SLAB	920.00	FT3
R	CONCRETE'S VOLUME OF SWIMOUT	0.00	FT3
S	CONCRETE'S VOLUME OF SPA	190.06	FT3
T	CONCRETE WEIGHT	150.00	LB/FT3
(DOWN) TOTAL POOL WEIGHT=(N + O + P + Q + R + S) x T		219,909.10	POUND


TOTAL POOL WEIGHT CONCRETE > POOL UPLIFT PRESSURE (OK)
PROPOSED THICKNESS FOR POOL WALLS = 6 INCHES
PROPOSED THICKNESS FOR POOL SLAB = 8 INCHES

POOL SPECIFICATION TABLE		
SIZE	20 X 69	FT
SHALLOW END	3.00	FT
BOTTOM OF POOL	5.00	FT
PERIMETER	178	LF
AREA	1380	SQ.FT
CAPACITY	41,290	GLS
PUMP*	2.7	HP
FILTER	300	SQ.FT
TILE	6" (BY OWNER)	
TYPE OF PATIO	SLIP RESISTANT	
BLOWER	N/A	HP
WATER HEATER (GAS)	400,000	BTU
TURNOVER RATE	5.93	HRS
*RESIDENTIAL POOL FILTER PUMP MOTORS WITH A CAPACITY OF 1 HP OR GREATER SHALL HAVE THE CAPABILITY OF OPERATING AT TWO OR MORE SPEEDS PER FBC RE R403.12		

SPA SPECIFICATION TABLE		
SIZE	8 X 9.5	FT
DEPTH	3.00	FT
PERIMETER	35.00	LF
AREA	76	SQ.FT
CAPACITY	1706	GLS
PUMP*	1.50	HP
FILTER	SAME AS POOL	SQ.FT
TILE	6" (BY OWNER)	
TYPE OF PATIO	SLIP RESISTANT	
BLOWER	2	HP
WATER HEATER (GAS)	400,000	BTU
TURNOVER RATE	0.52	HRS
*RESIDENTIAL POOL FILTER PUMP MOTORS WITH A CAPACITY OF 1 HP OR GREATER SHALL HAVE THE CAPABILITY OF OPERATING AT TWO OR MORE SPEEDS PER FBC RE R403.12		



PROPOSED POOL LAYOUT
SCALE: 1/4" = 1'-0"



REVISION: _____
NO. DESCRIPTION

ENGINEER _____
VICTOR RAMOS P.E. LIC No: 87 496
7700 N KENDALL DR, SUITE 706, MIAMI FL 33156
(786) 830-3551

Victor Ramos
Digitally signed by Victor Ramos
Date: 2025.05.19 14:01:42 -04'00'

THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY VICTOR RAMOS, P.E. ON THE DATE AND/OR TIME STAMP SHOWN USING A DIGITAL SIGNATURE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED BY A 3RD PARTY CERTIFICATE AUTHORITY ON ANY ELECTRONIC COPY.

DESIGNER: _____



TERRA
ENGINEERING
CONSULTING

PROJECT: _____

NEW CONCRETE SWIMMING POOL & SPA

ADDRESS: _____

6200 SWJ 123RD TERRACE, MIAMI, FL 33156

PROJECT DATE: 5.9.2025
DRAWING BY: MR
CHECKED: FD

SHEET TITLE: _____

STRUCTURAL PLAN

SHEET No: _____

A.2

