



ENGINEERING COVER SHEET

This cover sheet is provided as per Florida Statute 61G15-23.001, F.A.C. in lieu signing and sealing each individual sheet. An index sheet of the quantity of truss designs specified below is attached with the identification and date of each drawing.

Quantity of Truss Designs:

123

LAZ CONST. - 12715 ROLLING ROAD DR. REV 6/5/25

Building Authority:
Design Loads:

PINECREST, FL.

Roof:30-15-0-10 psf

Wind: 175 mph

Exposure.C

Kd: .85

HVHZ

DOL: Plate: 1.33 Lumber: 1.33

FBC 2020 / TPI 2014 / ASCE 7-16

Building Code:
Software Used:

MITEK 2023 v 8.7

Attachments:

Truss placement diagram, Truss profile list, Certificate of Competency, Product approvals, Valley detail, Web bracing recommendation.

Engineer of Truss Design Package:

ULTIMATE ENGINEERING DESIGNS INC.

9590 N.W. 89th Avenue

MEDLEY, FL 33178

PHONE: (305) 882-8826 (Office)

ARMANDO R. PEREZ. P.E. 28026



















This item has been digitally Signed and Sealed by Armando R. Perez, P.E. 28026 on the date adjacent to the seal .

Printed copies of this document are not considered Signed and Sealed and the signature must be verified on any electronic copies.

ARMANDO R. PEREZ P.E. 28026
9590 NW 89 AVE MEDLEY, FL 33178
PH: 305-882-8826











CUETO ENGINEERING	
SHOP DRAWING / SUBMITTAL REVIEW	
☒ APPROVED	☐ REJECTED
☐ APPROVED AS NOTED	☐ REVISE & RESUBMIT
This submittal has been reviewed for design conformity and general compliance with Contract Documents. The Contractor is solely responsible for: confirming all dimensions and quantities; procedures, means, methods, techniques, and sequences of fabrication and construction; coordination of work for all trades; and full compliance with design documents.	
By : <u>Nestor A. Cueto, PE</u> Date : <u>06-06-25</u>	

Trusscorp International, Inc. 9590 NW 8th Ave Medley, FL 33178 (305) 882-8826 Fax: (305) 887-6008			To: 			Reaction		
Project: LAZ CONST. Model: 12715 ROLLING RD		Block No: Lot No:				Job Number: B2500171 Page: 1 Date: 06/05/25 12:50:58		
Contact:	Site:	Office:	Deliver To:			Account No: 254504030 Designer: / Salesperson: Inside Sales Quote Number: B2500171 P.O. Number:		
Name:								
Phone:								
Fax:	.F.							







	Qty:	Truss Id:	Span:	Truss Type:	Slope	Reactions:				
	2	CJ5	06-11-06	DIAGONAL HIP	2.83	Joint 3 1055.86 -1407.85	Joint 8 396.87 -554.60	Joint 10		
	4	CJ5A	06-11-06	DIAGONAL HIP	2.12	Joint 3 1106.66 -1460.27	Joint 8 400.06 -534.99	Joint 10		
	5	CJ5AT	06-11-06	DIAGONAL HIP	2.12	Joint 3 1340.34 -1693.21	Joint 8 484.18 -617.74	Joint 10		
	2	CJ5C	06-11-06	DIAGONAL HIP	2.12	Joint 3 1387.28 -1750.42	Joint 8 443.51 -560.59	Joint 10		
	4	CJ5T	06-11-06	DIAGONAL HIP	2.83	Joint 3 1108.41 -1347.04	Joint 8 508.68 -678.96	Joint 10		
	1	CJ7	09-09-05	DIAGONAL HIP	2.83	Joint 3 1182.02 -1496.64	Joint 8 618.22 -828.49	Joint 10		
	2	CJ7B	09-07-13	DIAGONAL HIP	2.12	Joint 3 1285.19 -1604.73	Joint 8 530.98 -662.92	Joint 10		
	1	CJ7T	09-09-05	DIAGONAL HIP	2.83	Joint 3 1447.95 -1762.69	Joint 8 760.55 -970.72	Joint 10		
	1	H1	21-04-00	HIP	4.00	Joint 3 1445.02 -1326.07	Joint 7 1459.43 -1338.36	Joint 13	Joint 14	
	1	H10	25-00-00	HALF HIP	3.00	Joint 3 1654.47 -1336.78	Joint 8 1356.30 -988.43	Joint 13		
	1	H10T	25-00-00	HIP	3.00	Joint 3 1725.80 -1821.43	Joint 7 1758.64 -1855.09	Joint 14	Joint 15	
	1	H11	25-00-00	HALF HIP	3.00	Joint 3 1670.03 -1330.86	Joint 9 1334.08 -991.18	Joint 14		
	1	H11T	25-00-00	HIP	3.00	Joint 3 1724.51 -1806.38	Joint 9 1746.59 -1828.00	Joint 17	Joint 18	
	1	H12	25-00-00	HIP	3.00	Joint 3 1661.31 -1340.54	Joint 8 1365.51 -1064.74	Joint 13		
	1	H12T	25-00-00	HIP	3.00	Joint 3 1730.22 -1762.51	Joint 8 1754.22 -1786.60	Joint 15	Joint 16	
	1	H14	46-01-14	HIP	3.00 3.22	Joint 3 1608.92 -1237.78	Joint 16 624.56 -593.77	Joint 23 3486.90 -2432.57	Joint 34	Joint 35
	1	H15	46-01-14	HIP	3.00 3.22	Joint 1 279.23 -145.29	Joint 3 1595.93 -1204.03	Joint 7 279.23 -145.29	Joint 8 437.88 -395.01	Joint 10 260.85 -129.68
	1	H16	46-01-14	HIP	3.00 3.22	Joint 3 1607.04 -1187.14	Joint 14 635.25 -486.22	Joint 20 3559.66 -2596.39	Joint 30	Joint 31
	1	H17	46-01-14	HIP	3.00	Joint 3 1639.98 -1232.43	Joint 14 748.46 -531.80	Joint 20 3375.72 -2538.36	Joint 26	Joint 27
	1	H18	46-01-14	HIP	3.00	Joint 3 1629.43 -1205.97	Joint 16 715.15 -481.50	Joint 22 3452.56 -2616.35	Joint 28	Joint 30









Trusscorp International, Inc. 9590 NW 8th Ave Medley, FL 33178 (305) 882-8826 Fax: (305) 887-6008			To:			Reaction			
						Job Number: B2500171 Page: 2 Date: 06/05/25 12:51:36			
Project: LAZ CONST.		Block No:	Deliver To:			Account No: 254504030 Designer: / Salesperson: Inside Sales Quote Number: B2500171 P.O. Number:			
Model: 12715 ROLLING RD		Lot No:							
Contact:	Site:	Office:							
Name:									
Phone:									
Fax:	.F.								

Trusscorp International, Inc. 9590 NW 8th Ave Medley, FL 33178 (305) 882-8826 Fax: (305) 887-6008			To: ,	Reaction	
				Job Number: B2500171 Page: 3 Date: 06/05/25 12:52:13	
Project: LAZ CONST.		Block No:	Deliver To:	Account No: 254504030	
Model: 12715 ROLLING RD		Lot No:		Designer: /	
Contact:	Site:	Office:		Salesperson: Inside Sales	
Name:				Quote Number: B2500171	
Phone:				P.O. Number:	
Fax:	.F.				



	Qty:	Truss Id:	Span:	Truss Type:	Slope	Reactions:				
	1	HG2T	28-02-10	HIP GIRDER	4.00	Joint 3 1825.83 -1854.49	Joint 8 517.05 -500.06	Joint 9 898.49 -809.80	Joint 10 3061.34 -3128.12	Joint 14
	1	HG3A	20-00-10	HIP GIRDER	4.00	Joint 3 2524.73 -2620.11	Joint 6 2822.41 -3157.52	Joint 10		
	1	HG3T	20-00-10	HIP GIRDER	4.00	Joint 3 2272.42 -2768.40	Joint 7 2295.36 -2795.76	Joint 14	Joint 15	
	1	HG4T	16-11-10	HIP GIRDER	4.00	Joint 3 2054.57 -2593.87	Joint 7 1722.89 -2108.34	Joint 11		
	1	HG5T	25-00-00	HIP GIRDER	3.00	Joint 3 2812.17 -2791.63	Joint 8 2812.17 -2790.28			
	1	HG6	25-00-00	HALF HIP	3.00	Joint 3 2352.26 -2450.32	Joint 10 2033.44 -2079.13	Joint 16		
	1	HG7	46-01-14	HIP GIRDER	3.00	Joint 3 2377.93 -2458.67	Joint 14 805.34 -971.33	Joint 20 5121.47 -5446.85	Joint 27	Joint 28
	1	HG8	22-05-00	HIP GIRDER	3.00	Joint 3 2527.67 -2438.14	Joint 9 2691.09 -2596.35	Joint 17	Joint 18	
	1	HG9	22-05-00	HIP GIRDER	3.00	Joint 3 2571.64 -2915.50	Joint 10 2674.36 -3026.82	Joint 20	Joint 21	
	16	J1	01-00-00	JACK-OPEN	4.00	Joint 3 531.21 -881.25	Joint 4 202.58 -110.20	Joint 6		
	26	J1A	01-00-00	JACK-OPEN	3.00	Joint 3 550.68 -916.46	Joint 4 241.73 -131.97	Joint 6		
	16	J2	02-00-00	JACK-OPEN	4.00	Joint 2 190.17 -275.70	Joint 3 50.88 -47.76			
	26	J2A	02-00-00	JACK-OPEN	3.00	Joint 2 185.72 -269.05	Joint 3 54.37 -53.13			
	6	J3	03-00-00	JACK-OPEN	4.00	Joint 3 525.28 -820.28	Joint 4 106.35 -184.47	Joint 5 45.70	Joint 6	
	12	J3A	03-00-00	JACK-OPEN	3.00	Joint 3 533.56 -839.43	Joint 4 97.84 -164.85	Joint 5 44.71	Joint 6	
	12	J3AT	03-00-00	JACK-OPEN	3.00	Joint 3 679.09 -984.96	Joint 4 126.04 -193.04	Joint 5 44.71	Joint 6	
	2	J3B	03-00-00	JACK-OPEN	3.00	Joint 3 564.19 -809.76	Joint 4 121.59 -184.41	Joint 5 45.08	Joint 7	
	9	J3T	03-00-00	JACK-OPEN	4.00	Joint 3 525.27 -820.27	Joint 4 106.34 -184.45	Joint 5 45.70	Joint 6	
	1	J3TA	03-00-00	JACK-OPEN	4.00	Joint 3 397.75 -605.05	Joint 4 108.68 -186.64	Joint 5 47.94	Joint 7	
	9	J5	05-00-00	JACK-OPEN	4.00	Joint 3 625.98 -943.28	Joint 4 207.30 -406.33	Joint 5 83.29 -11.73	Joint 6	

Trusscorp International, Inc. 9590 NW 8th Ave Medley, FL 33178 (305) 882-8826 Fax: (305) 887-6008			To:			Reaction					
						Job Number: B2500171 Page: 4 Date: 06/05/25 12:52:50					
Project: LAZ CONST.		Block No:		Deliver To:			Account No: 254504030 Designer: / Salesperson: Inside Sales Quote Number: B2500171 P.O. Number:				
Model: 12715 ROLLING RD		Lot No:									
Contact:	Site:	Office:									
Name:											
Phone:											
Fax:	.F.										

Trusscorp International, Inc. 9590 NW 8th Ave Medley, FL 33178 (305) 882-8826 Fax: (305) 887-6008			To: ,			Reaction				
						Job Number: B2500171 Page: 5 Date: 06/05/25 12:53:28				
Project: LAZ CONST. Model: 12715 ROLLING RD		Block No: Lot No:	Deliver To:			Account No: 254504030 Designer: / Salesperson: Inside Sales Quote Number: B2500171 P.O. Number:				
Contact:	Site:	Office:								
Name:										
Phone:										
Fax:	.F.									
	Qty:	Truss Id:	Span:	Truss Type:	Slope	Reactions:				
	1	T13	25-00-00	COMMON	3.00	Joint 3 1654.05 -1275.18	Joint 8 1496.31 -1133.07	Joint 16	Joint 17	
	5	T13A	25-00-00	COMMON	3.00	Joint 3 1660.38 -1285.18	Joint 8 1323.11 -972.23	Joint 13		
	3	T14	07-00-00	ROOF SPECIAL	4.00	Joint 1 376.98 -496.53	Joint 5 400.58 -683.63			
	3	T17	21-04-00	COMMON	3.00	Joint 3 929.69 -733.14	Joint 7 553.88 -381.95	Joint 10 1517.58 -1239.43	Joint 13	Joint 14
	7	T18	15-06-06	COMMON	3.00	Joint 3 1147.51 -1068.23	Joint 7 849.21 -842.84	Joint 10		
	1	T19	22-05-00	ROOF SPECIAL	3.00	Joint 2 1224.12 -1005.49	Joint 8 1595.46 -1266.01	Joint 14		
	10	T19A	21-09-00	ROOF SPECIAL	3.00	Joint 1 1207.87 -917.97	Joint 7 1191.40 -931.47			
	1	T2	21-04-00	COMMON	4.00	Joint 3 1456.56 -1185.08	Joint 7 1281.50 -1021.54	Joint 14	Joint 15	
	1	T20	11-06-00	COMMON	3.00	Joint 1 632.50 -797.31	Joint 3 632.50 -797.31			
	1	T21	21-09-00	COMMON	3.00	Joint 1 1177.63 -916.70	Joint 6 1214.87 -951.50			
	1	T22	22-05-00	COMMON	3.00	Joint 3 1427.24 -1419.86	Joint 7 1609.07 -1626.48	Joint 14	Joint 15	
	8	T23	22-05-00	ROOF SPECIAL	3.00	Joint 3 1550.17 -1576.70	Joint 7 1617.91 -1642.47	Joint 13	Joint 14	
	6	T3	21-04-00	COMMON	4.00	Joint 3 1459.84 -1192.68	Joint 7 1165.72 -912.25	Joint 11		
	1	T4	21-04-00	COMMON	4.00	Joint 3 1443.40 -1140.52	Joint 9 1175.50 -987.72	Joint 12		
	1	T4A	21-04-00	COMMON	4.00	Joint 3 1037.19 -816.62	Joint 10 85.27 -319.61	Joint 11 1751.91 -1396.88	Joint 14	
	1	T5T	28-01-08	COMMON	4.00	Joint 3 976.50 -732.01	Joint 13 1267.46 -1055.96	Joint 14 1467.02 -908.33	Joint 18	Joint 20
	1	T6T	28-01-08	COMMON	4.00	Joint 3 962.06 -685.29	Joint 13 1463.13 -1225.85	Joint 14 1447.14 -910.14	Joint 17	Joint 19
	9	T7	20-00-10	COMMON	4.00	Joint 3 1375.33 -1148.49	Joint 7 1388.18 -1158.50	Joint 13	Joint 14	
	1	T7A	20-00-10	COMMON	4.00	Joint 3 1388.84 -1164.10	Joint 7 1154.85 -979.85	Joint 12		
	1	T7B	20-00-10	COMMON	4.00	Joint 3 1389.80 -1168.35	Joint 7 1094.82 -883.93	Joint 11		

Trusscorp International, Inc. 9590 NW 8th Ave Medley, FL 33178 (305) 882-8826 Fax: (305) 887-6008			To: ,			Reaction				
Project: LAZ CONST. Block No: Model: 12715 ROLLING RD Lot No:						Job Number: B2500171 Page: 6 Date: 06/05/25 12:54:04				
Contact:	Site:	Office:	Deliver To:			Account No: 254504030 Designer: / Salesperson: Inside Sales Quote Number: B2500171 P.O. Number:				
Name:										
Phone:										
Fax:	.F.									
	Qty:	Truss Id:	Span:	Truss Type:	Slope	Reactions:				
	6	T8	20-00-10	ROOF SPECIAL	4.00	Joint 3 1381.76 -1146.90	Joint 11 1381.76 -1146.90			
	1	T9T	16-11-10	COMMON	4.00	Joint 3 1297.01 -1461.82	Joint 7 975.89 -1069.33	Joint 10		
	1	V10	10-00-00	VALLEY	4.00	Joint 1 198.96 -155.93	Joint 6 28.68 -48.78	Joint 7 134.78 -145.60	Joint 8 116.76 -179.59	Joint 9 509.09 -733.27
	1	V10A	10-00-00	VALLEY	3.00	Joint 1 207.57 -175.11	Joint 4 160.29 -239.91	Joint 5 585.79 -721.00		
	1	V12	12-00-00	VALLEY	3.00	Joint 1 233.65 -269.54	Joint 3 233.65 -269.54	Joint 4 611.75 -739.36		
	1	V12C	12-00-00	VALLEY	2.97	Joint 1 233.01 -268.53	Joint 3 233.01 -268.53	Joint 4 610.51 -737.92		
	1	V16	16-00-00	VALLEY	3.00	Joint 1 330.68 -327.27	Joint 3 330.68 -327.27	Joint 4 865.90 -856.96		
	1	V16C	16-00-00	VALLEY	2.97	Joint 1 330.00 -326.50	Joint 3 330.00 -326.50	Joint 4 864.75 -856.72		
	4	V2	02-00-00	VALLEY	0.00	Joint 1 21.88	Joint 2 21.88			
	1	V20	20-00-00	VALLEY	3.00	Joint 1 205.84 -175.78	Joint 5 205.84 -175.77	Joint 6 589.55 -498.21	Joint 8 359.33 -278.47	Joint 9 589.55 -498.21
	1	V20C	20-00-00	VALLEY	2.97	Joint 1 205.31 -175.39	Joint 5 205.23 -175.32	Joint 6 588.61 -496.91	Joint 8 359.83 -280.20	Joint 9 588.64 -496.92
	1	V2A	02-00-00	GABLE	0.00	Joint 1 21.67	Joint 2 21.67			
	2	V4	04-00-00	GABLE	0.00	Joint 1 43.33	Joint 2 43.33			
	4	V4A	04-00-00	VALLEY	4.00	Joint 1 163.38 -204.94	Joint 3 185.75 -263.56			
	1	V4B	04-00-00	VALLEY	3.00	Joint 1 151.99 -196.69	Joint 3 163.36 -226.48			
	1	V4C	04-00-00	VALLEY	0.00	Joint 1 42.96	Joint 2 42.96			
	3	V6	06-00-00	VALLEY	4.00	Joint 1 272.55 -334.22	Joint 3 304.68 -430.16			
	1	V6A	06-00-00	VALLEY	3.00	Joint 1 260.48 -334.71	Joint 3 279.64 -385.57			
	1	V7	06-08-00	VALLEY	4.00	Joint 1 151.04 -125.27	Joint 4 73.49 -103.35	Joint 5 435.60 -610.93		
	2	V8	08-00-00	VALLEY	3.00	Joint 1 309.69 -405.65	Joint 3 309.69 -405.65			

Trusscorp International, Inc. 9590 NW 8th Ave Medley, FL 33178 (305) 882-8826 Fax: (305) 887-6008			To:			Reaction		
Project: LAZ CONST. Block No: Model: 12715 ROLLING RD Lot No:						Job Number: B2500171 Page: 7 Date: 06/05/25 12:54:43		
Contact:	Site:	Office:	Deliver To:			Account No: 254504030		
Name:						Designer: /		
Phone:						Salesperson: Inside Sales		
Fax:	.F.					Quote Number: B2500171		
						P.O. Number:		

	Qty:	Truss Id:	Span:	Truss Type:	Slope	Reactions:
	1	V8A	08-00-00	VALLEY	3.00	Joint 1 Joint 4 Joint 5 159.93 113.02 468.78 -152.40 -152.95 -633.81
	1	V8B	08-00-00	VALLEY	4.00	Joint 1 Joint 5 Joint 6 Joint 7 153.24 59.98 148.31 421.65 -112.29 -86.28 -207.88 -621.07
	1	V8C	08-00-09	VALLEY	2.97	Joint 1 Joint 3 311.03 311.03 -404.99 -404.99

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	CJ5	Diagonal Hip Girder	2	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:41:43 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-t6BxAG7q8ykQY4YpnTIBYkvUFct4R76mdr91C8z9LOs




Plate Offsets (X,Y)-- [8:0-3-0,0-2-12], [10:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.49		Vert(LL)	0.03	9	>999	360	MT20
TCDL 15.0	Lumber DOL	1.33	BC 0.47		Vert(CT)	-0.03	8-9	>999	180	244/190
BCLL 0.0	Rep Stress Incr	NO	WB 0.29		Horz(CT)	-0.01	8	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP							Weight: 43 lb FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1	TOP CHORD
BOT CHORD 2x4 SP No.2	Structural wood sheathing directly applied or 5-6-9 oc purlins, except end verticals.
WEBS 2x4 SP No.3	BOT CHORD
OTHERS 2x4 SP No.3	Rigid ceiling directly applied or 5-8-2 oc bracing.
	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=827/0-10-15 (min. 0-1-8), 8=292/Mechanical, 10=0/Mechanical
Max Horz 3=627(LC 1), 10=987(LC 4)
Max Uplift3=-1408(LC 4), 8=-555(LC 4)
Max Grav 3=1056(LC 21), 8=397(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-951/644, 2-14=-937/709, 2-3=-945/723, 3-4=-613/734, 5-8=-147/259
BOT CHORD 3-16=-909/648, 9-16=-909/648, 9-17=-909/648, 8-17=-909/648
WEBS 4-8=-681/955, 1-10=-627/987

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Corner(3) -4-4-5 to 0-0-0, Exterior(2R) 0-0-0 to 6-11-6; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1408 lb uplift at joint 3 and 555 lb uplift at joint 8.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 379 lb down and 300 lb up at -1-3-15, 379 lb down and 300 lb up at -1-3-15, and 333 lb down and 224 lb up at 4-4-0, and 333 lb down and 224 lb up at 4-4-0 on top chord, and 125 lb down and 136 lb up at 1-6-1, 125 lb down and 136 lb up at 1-6-1, and 11 lb down and 4 lb up at 4-4-0, and 11 lb down and 4 lb up at 4-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33
Uniform Loads (plf)
Vert: 1-5=-90, 5-6=-30, 7-11=-20
Concentrated Loads (lb)
Vert: 14=-102(F=-51, B=-51) 16=116(F=58, B=58) 17=7(F=4, B=4)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.																																				
12715	CJ5A	DIAGONAL HIP GIRDER	4	1	Job Reference (optional)																																				
Trusscorp Int., 9590 NW 89 AVE, Medley, FL																																									
8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:41:45 2025 Page 1 ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-pVJhbx94gZ_8oOiCuuLfd9_oCPZ6v0j359e8H1z9LOq																																									
Scale = 1:21.5																																									
The diagram shows a side elevation of a truss. The top chord consists of members 1 through 12. The bottom chord consists of members 13 through 15. Vertical hangers are labeled 16 through 21. Diagonal bracing is shown between members 1-2, 2-3, 3-4, 4-5, 5-6, 6-7, 7-8, 8-9, 9-10, 10-11, and 11-12. Plate offsets are indicated at various joints. Dimensions include vertical heights of 1.8'-11" and 0.4'-11", and horizontal spans of 4'-2"-15", 3'-5"-2", 6'-11"-6", and 3'-6"-4".																																									
Plate Offsets (X,Y)-- [10:0-2-0,0-1-4]																																									
<table><tr><td>LOADING (psf)</td><td>SPACING-</td><td>CSI.</td><td>DEFL.</td><td>PLATES</td><td>GRIP</td></tr><tr><td>TCLL 30.0</td><td>2-0-0</td><td>TC 0.53</td><td>in (loc) l/defl L/d</td><td>MT20</td><td>244/190</td></tr><tr><td>TCDL 15.0</td><td>Plate Grip DOL 1.33</td><td>BC 0.50</td><td>Vert(LL) 0.04 9 >999 360</td><td></td><td></td></tr><tr><td>BCLL 0.0</td><td>Lumber DOL 1.33</td><td>WB 0.35</td><td>Vert(CT) 0.04 9 >999 180</td><td></td><td></td></tr><tr><td>BCDL 10.0</td><td>Rep Stress Incr NO</td><td>Matrix-MP</td><td>Horz(CT) -0.01 8 n/a n/a</td><td></td><td></td></tr><tr><td></td><td>Code FBC2020/TPI2014</td><td></td><td></td><td>Weight: 42 lb</td><td>FT = 0%</td></tr></table>						LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP	TCLL 30.0	2-0-0	TC 0.53	in (loc) l/defl L/d	MT20	244/190	TCDL 15.0	Plate Grip DOL 1.33	BC 0.50	Vert(LL) 0.04 9 >999 360			BCLL 0.0	Lumber DOL 1.33	WB 0.35	Vert(CT) 0.04 9 >999 180			BCDL 10.0	Rep Stress Incr NO	Matrix-MP	Horz(CT) -0.01 8 n/a n/a				Code FBC2020/TPI2014			Weight: 42 lb	FT = 0%
LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP																																				
TCLL 30.0	2-0-0	TC 0.53	in (loc) l/defl L/d	MT20	244/190																																				
TCDL 15.0	Plate Grip DOL 1.33	BC 0.50	Vert(LL) 0.04 9 >999 360																																						
BCLL 0.0	Lumber DOL 1.33	WB 0.35	Vert(CT) 0.04 9 >999 180																																						
BCDL 10.0	Rep Stress Incr NO	Matrix-MP	Horz(CT) -0.01 8 n/a n/a																																						
	Code FBC2020/TPI2014			Weight: 42 lb	FT = 0%																																				
<table><tr><td>LUMBER-</td><td>BRACING-</td></tr><tr><td>TOP CHORD 2x4 SP No.1</td><td>TOP CHORD Structural wood sheathing directly applied or 4-11-10 oc purlins, except end verticals.</td></tr><tr><td>BOT CHORD 2x4 SP No.2</td><td>BOT CHORD Rigid ceiling directly applied or 5-3-7 oc bracing.</td></tr><tr><td>WEBS 2x4 SP No.3</td><td>MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.</td></tr><tr><td>OTHERS 2x4 SP No.3</td><td></td></tr></table>						LUMBER-	BRACING-	TOP CHORD 2x4 SP No.1	TOP CHORD Structural wood sheathing directly applied or 4-11-10 oc purlins, except end verticals.	BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 5-3-7 oc bracing.	WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.	OTHERS 2x4 SP No.3																											
LUMBER-	BRACING-																																								
TOP CHORD 2x4 SP No.1	TOP CHORD Structural wood sheathing directly applied or 4-11-10 oc purlins, except end verticals.																																								
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 5-3-7 oc bracing.																																								
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.																																								
OTHERS 2x4 SP No.3																																									
REACTIONS. (lb/size) 8=284/Mechanical, 3=811/0-10-15 (min. 0-1-8), 10=-0/Mechanical Max Horz 3=-829(LC 4), 10=1177(LC 4) Max Uplift 8=-535(LC 4), 3=-1460(LC 4) Max Grav 8=400(LC 21), 3=1107(LC 21)																																									
FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-14=-1151/775, 2-14=-1140/823, 2-3=-1148/835, 3-4=-786/921, 5-8=-154/266 BOT CHORD 3-16=-1050/812, 9-16=-1050/812, 9-17=-1050/812, 8-17=-1050/812 WEBS 4-8=-836/1082, 1-10=-764/1178																																									
NOTES- (10-11) 1) Unbalanced roof live loads have been considered for this design. 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Corner(3) -4-4-2 to 0-0-0, Exterior(2R) 0-0-0 to 6-11-6; Lumber DOL=1.60 plate grip DOL=1.60 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 5) Refer to girder(s) for truss to truss connections. 6) Refer to girder(s) for truss to truss connections. 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 535 lb uplift at joint 8 and 1460 lb uplift at joint 3. 8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 375 lb down and 295 lb up at -1-3-15, 375 lb down and 295 lb up at -1-3-15, and 327 lb down and 210 lb up at 4-4-0, and 327 lb down and 210 lb up at 4-4-0 on top chord, and 152 lb down and 155 lb up at 1-6-1, 152 lb down and 155 lb up at 1-6-1, and 13 lb down and 4 lb up at 4-4-0, and 13 lb down and 4 lb up at 4-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others. 9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B). 10) All truss to truss connection by TCI are on the Truss Placement plan. 11) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826																																									
LOAD CASE(S) Standard 1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33 Uniform Loads (plf) Vert: 1-5=-90, 5-6=-30, 7-11=-20 Concentrated Loads (lb) Vert: 14=-92(F=-46, B=-46) 16=128(F=64, B=64) 17=8(F=4, B=4)																																									

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	CJ5AT	DIAGONAL HIP GIRDER	5	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:41:47 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-luRS0dALCAEs1isa0JN7ia47EDCHNvAMYT7FLvz9LOo




Plate Offsets (X,Y)-- [3:0-4-11,0-1-2], [8:0-3-0,0-2-12], [10:0-2-0,0-1-4]					
LOADING (psf)	SPACING-	2-0-0	CSI.	in	(loc)
TCLL	Plate Grip DOL	1.33	TC	0.04	8-9
TCDL	Lumber DOL	1.33	BC	0.04	9
BCLL	Rep Stress Incr	NO	WB	-0.01	8
BCDL	Code FBC2020/TPI2014		Matrix-MP		
				L/defl	L/d
				>999	360
				>999	180
				n/a	n/a
				Weight: 42 lb FT = 0%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.1	TOP CHORD	Structural wood sheathing directly applied or 4-4-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied or 4-10-7 oc bracing.
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3		
		MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.	

REACTIONS. (lb/size) 8=284/Mechanical, 3=811/0-10-15 (min. 0-1-9), 10=-0/Mechanical
Max Horz 3=-997(LC 4), 10=1401(LC 4)
Max Uplift 8=-618(LC 4), 3=-1693(LC 4)
Max Grav 8=484(LC 21), 3=1340(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-1369/923, 2-14=-1359/945, 2-3=-1368/954, 3-4=-898/1030, 5-8=-197/311
BOT CHORD 3-16=-1179/944, 9-16=-1179/944, 9-17=-1179/944, 8-17=-1179/944
WEBS 4-8=-972/1215, 1-10=-935/1402

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Corner(3) -4-4-2 to 0-0-0, Exterior(2R) 0-0-0 to 6-11-6; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 618 lb uplift at joint 8 and 1693 lb uplift at joint 3.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 416 lb down and 336 lb up at -1-3-15, 416 lb down and 336 lb up at -1-3-15, and 387 lb down and 271 lb up at 4-4-0, and 387 lb down and 271 lb up at 4-4-0 on top chord, and 152 lb down and 155 lb up at 1-6-1, 152 lb down and 155 lb up at 1-6-1, and 14 lb down and 4 lb up at 4-4-0, and 14 lb down and 4 lb up at 4-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33
Uniform Loads (plf)
Vert: 1-5=-90, 5-6=-30, 7-11=-20
Concentrated Loads (lb)
Vert: 14=-92(F=-46, B=-46) 16=128(F=64, B=64) 17=8(F=4, B=4)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	CJ5C	DIAGONAL HIP GIRDER	2	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:41:49 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-hGZCRJCbkoVaG?0z7kPbn?9RP0z4rrse0ncMQoz9LOm




Plate Offsets (X,Y)-- [3:0-10-3,Edge], [5:0-2-11,1-5-2], [10:0-2-0,0-1-4]

LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 1.33	TC 0.77	Vert(LL) 0.11 9-13 >751 360	MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.30	Vert(CT) -0.11 9-13 >753 180		
BCLL 0.0	Rep Stress Incr NO	WB 0.28	Horz(CT) -0.04 8 n/a n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MP		Weight: 46 lb	FT = 0%

LUMBER-
TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
 B2: 2x4 SP No.3
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-2-6 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 4-8.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 8=270/Mechanical, 3=824/0-10-15 (min. 0-1-10), 10=-0/Mechanical
Max Horz 3=694(LC 13), 10=931(LC 20)
Max Uplift8=-561(LC 4), 3=-1750(LC 4)
Max Grav8=444(LC 21), 3=1387(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-913/705, 2-14=-887/753, 2-3=-890/762, 5-8=-421/572
WEBS 1-10=-694/931

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Corner(3) -4-4-3 to 0-0-0, Exterior(2R) 0-0-0 to 6-11-6; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 561 lb uplift at joint 8 and 1750 lb uplift at joint 3.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 416 lb down and 336 lb up at -1-3-15, 416 lb down and 336 lb up at -1-3-15, and 384 lb down and 265 lb up at 4-4-0, and 387 lb down and 271 lb up at 4-4-0 on top chord, and 152 lb down and 155 lb up at 1-6-1, 152 lb down and 155 lb up at 1-6-1, and 20 lb down and 6 lb up at 4-4-0, and 14 lb down and 4 lb up at 4-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

- Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33
Uniform Loads (plf)
Vert: 1-4=-90, 4-5=-90, 5-6=-30, 9-11=-20, 4-7=-20
Concentrated Loads (lb)
Vert: 13=128(F=64, B=64) 14=-92(F=-46, B=-46) 16=10(F=4, B=6)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	CJ5T	DIAGONAL HIP GIRDER	4	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:41:51 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-efgzs?DrGPIHWJALF9S3sQErWqcJJkqxT55Sugz9LOk




Plate Offsets (X,Y)-- [8:0-3-0,0-2-12], [10:0-2-0,0-1-4]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.47		Vert(LL)	0.03	9	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.51		Vert(CT)	-0.03	8-9	>999	180		
BCLL 0.0	Rep Stress Incr	NO	WB 0.37		Horz(CT)	-0.01	8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP							Weight: 39 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 5-1-11 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=695/0-10-15 (min. 0-1-8), 8=313/Mechanical, 10=0/Mechanical
Max Horz 3=480(LC 1), 10=729(LC 4)
Max Uplift3=-1347(LC 4), 8=-679(LC 4)
Max Grav 3=1108(LC 21), 8=509(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-14=-699/512, 2-14=-689/540, 2-3=-697/555, 3-15=-817/983, 4-15=-805/989, 5-8=-184/294
BOT CHORD 3-17=-1196/882, 9-17=-1196/882, 9-18=-1196/882, 8-18=-1196/882
WEBS 4-8=-927/1257, 1-10=-526/730

- NOTES-** (9-10)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Corner(3) -3-1-6 to 1-1-8, Exterior(2R) 1-1-8 to 6-11-6; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1347 lb uplift at joint 3 and 679 lb uplift at joint 8.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 418 lb down and 341 lb up at -1-3-15, 418 lb down and 341 lb up at -1-3-15, and 376 lb down and 267 lb up at 4-4-0, and 374 lb down and 265 lb up at 4-4-0 on top chord, and 125 lb down and 136 lb up at 1-6-1, 125 lb down and 136 lb up at 1-6-1, and 11 lb down and 3 lb up at 4-4-0, and 11 lb down and 4 lb up at 4-4-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33

Uniform Loads (plf)

Vert: 1-5=-90, 5-6=-30, 7-11=-20

Concentrated Loads (lb)

Vert: 14=-102(F=-51, B=-51) 17=116(F=58, B=58) 18=7(F=4, B=3)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	CJ7	Diagonal Hip Girder	1	1	Job Reference (optional)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	CJ7B	Diagonal Hip Girder	2	2	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL 8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:41:56 2025 Page 1
ID: GLN6EJBZ1GCD23RDL tAxzKvJz- cUsviH 4xNac42J1iEZUyf rLm 1NgdNpDauz9LOf




Plate Offsets (X,Y)-- [1:0-8,4,0-3-11], [3:0-2-15,0-0-1], [4:0-2-14,0-0-7], [5:0-1-12,0-1-8], [10:0-2-0,0-1-0]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP		
TCLL	30.0	Plate Grip DOL	1.33	TC	0.68	Vert(LL)	0.20	4-8	>577	360	MT20	244/190
TCDL	15.0	Lumber DOL	1.33	BC	0.36	Vert(CT)	-0.18	4-8	>611	180		
BCLL	0.0	Rep Stress Incr	NO	WB	0.16	Horz(CT)	-0.05	8	n/a	n/a		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-MSH							Weight: 113 lb FT = 0%	

LUMBER-		BRACING-	
TOP CHORD	2x6 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2 *Except*		
	B2: 2x4 SP No.3	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3		

REACTIONS. (lb/size) 8=508/Mechanical, 3=1005/0-10-9 (min. 0-1-8), 10=0/Mechanical
 Max Horz 3=-696(LC 20), 10=1089(LC 20)
 Max Uplift 8=-663(LC 4), 3=-1605(LC 4)
 Max Grav 8=531(LC 21), 3=1285(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-14=-1068/645, 2-14=-939/559, 2-3=-943/563, 3-4=-259/108, 4-15=-407/400, 5-15=-355/393, 5-8=-409/599
BOT CHORD	4-16=-502/418, 8-16=-503/416
WEBS	1-10=-649/1089

NOTES- (11-12)

- 1) Special connection required to distribute bottom chord loads equally between all plies.
- 2) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows:
Top chords connected as follows: 2x6 - 3 rows staggered at 0-2-0 oc clinched, 2x4 - 1 row at 0-9-0 oc clinched.
Bottom chords connected as follows: 2x4 - 2 rows staggered at 0-2-0 oc clinched, Except member 4-7 2x4 - 2 rows staggered at 0-2-0 oc clinched.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc clinched.
- 3) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- 4) Unbalanced roof live loads have been considered for this design.
- 5) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TC DL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Corner(3) -4-3-7 to 0-0-0, Exterior(2R) 0-0-0 to 9-7-13; Lumber DOL=1.60 plate grip DOL=1.60
- 6) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) Refer to girder(s) for truss to truss connections.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 663 lb uplift at joint 8 and 1605 lb uplift at joint 3.
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 353 lb down and 283 lb up at -1-3-14, 353 lb down and 283 lb up at -1-3-14, 300 lb down and 198 lb up at 4-4-0, 300 lb down and 198 lb up at 4-4-0, and 391 lb down and 357 lb up at 6-10-15, and 406 lb down and 372 lb up at 7-1-15 on top chord, and 152 lb down and 155 lb up at 1-6-1, 152 lb down and 155 lb up at 1-6-1, 13 lb down and 4 lb up at 4-1-11, 13 lb down and 4 lb up at 4-1-11, and 10 lb down at 6-10-15, and 5 lb down at 7-1-15 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 11) All truss to truss connection by TCI are on the Truss Placement plan.
- 12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33
Uniform Loads (plf)
Vert: 1-4=-90, 4-5=-90, 5-6=-30, 9-11=-20, 4-7=-20

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	CJ7B	Diagonal Hip Girder	2	2	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:41:56 2025 Page 2
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-_cUsviH_4xNac42J1i1EZUyf_rLm_1NgdNpDAuz9LOf

LOAD CASE(S) Standard
Concentrated Loads (lb)
Vert: 9=8(F=4, B=4) 13=128(F=64, B=64) 14=-92(F=-46, B=-46) 15=-127(F=-55, B=-71)

[illegible]

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H1	Hip	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:00 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-tOjMl4KU8At05hM4GY6AkK6JuSduwrlGY?nRJfz9LOb




Plate Offsets (X,Y)-- [4:0-3-4,0-2-0], [6:0-3-4,0-2-0], [13:0-2-0,0-1-0], [14:0-2-0,0-0-8]					
LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 30.0	2-0-0	TC 0.75	in (loc) l/defl L/d	MT20	244/190
TCDL 15.0	Plate Grip DOL 1.33	BC 0.67	Vert(LL) 0.20 10-12 >999 360		
BCLL 0.0	Lumber DOL 1.33	WB 0.17	Vert(CT) -0.30 10-12 >856 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS	Horz(CT) 0.08 7 n/a n/a		
	Code FBC2020/TPI2014			Weight: 104 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 *Except*	TOP CHORD Structural wood sheathing directly applied.
T2: 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
BOT CHORD 2x4 SP No.2	
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=1445/0-8-0 (min. 0-1-11), 13=-0/Mechanical, 14=-0/Mechanical, 7=1459/0-8-0 (min. 0-1-12)
Max Horz 3=240(LC 9), 13=281(LC 4), 14=-147(LC 4)
Max Uplift 3=-1326(LC 4), 7=-1338(LC 4)
Max Grav 3=1445(LC 1), 7=1459(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-261/256, 2-3=-258/272, 3-21=-2350/2032, 4-21=-2239/2052, 4-5=-2139/2058, 5-6=-2103/2027, 6-22=-2200/2022, 7-22=-2316/2003
BOT CHORD 3-12=-1823/2161, 11-12=-2055/2365, 10-11=-2055/2365, 7-10=-1792/2124
WEBS 4-12=-91/359, 5-12=-397/280, 5-10=-435/318, 6-10=-98/366, 1-13=-194/281

- NOTES-** (9-10)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 2-9-1, Exterior(2R) 2-9-1 to 18-6-15, Interior(1) 18-6-15 to 21-4-0, Exterior(2E) 21-4-0 to 24-5-3; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1326 lb uplift at joint 3 and 1338 lb uplift at joint 7.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H1T	HIP	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:02 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-pmr7AIMlgn7jK?VT Oy8epIBb?GHsOkOZ?IGYNYz9LOZ




Plate Offsets (X,Y)-- [1:0-2-0,0-0-13], [3:0-0-3,0-0-14], [6:0-3-0,0-2-4], [7:0-5-10,0-0-9], [9:0-2-0,0-0-13], [13:0-2-0,0-1-0], [14:0-2-0,0-0-8]					
LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 30.0	2-0-0	TC 0.97	in (loc) l/defl L/d	MT20	244/190
TCDL 15.0	Plate Grip DOL 1.33	BC 0.83	Vert(LL) 0.39 10-12 >662 360	MT20HS	187/143
BCLL 0.0	Lumber DOL 1.33	WB 0.19	Vert(CT) -0.45 10-12 >575 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS	Horz(CT) 0.09 7 n/a n/a		
	Code FBC2020/TPI2014			Weight: 99 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1 *Except*	TOP CHORD Structural wood sheathing directly applied.
T2: 2x4 SP No.2, T3: 2x4 SP 2400F 2.0E	BOT CHORD Rigid ceiling directly applied.
BOT CHORD 2x4 SP No.2	
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

REACTIONS. (lb/size) 3=1422/0-8-0 (min. 0-1-12), 13=0/Mechanical, 14=0/Mechanical, 7=1449/0-8-0 (min. 0-1-13)
Max Horz 3=-450(LC 4), 13=335(LC 4), 14=-258(LC 9)
Max Uplift 3=-1686(LC 4), 7=-1717(LC 4)
Max Grav 3=1500(LC 5), 7=1528(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-318/223, 2-3=-319/236, 3-21=-3002/3265, 4-21=-2973/3279, 4-5=-2949/3287, 5-6=-2860/3187, 6-22=-2885/3183, 7-22=-2916/3169
BOT CHORD 3-12=-2814/2553, 11-12=-3212/2834, 10-11=-3212/2834, 7-10=-2712/2463
WEBS 4-12=-134/356, 5-12=-485/444, 5-10=-565/557, 6-10=-158/372, 1-13=-193/336, 9-14=-115/259

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -2-10-15 to 0-0-0, Interior(1) 0-0-0 to 2-9-1, Exterior(2R) 2-9-1 to 18-6-15, Interior(1) 18-6-15 to 21-2-15, Exterior(2E) 21-2-15 to 24-2-15; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1686 lb uplift at joint 3 and 1717 lb uplift at joint 7.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

[illegible]


[illegible]

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H3T	HIP	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:07 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-Ake0DTQtVKm0RmOQBWkpWovXMH0e3ynI9azJ3lz9LOU



Scale = 1:58.4




Plate Offsets (X,Y)-- [5:0-5-4,0-2-8], [9:0-3-7,0-0-14], [11:Edge,0-1-8], [13:0-5-0,0-2-12]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.33	TC	0.67	Vert(LL)	-0.11 15-22	>999	360
TCDL	15.0	Lumber DOL	1.33	BC	0.66	Vert(CT)	-0.23 15-22	>825	180
BCLL	0.0	Rep Stress Incr	YES	WB	0.44	Horz(CT)	0.03 13	n/a	n/a
BCDL	10.0	Code FBC2020/TPI2014		Matrix-AS					
Weight: 139 lb									FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3	BRACING- TOP CHORD Structural wood sheathing directly applied. BOT CHORD Rigid ceiling directly applied. WEBS 1 Row at midpt 5-13
MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.	

REACTIONS. All bearings 0-8-0 except (jt=length) 16=Mechanical, 18=Mechanical.

(lb) - Max Horz 3=437(LC 1), 16=393(LC 4), 18=172(LC 1)

Max Uplift All uplift 100 lb or less at joint(s) except 3=916(LC 4), 13=991(LC 4), 12=637(LC 4), 9=388(LC 4)

Max Grav All reactions 250 lb or less at joint(s) except 3=1113(LC 1), 13=1325(LC 9), 12=734(LC 10), 9=548(LC 10)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-365/322, 2-3=-365/339, 3-4=-1622/1315, 4-26=-1093/862, 5-26=-1034/876, 5-27=-20/298, 27-28=-20/298, 6-28=-20/298, 6-7=-20/298, 8-29=-257/316, 29-30=-270/258, 9-30=-272/228

BOT CHORD 3-15=-1013/1303, 14-15=-480/822, 13-14=-480/822, 12-13=-394/504, 9-12=-394/504

WEBS 4-15=-524/563, 5-15=-69/399, 5-13=-1350/1043, 6-13=-614/646, 8-12=-590/672, 1-17=-265/394, 16-17=-265/393

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 4-9-1, Exterior(2R) 4-9-1 to 13-2-15, Interior(1) 13-2-15 to 14-10-9, Exterior(2R) 14-10-9 to 23-4-7, Interior(1) 23-4-7 to 27-3-3, Exterior(2E) 27-3-3 to 30-3-3; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 916 lb uplift at joint 3, 991 lb uplift at joint 13, 637 lb uplift at joint 12 and 388 lb uplift at joint 9.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type		Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H4	Hip		1	1	Job Reference (optional)
Trusscorp Int., 9590 NW 89 AVE, Medley, FL						8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:09 2025 Page 1
ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-66mme9R80x0kg4YplxmHbD_rg4gpXoubcuSP7ez9LOS						Los Angeles, CA
The diagram shows a hip truss with various members labeled with numbers and sizes. Key dimensions include a total width of 21'-4", a peak height of 11'-11", and a depth of 4'-2-1". Members are labeled with sizes like 2x4, 3x4, 4x6, and 4x10. Plate offsets are indicated at the bottom chord joints.						Scale = 1:42.4
Plate Offsets (X,Y)-- [6:0-3-0,0-2-4]						
LOADING (psf) TCLL 30.0 TCDL 15.0 BCCL 0.0 BCDL 10.0						SPACING- 2-0-0 Plate Grip DOL 1.33 Lumber DOL 1.33 Rep Stress Incr YES Code FBC2020/TPI2014
LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3						CSL. TC 0.81 BC 0.81 WB 0.66 Matrix-AS
REACTIONS. (lb/size) 3=1444/0-8-0 (min. 0-1-11), 9=1175/0-8-0 (min. 0-1-8), 13=0/Mechanical Max Horz 3=222(LC 1), 13=317(LC 4) Max Uplift 3=-1220(LC 4), 9=-1081(LC 4) Max Grav 3=1444(LC 1), 9=1175(LC 1)						DEFL. in (loc) l/defl L/d Vert(LL) -0.22 10-12 >999 360 Vert(CT) -0.48 10-12 >528 180 Horz(CT) 0.05 9 n/a n/a
FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-2=-294/282, 2-3=-292/299, 3-18=-2386/1845, 4-18=-2191/1846, 4-5=-2333/2027, 5-6=-1030/1036, 6-19=-1033/1009, 7-19=-1122/1002 BOT CHORD 3-12=-1825/2159, 11-12=-1398/1544, 10-11=-1398/1544 WEBS 4-12=-448/533, 5-12=-605/869, 5-10=-665/637, 6-10=-215/296, 7-10=-1040/1231, 7-9=-1169/1085, 1-14=-222/318, 13-14=-222/317						PLATES MT20 GRIP 244/190 Weight: 112 lb FT = 0%
NOTES- (9-10) 1) Unbalanced roof live loads have been considered for this design. 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 6-9-1, Exterior(2R) 6-9-1 to 18-4-0, Exterior(2E) 18-4-0 to 21-4-0; Lumber DOL=1.60 plate grip DOL=1.60 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 4) Provide adequate drainage to prevent water ponding. 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 6) Refer to girder(s) for truss to truss connections. 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1220 lb uplift at joint 3 and 1081 lb uplift at joint 9. 8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord. 9) All truss to truss connection by TCI are on the Truss Placement plan. 10) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826						BRACING- TOP CHORD Structural wood sheathing directly applied. BOT CHORD Rigid ceiling directly applied. MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
LOAD CASE(S) Standard						

Job

12715

Truss

H4T

Truss Type

HIP

Qty

1

Ply

1

12715 ROLLING ROAD DR, PINECREST, FL.

Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:11 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-2VuW2qTOYYGSvOhBQLplge3B2uO4?mxu3CxCWCWz9LOQ

0-11-12

0-3-11

0-11-12

0-3-11

-3-0-0

3-0-0

7-1-8

7-1-8

11-0-0

3-10-8

17-1-8

6-1-8

21-0-0

3-10-8

28-1-8

7-1-8

31-1-8

3-0-0

Scale = 1:61.4

4x6 =

5

4x6 =

6

4.00 $\sqrt{12}$

2x4 ||

4

2x4 ||

20

2x4 ||

2

2x4 ||

3

17 2x4 ||

15

3x10 =

1027#/-830#

3x4 =

14

3x6 =

13

5x10 =

12

2x4 ||

11

3x4 =

18

2x4 ||

22

3x4 =

10

3x4 =

625#/-519#

1737#/-1414#

451#/-199#

-0-1-8

0-1-8

7-1-8

7-1-8

11-0-0

3-10-8

16-1-6

5-1-6

21-0-0

4-10-10

28-1-8

7-1-8

28-3-0

0-1-8

Plate Offsets (X,Y)-- [3:0-5-0,0-0-8], [5:0-3-0,0-1-12], [6:0-3-0,0-2-4], [8:0-2-7,0-1-14], [12:0-5-0,0-3-0]

LOADING (psf)

TCLL 30.0

TCDL 15.0

BCLL 0.0

BCDL 10.0

SPACING-

2-0-0

Plate Grip DOL 1.33

Lumber DOL 1.33

Rep Stress Incr YES

Code FBC2020/TPI2014

CSI.

TC 0.82

BC 0.63

WB 0.36

Matrix-S

DEFL.

in (loc)

l/defl

L/d

Vert(LL) -0.13 12-14 >999 360

Vert(CT) -0.27 12-14 >704 180

Horz(CT) 0.02 12 n/a n/a

PLATES

GRIP

MT20 244/190

Weight: 143 lb FT = 0%

LUMBER-

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

WEBS 2x4 SP No.3

OTHERS 2x4 SP No.3

BRACING-

TOP CHORD

BOT CHORD

WEBS

Structural wood sheathing directly applied or 4-7-3 oc purlins.

Rigid ceiling directly applied or 6-0-0 oc bracing.

1 Row at midpt 5-12

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS.

All bearings 0-8-0 except (jt=length) 15=Mechanical, 16=Mechanical.

(lb) - Max Horz 3=166(LC 9), 15=293(LC 4), 16=-298(LC 4)

Max Uplift All uplift 100 lb or less at joint(s) except 3=-830(LC 4), 12=-1414(LC 4), 11=-199(LC 4), 8=-519(LC 4)

Max Grav All reactions 250 lb or less at joint(s) except 3=1027(LC 9), 12=1737(LC 1), 11=451(LC 10), 8=625(LC 10)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-272/264, 3-20=-1095/677, 4-20=-878/678, 4-5=-1031/872, 5-6=-445/785, 6-7=-370/695, 7-21=-163/356, 8-21=-187/344, 9-10=-277/259

BOT CHORD 3-14=-708/1045, 13-14=-258/413, 12-13=-258/413

WEBS 4-14=-455/537, 5-14=-637/894, 6-12=-646/633, 7-11=-333/250, 7-12=-431/431, 1-17=-203/293, 15-17=-202/293, 16-18=-196/298, 10-18=-197/299, 5-12=-1266/1110

NOTES- (8-9)

1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to -0-1-3, Interior(1) -0-1-3 to 6-9-1, Exterior(2R) 6-9-1 to 21-4-7, Interior(1) 21-4-7 to 28-2-11, Exterior(2E) 28-2-11 to 31-2-11; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60

3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.

4) Provide adequate drainage to prevent water ponding.

5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

6) Refer to girder(s) for truss to truss connections.

7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 830 lb uplift at joint 3, 1414 lb uplift at joint 12, 199 lb uplift at joint 11 and 519 lb uplift at joint 8.

8) All truss to truss connection by TCI are on the Truss Placement plan.

9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H5T	HIP	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:14 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-S4ZfhsVGrTe1mrQm5UMSIHhg95QAC?WKmAAAorz9LON




Plate Offsets (X,Y)-- [7:0-3-0,0-1-12], [15:0-3-0,0-2-12]

LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	2-0-0	TC 0.96	Vert(LL)	-0.04 18-26	>999	360	MT20	244/190
TCDL 15.0	Plate Grip DOL 1.33	BC 0.61	Vert(CT)	-0.11 18-26	>999	180		
BCLL 0.0	Lumber DOL 1.33	WB 0.89	Horz(CT)	0.02 15	n/a	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS						
	Code FBC2020/TPI2014						Weight: 161 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied. Except:
WEBS 2x4 SP No.3	1 Row at midpt 13-27
OTHERS 2x4 SP No.3	JOINTS 1 Brace at Jt(s): 23
	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=909/0-8-0 (min. 0-1-8), 15=1354/0-8-0 (min. 0-1-10), 14=1262/0-8-0 (min. 0-1-12), 19=0/Mechanical, 20=0/Mechanical
Max Horz 3=-204(LC 10), 19=273(LC 4), 20=-297(LC 4)
Max Uplift3=-703(LC 4), 15=-974(LC 4), 14=-1250(LC 4)
Max Grav3=991(LC 9), 15=1394(LC 9), 14=1487(LC 10)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-253/247, 2-3=-251/263, 3-4=-1091/481, 4-5=-150/278, 5-30=-145/283, 6-30=-139/371, 6-7=-48/298, 7-31=-753/1127, 8-31=-761/992, 8-9=-765/976, 9-10=-1599/1724, 10-11=-283/314
BOT CHORD 3-18=-522/976, 17-18=-522/976, 16-17=-502/614, 15-16=-502/614, 14-15=-1324/1417, 13-14=-1324/1417, 12-13=-1324/1417, 10-12=-1324/1417
WEBS 4-18=0/277, 4-17=-1092/871, 6-17=-423/431, 7-17=-806/1025, 7-15=-1598/1351, 9-15=-618/875, 9-14=-1339/1206, 1-21=-184/274, 19-21=-184/273, 20-22=-234/297, 22-23=-234/297, 11-23=-234/297

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 8-9-1, Exterior(2R) 8-9-1 to 19-4-7, Interior(1) 19-4-7 to 28-1-8, Exterior(2E) 28-1-8 to 31-2-11; cantilever right exposed ; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 703 lb uplift at joint 3, 974 lb uplift at joint 15 and 1250 lb uplift at joint 14.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H6	Hip	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:16 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-PTHP6YXXN5uk09a9CvOwNin_Pv6Ag44dDUfHtkz9LOL




Plate Offsets (X,Y)-- [4:0-6-4,0-2-4], [12:0-2-0,0-1-0], [13:0-2-0,0-0-8]											
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES GRIP	
TCLL	30.0	Plate Grip DOL	1.33	TC	0.97	Vert(LL)	0.17	9-11	>999	360	MT20 244/190
TCDL	15.0	Lumber DOL	1.33	BC	0.64	Vert(CT)	-0.23	9-11	>999	180	MT20HS 187/143
BCLL	0.0	Rep Stress Incr	YES	WB	0.18	Horz(CT)	0.06	6	n/a	n/a	
BCDL	10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 97 lb FT = 0%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied.
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3		

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.


REACTIONS. (lb/size) 3=1376/0-8-0 (min. 0-1-10), 12=-0/Mechanical, 13=-0/Mechanical, 6=1388/0-8-0 (min. 0-1-10)
Max Horz 3=212(LC 9), 12=308(LC 4), 13=-200(LC 4)
Max Uplift 3=-1296(LC 4), 6=-1306(LC 4)
Max Grav 3=1376(LC 1), 6=1388(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-286/265, 2-3=-283/281, 3-20=-2168/1944, 4-20=-2063/1963, 4-5=-1936/1948, 5-21=-2035/1940, 6-21=-2144/1920
BOT CHORD 3-11=-1792/2038, 10-11=-1788/2045, 9-10=-1788/2045, 6-9=-1767/2011
WEBS 1-12=-203/308

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 2-9-1, Exterior(2R) 2-9-1 to 17-3-9, Interior(1) 17-3-9 to 20-0-10, Exterior(2E) 20-0-10 to 23-1-13; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1296 lb uplift at joint 3 and 1306 lb uplift at joint 6.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H7	HIP	1	1	Job Reference (optional)



LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD Structural wood sheathing directly applied or 3-7-8 oc purlins. Rigid ceiling directly applied or 4-1-7 oc bracing. MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
--	---

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-406/331, 2-16=-310/255, 3-16=-310/251, 3-4=-2120/1901, 4-17=-1696/1498, 5-17=-1625/1511, 5-6=-1551/1529, 6-18=-1626/1510, 7-18=-1695/1497, 7-8=-2085/1868, 9-10=-321/256
BOT CHORD	3-13=-1915/2067, 12-13=-1434/1726, 11-12=-1877/2025, 8-11=-1877/2025
WEBS	4-13=-442/509, 7-12=-404/468, 1-14=-275/438, 10-15=-194/347

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H8A	HIP	1	1	Job Reference (optional)


Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:19 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-p2NYkaZPg0GJtcJku1yd?KPa263WtPG3vStxU3z9LOI

-3-0-03-0-04-4-144-4-149-0-04-7-211-0-102-0-1015-7-124-7-220-0-104-4-14

Scale = 1:40.0



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 30.0	2-0-0	TC 0.69	in (loc)	MT20	244/190
TCDL 15.0	Plate Grip DOL 1.33	BC 0.85	Vert(LL) -0.18 8-10 >999 360		
BCLL 0.0	Lumber DOL 1.33	WB 0.28	Vert(CT) -0.40 8-10 >586 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.06 8 n/a n/a		
	Code FBC2020/TPI2014			Weight: 95 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD
Structural wood sheathing directly applied or 3-7-13 oc purlins.
Rigid ceiling directly applied or 4-2-5 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 8=1053/0-8-0 (min. 0-1-8), 3=1388/0-8-0 (min. 0-1-10), 12=-0/Mechanical
Max Horz 3=-376(LC 4), 12=441(LC 4)
Max Uplift 8=-934(LC 4), 3=-1255(LC 4)
Max Grav 8=1053(LC 1), 3=1388(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-410/333, 2-13=-314/257, 3-13=-315/253, 3-4=-2172/1970, 4-14=-1758/1577, 5-14=-1687/1591, 5-6=-1610/1606,
6-15=-1685/1595, 7-15=-1761/1582, 7-16=-2147/2114, 8-16=-2253/2106
BOT CHORD 3-11=-1698/1939, 10-11=-1230/1610, 9-10=-1869/2050, 8-9=-1869/2050
WEBS 4-11=-434/495, 6-10=-146/272, 7-10=-545/678, 1-12=-277/442

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to -0-1-3, Interior(1) -0-1-3 to 4-9-1, Exterior(2R) 4-9-1 to 15-3-9, Interior(1) 15-3-9 to 16-8-10, Exterior(2E) 16-8-10 to 19-8-10; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 934 lb uplift at joint 8 and 1255 lb uplift at joint 3.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H10	Half Hip	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:23 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-ipc3axcwjEnlLEcV7t0Z9AZBAkPlp3Ufq4r9dqz9LOE




Plate Offsets (X,Y)--	[4:0-5-4,0-2-12], [6:0-4-0,0-3-0], [7:Edge,0-1-8], [8:0-3-0,0-3-0], [13:0-2-0,0-1-0]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 1.00	Vert(LL)	0.43 11-12	>702	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.96	Vert(CT)	-0.66 11-12	>450	180	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.90	Horz(CT)	0.14 8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS					Weight: 121 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 *Except* T1: 2x4 SP No.1	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP No.1 *Except* B2: 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 6-8
OTHERS 2x4 SP No.3	

REACTIONS. (lb/size) 8=1356/0-8-0 (min. 0-1-10), 3=1654/0-8-0 (min. 0-1-15), 13=0/Mechanical
Max Horz 3=220(LC 1), 13=299(LC 4)
Max Uplift 8=988(LC 4), 3=1337(LC 4)
Max Grav 8=1356(LC 1), 3=1654(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-285/268, 2-3=-284/281, 3-17=-3676/2722, 4-17=-3589/2737, 4-18=-4409/3258, 5-18=-4409/3258,
5-6=-3238/2310, 7-8=-254/265
BOT CHORD 3-12=-2727/3481, 11-12=-2719/3487, 10-11=-3258/4409, 9-10=-3258/4409, 8-9=-2305/3226
WEBS 4-11=-566/1193, 5-9=-1234/998, 6-9=-233/491, 6-8=-3261/2326, 1-13=-220/300

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ: TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 2-9-1, Exterior(2R) 2-9-1 to 11-2-15, Interior(1) 11-2-15 to 21-10-4, Exterior(2E) 21-10-4 to 24-10-4; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 988 lb uplift at joint 8 and 1337 lb uplift at joint 3.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss Type		Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H10T	HIP	1	1	Job Reference (optional)
Trusscorp Int., 9590 NW 89 AVE, Medley, FL ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-A?ARnHdYUYvczNBhgaYoiO6MK7lqYYlo3jbi9Gz9LOD					
Scale = 1:55.1					
LOADING (psf) SPACING- 2-0-0 CSI. DEFL. in (loc) l/defl L/d PLATES GRIP TCLL 30.0 Plate Grip DOL 1.33 TC 0.98 Vert(LL) 0.53 10-12 >562 360 MT20 244/190 TCDL 15.0 Lumber DOL 1.33 BC 0.91 Vert(CT) -0.62 10-12 >487 180 MT20HS 187/143 BCLL 0.0 Rep Stress Incr YES WB 0.77 Horz(CT) 0.13 7 n/a n/a BCDL 10.0 Code FBC2020/TPI2014 Matrix-AS LUMBER- BRACING- TOP CHORD 2x4 SP 2400F 2.0E *Except* T2: 2x4 SP No.2 TOP CHORD Structural wood sheathing directly applied. BOT CHORD 2x4 SP No.2 *Except* B2: 2x4 SP No.1 BOT CHORD Rigid ceiling directly applied. WEBS 2x4 SP No.3 MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide. OTHERS 2x4 SP No.3					
REACTIONS. (lb/size) 3=1636/0-8-0 (min. 0-2-1), 14=-0/Mechanical, 15=0/Mechanical, 7=1668/0-8-0 (min. 0-2-1) Max Horz 3=612(LC 9), 14=355(LC 4), 15=-417(LC 9) Max Uplift3=-1821(LC 4), 7=-1855(LC 4) Max Grav3=1726(LC 5), 7=1759(LC 5)					
FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-2=-338/244, 2-3=-337/256, 3-22=-3733/3769, 4-22=-3703/3783, 4-23=-3666/3775, 5-23=-3666/3775, 5-24=-3528/3634, 6-24=-3528/3634, 6-25=-3567/3646, 7-25=-3599/3632, 7-8=-385/223, 8-9=-397/219 BOT CHORD 3-13=-3195/3116, 12-13=-4146/4058, 11-12=-4146/4058, 10-11=-4146/4058, 7-10=-3054/2978 WEBS 4-13=-228/459, 5-13=-1129/994, 5-10=-1257/1144, 6-10=-236/466, 1-14=-210/355, 9-15=-223/418					
NOTES- (10-11) 1) Unbalanced roof live loads have been considered for this design. 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 2-9-1, Exterior(2R) 2-9-1 to 11-2-15, Interior(1) 11-2-15 to 13-9-1, Exterior(2R) 13-9-1 to 22-2-15, Interior(1) 22-2-15 to 25-0-0, Exterior(2E) 25-0-0 to 28-0-15; Lumber DOL=1.60 plate grip DOL=1.60 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 4) Provide adequate drainage to prevent water ponding. 5) All plates are MT20 plates unless otherwise indicated. 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 7) Refer to girder(s) for truss to truss connections. 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1821 lb uplift at joint 3 and 1855 lb uplift at joint 7. 9) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord. 10) All truss to truss connection by TCI are on the Truss Placement plan. 11) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826					
LOAD CASE(S) Standard					

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H11	HALF HIP	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:26 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-6OIBCzeo099KChL4o?aGnpBI9xTy0UU5W14pE9z9LOB






Plate Offsets (X,Y)-- [3:0-3-0,0-2-6], [5:0-5-4,0-2-0], [9:0-3-0,0-3-0], [11:0-3-4,0-3-0], [14:0-2-0,0-1-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.83	Vert(LL)	0.29 11-12	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.80	Vert(CT)	-0.44 11-12	>665	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.70	Horz(CT)	0.12 9	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S					Weight: 129 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD
WEBS

Structural wood sheathing directly applied or 2-4-8 oc purlins, except end verticals.
Rigid ceiling directly applied or 3-5-15 oc bracing.
1 Row at midpt 7-9

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 9=1334/0-8-0 (min. 0-1-9), 3=1670/0-8-0 (min. 0-2-0), 14=-0/Mechanical
Max Horz 3=227(LC 1), 14=353(LC 4)
Max Uplift 9=-991(LC 4), 3=-1331(LC 4)
Max Grav 9=1334(LC 1), 3=1670(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-336/275, 2-15=-250/198, 3-15=-251/192, 3-4=-3539/2578, 4-5=-3173/2423, 5-16=-3328/2518, 6-16=-3327/2518, 6-7=-2329/1701
BOT CHORD 3-13=-2624/3307, 12-13=-2624/3307, 11-12=-2409/3052, 10-11=-2518/3327, 9-10=-1701/2329
WEBS 4-12=-284/232, 5-12=-58/271, 5-11=-119/521, 6-10=-1102/902, 7-10=-319/571, 7-9=-2512/1832, 1-14=-228/353

- NOTES-** (8-9)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to -0-0-15, Interior(1) -0-0-15 to 4-9-1, Exterior(2R) 4-9-1 to 13-2-15, Interior(1) 13-2-15 to 21-10-4, Exterior(2E) 21-10-4 to 24-10-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 991 lb uplift at joint 9 and 1331 lb uplift at joint 3.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

[illegible]

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H12	Hip	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:30 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-_9Xi2KiJ4Ofhler1reCyfMO2Yn1yJlhRf21Nwz9LO7




Plate Offsets (X,Y)-- [10:0-3-0,0-3-0], [13:0-2-0,0-1-0]									
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d		PLATES GRIP	
TCLL 30.0		Plate Grip DOL 1.33		TC 0.96		Vert(LL) 0.36 9-10 >832 360		MT20	244/190
TCDL 15.0		Lumber DOL 1.33		BC 0.98		Vert(CT) -0.54 9-10 >558 180			
BCLL 0.0		Rep Stress Incr YES		WB 0.55		Horz(CT) 0.12 8 n/a n/a			
BCDL 10.0		Code FBC2020/TPI2014		Matrix-AS				Weight: 112 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 *Except* B1: 2x4 SP No.1 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3		BRACING- TOP CHORD BOT CHORD Structural wood sheathing directly applied. Rigid ceiling directly applied.
--	--	---

REACTIONS. (lb/size) 8=1366/0-8-0 (min. 0-1-10), 3=1661/0-8-0 (min. 0-1-15), 13=-0/Mechanical
Max Horz 3=-290(LC 4), 13=361(LC 4)
Max Uplift 8=-1065(LC 4), 3=-1341(LC 4)
Max Grav 8=1366(LC 1), 3=1661(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-344/306, 2-3=-344/319, 3-4=-3749/2872, 4-20=-3006/2454, 5-20=-2954/2464, 5-6=-2882/2464, 6-21=-2972/2476, 7-21=-3026/2465, 7-22=-3782/3008, 8-22=-3855/2996
BOT CHORD 3-12=-2681/3561, 11-12=-2681/3561, 10-11=-2175/2882, 9-10=-2820/3669, 8-9=-2820/3669
WEBS 4-11=-910/543, 5-11=-177/353, 6-10=-200/369, 7-10=-999/683, 1-13=-261/362

- NOTES-** (9-10)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 6-9-1, Exterior(2R) 6-9-1 to 18-2-15, Interior(1) 18-2-15 to 22-0-0, Exterior(2E) 22-0-0 to 25-0-0; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1065 lb uplift at joint 8 and 1341 lb uplift at joint 3.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

<

Job

12715

Truss

H16

Truss Type

HIP

Qty

1

Ply

1

12715 ROLLING ROAD DR, PINECREST, FL.

Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:39 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-Eua6xPoyy9oTGhqa3EJKpYEWEAfTZH0?WZj?Buz9LO

-3-0-0

3-0-0

5-4-12

11-0-0

16-5-10

21-7-12

25-7-0

29-6-4

35-1-14

40-1-1

46-1-14

49-1-14

3-0-0

3-0-0

2-4-12

5-7-4

5-5-10

5-2-2

3-11-4

3-11-4

5-7-10

4-11-3

6-0-13

3-0-0

Scale = 1:89.2

3.00

12

5x10 MT20HS

3x6 =

3x6 =

3x6 =

4x6 =

5x8 MT20HS

3x6 =

23

4

5

38

6

39

7

8

9

10

11

40

12

41

13

29

28

27

26

25

24

23

22

21

20

19

18

17

14

15

1607#/-1187#

4x6 =

5x6 =

6x14 =

3.22

12

3x6 =

3x6 =

4x10 =

3x6 =

3x6 =

3560#/-2596#

5x6 =

635#/-486#

4x6 =

-0-1-8

3-0-0

5-4-12

11-0-0

16-5-10

25-7-0

29-6-4

35-1-14

40-1-1

46-1-14

46-3-6

0-1-8

3-0-0

2-4-12

5-7-4

5-5-10

9-1-6

3-11-4

5-7-10

4-11-3

6-0-13

0-1-8

Plate Offsets (X,Y)-- [4:0-2-8,0-2-0], [6:0-5-4,0-1-12], [11:0-3-0,0-1-12], [12:0-5-8,0-2-12], [19:0-2-14,0-1-8], [20:0-3-0,0-3-0], [21:0-2-4,0-1-12], [23:0-4-12,0-2-8], [27:0-7-12,0-3-0], [29:0-2-12,0-2-8]

LOADING (psf)

TCLL 30.0

TCDL 15.0

BCLL 0.0

BCDL 10.0

SPACING-

2-0-0

Plate Grip DOL 1.33

Lumber DOL 1.33

Rep Stress Incr YES

Code FBC2020/TPI2014

CSI.

TC 1.00

BC 0.90

WB 1.00

Matrix-AS

DEFL.

in (loc)

l/defl

L/d

Vert(LL) 0.53 28 >667 360

Vert(CT) -0.88 28 >403 180

Horz(CT) 0.16 20 n/a n/a

PLATES

GRIP

MT20 244/190

MT20HS 187/143

Weight: 249 lb FT = 0%

LUMBER-

TOP CHORD 2x4 SP No.1 *Except*
T2: 2x4 SP No.2

BOT CHORD 2x4 SP No.2 *Except*
B1,B8: 2x4 SP No.1, B3,B6: 2x4 SP No.3

WEBS 2x4 SP No.3

OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied.

BOT CHORD Rigid ceiling directly applied.

WEBS 1 Row at midpt 6-27, 12-20, 7-23

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS.

(lb/size) 3=1572/0-8-0 (min. 0-1-14), 20=3560/0-8-0 (min. 0-4-3), 30=0/Mechanical, 31=0/Mechanical, 14=547/0-8-0 (min. 0-1-8)

Max Horz 3=376(LC 9), 30=155(LC 10), 31=431(LC 9)

Max Uplift3=-1187(LC 4), 20=-2596(LC 4), 14=-486(LC 4)

Max Grav3=1607(LC 9), 20=3560(LC 1), 14=635(LC 10)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-4=-3087/1918, 4-5=-5536/3818, 5-38=-5567/3977, 6-38=-5526/3987, 6-39=-2554/1772, 7-39=-2554/1772, 7-8=-678/269, 8-9=-640/254, 9-10=-640/254, 10-11=-1067/1515, 11-40=-2597/3713, 12-40=-2597/3713, 12-41=-922/1664, 13-41=-928/1631, 13-14=-303/1199, 14-15=-399/27, 15-16=-410/26

BOT CHORD 3-29=-1676/2528, 5-27=-373/430, 26-27=-1985/2743, 25-26=-1984/2754, 24-25=-1392/2122, 23-24=-1392/2122, 8-23=-436/386, 20-21=-3996/2977, 19-20=-2015/1197, 18-19=-2015/1197, 17-18=-1575/468, 14-17=-1575/468, 27-29=-1749/2650

WEBS 4-29=-856/678, 6-27=-1703/2412, 6-26=0/267, 21-23=-1646/1330, 10-23=-1493/2122, 10-21=-1363/1006, 11-21=-1934/2780, 11-20=-2218/1686, 12-20=-2610/2010, 12-18=-185/420, 13-18=-1024/778, 16-31=-20/432, 4-27=-1855/2478, 7-23=-2126/1636, 6-25=-745/641, 7-25=-169/394

NOTES- (11-12)

1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 6-9-1, Exterior(2R) 6-9-1 to 15-2-15, Interior(1) 15-2-15 to 30-10-15, Exterior(2R) 30-10-15 to 39-4-13, Interior(1) 39-4-13 to 46-1-14, Exterior(2E) 46-1-14 to 49-2-13; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60

3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.

4) Provide adequate drainage to prevent water ponding.

5) All plates are MT20 plates unless otherwise indicated.

6) All plates are 3x4 MT20 unless otherwise indicated.

7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

8) Refer to girder(s) for truss to truss connections.

9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1187 lb uplift at joint 3, 2596 lb uplift at joint 20 and 486 lb uplift at joint 14.

10) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

11) All truss to truss connection by TCI are on the Truss Placement plan.

12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H18	HIP	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:43 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-6fpdmnsTOOIVI8LI4NGzOOdFoHoV99bQBhDJgz9LNw



Scale = 1:94.8





Plate Offsets (X,Y)--	[3:0-4-14,0-2-1], [7:0-5-4,0-2-8], [10:0-3-0,Edge], [22:0-3-0,0-3-0]
-----------------------	--

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.93	Vert(LL)	0.29 26-27	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.75	Vert(CT)	-0.49 26-27	>725	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.73	Horz(CT)	0.09 22	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS					Weight: 249 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2 *Except* T4: 2x4 SP No.1	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.1 *Except* B2: 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 8-23, 9-22
OTHERS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=1567/0-8-0 (min. 0-1-15), 22=3453/0-8-0 (min. 0-4-1), 28=-0/Mechanical, 30=-0/Mechanical, 16=612/0-8-0 (min. 0-1-8)
Max Horz 3=470(LC 9), 28=404(LC 4), 30=-216(LC 4)
Max Uplift 3=-1206(LC 4), 22=-2616(LC 4), 16=-481(LC 4)
Max Grav 3=1629(LC 9), 22=3453(LC 1), 16=715(LC 10)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-385/350, 2-3=-385/364, 3-4=-3726/2504, 4-5=-3351/2227, 5-6=-3267/2234, 6-7=-2325/1632, 7-37=-1583/1050, 8-37=-1583/1050, 8-9=-165/301, 9-10=-1887/2664, 10-38=-1887/2664, 11-38=-1887/2664, 11-12=-1185/1754, 12-13=-1261/1822, 13-14=-464/973, 14-15=-475/942, 15-16=-484/757
BOT CHORD 3-27=-2476/3378, 26-27=-2113/2876, 25-26=-1442/2064, 24-25=-1442/2064, 23-24=-839/1419, 22-23=-292/376, 21-22=-2638/2098, 20-21=-2638/2098, 19-20=-1288/591, 16-19=-879/514
WEBS 4-27=-371/369, 6-27=-51/370, 6-26=-963/782, 7-26=-341/608, 7-24=-896/738, 8-24=-372/608, 8-23=-1904/1485, 9-23=-788/1192, 9-22=-2890/2106, 11-22=-1685/1408, 11-20=-1210/1569, 12-20=-677/618, 13-20=-1095/892, 13-19=-185/487, 15-19=-570/521, 1-29=-307/405, 28-29=-306/404

- NOTES-** (10-11)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 9-5-0, Exterior(2R) 9-5-0 to 18-1-7, Interior(1) 18-1-7 to 28-0-7, Exterior(2R) 28-0-7 to 36-8-14, Interior(1) 36-8-14 to 46-1-14, Exterior(2E) 46-1-14 to 49-2-13; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - All plates are 3x6 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1206 lb uplift at joint 3, 2616 lb uplift at joint 22 and 481 lb uplift at joint 16.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H20	HIP	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:47 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-?Q37c8vz4coLEwR6XvSC8EZlwPf9R?zBLpfQSRz9LNs




Plate Offsets (X,Y)-- [1:0-6-7,0-2-0], [3:0-11-8,Edge], [4:0-0-4,0-0-11], [8:0-0-4,0-0-11], [15:0-2-0,0-1-0], [16:0-2-0,0-0-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.95	Vert(LL)	0.23	8-13	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.72	Vert(CT)	-0.43	8-13	>607	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.55	Horz(CT)	-0.12	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 128 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1 *Except* T2: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2 *Except* B2: 2x4 SP No.3	BOT CHORD Rigid ceiling directly applied or 5-1-11 oc bracing.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=1524/0-8-0 (min. 0-1-13), 9=1468/0-8-0 (min. 0-1-12), 15=0/Mechanical, 16=-0/Mechanical
Max Horz 9=-1054(LC 1), 15=1529(LC 1), 16=-475(LC 1)
Max Uplift3=-1254(LC 4), 9=-1206(LC 4)
Max Grav 3=1524(LC 1), 9=1468(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-1462/955, 2-3=-1530/1060, 3-4=-1747/1232, 4-5=-2742/2289, 5-6=-2088/1701, 6-7=-2103/1705, 7-8=-3036/2519,
8-9=-1768/1249, 9-17=-476/222, 10-17=-476/222, 10-11=-452/148
BOT CHORD 4-13=-1029/1100, 8-13=-1280/1418
WEBS 6-13=-324/596, 5-13=-806/696, 7-13=-1046/957, 1-15=-990/1531, 11-16=-147/475

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -2-11-3 to 0-4-0, Interior(1) 0-4-0 to 6-11-9, Exterior(2R) 6-11-9 to 15-3-14, Interior(1) 15-3-14 to 22-5-11, Exterior(2E) 22-5-11 to 25-5-11; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1254 lb uplift at joint 3 and 1206 lb uplift at joint 9.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard


Job 12715	Truss H21	Truss Type HIP	Qty 1	Ply 1	12715 ROLLING ROAD DR, PINECREST, FL.
Trusscorp Int., 9590 NW 89 AVE, Medley, FL ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-xpBu1qwEbE23TDdbVeKUgDfejoCM0vvCUp68XXJz9LNq					
Scale = 1:51.0					
Plate Offsets (X,Y)-- [1:0-0-8,0-3-0], [3:0-11-8,Edge], [5:0-3-0,0-2-12], [7:0-3-0,0-2-12], [9:0-11-8,Edge], [11:0-0-8,0-3-0], [13:0-1-12,0-1-8], [14:0-1-12,0-1-8], [16:0-2-0,0-1-0], [17:0-2-0,0-0-8]					
LOADING (psf) TCLL 30.0 TCDL 15.0 BCLL 0.0 BCDL 10.0	SPACING- 2-0-0 Plate Grip DOL 1.33 Lumber DOL 1.33 Rep Stress Incr YES Code FBC2020/TPI2014	CSI. TC 0.61 BC 0.63 WB 0.57 Matrix-S	DEFL. in (loc) l/defl L/d Vert(LL) 0.31 13-14 >852 360 Vert(CT) -0.41 13-14 >640 180 Horz(CT) 0.11 9 n/a n/a	PLATES MT20 Weight: 128 lb	GRIP 244/190 FT = 0%
LUMBER- TOP CHORD 2x6 SP 2400F 2.0E *Except* T2: 2x6 SP No.2 BOT CHORD 2x4 SP No.2 *Except* B2: 2x4 SP No.3 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3					
REACTIONS. (lb/size) 3=1467/0-8-0 (min. 0-1-13), 9=1536/0-8-0 (min. 0-1-15), 16=-0/Mechanical, 17=0/Mechanical Max Horz 3=-1178(LC 4), 16=555(LC 9), 17=1617(LC 4) Max Uplift 3=-1725(LC 4), 9=-1802(LC 4) Max Grav 3=1548(LC 5), 9=1620(LC 5)					
FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-2=-528/429, 2-18=-590/532, 3-18=-590/532, 3-19=-1914/1987, 4-19=-1888/1995, 4-5=-3132/3344, 5-6=-3123/3363, 6-7=-2852/3062, 7-8=-2875/3063, 8-20=-1879/1981, 9-20=-1901/1972, 9-21=-1653/1710, 10-21=-1653/1710, 10-11=-1548/1564 BOT CHORD 4-14=-1400/1386, 13-14=-2155/1835, 8-13=-1087/1138 WEBS 5-14=-42/255, 6-14=-675/789, 6-13=-908/1103, 7-13=-142/323, 1-16=-439/555, 11-17=-1618/1610					
NOTES- (8-9) 1) Unbalanced roof live loads have been considered for this design. 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-0-11 to -0-0-11, Interior(1) -0-0-11 to 2-9-1, Exterior(2R) 2-9-1 to 19-7-15, Interior(1) 19-7-15 to 22-5-11, Exterior(2E) 22-5-11 to 25-5-11; Lumber DOL=1.60 plate grip DOL=1.60 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 4) Provide adequate drainage to prevent water ponding. 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 6) Refer to girder(s) for truss to truss connections. 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1725 lb uplift at joint 3 and 1802 lb uplift at joint 9. 8) All truss to truss connection by TCI are on the Truss Placement plan. 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826					
LOAD CASE(S) Standard					

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H22	HIP	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:50 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-P?lGEAxsMXAw5NAhC2?vltBupclteMLd1mu43mz9LNp



Scale = 1:50.3




Plate Offsets (X,Y)--	[3:0-11-0,Edge], [5:0-5-4,0-2-12], [6:0-3-0,0-2-12], [8:0-11-12,Edge], [15:0-2-0,0-1-0], [16:0-2-0,0-0-8]
-----------------------	---

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.59	Vert(LL)	0.27	4-13	>955	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.40	Vert(CT)	-0.33	4-13	>793	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.57	Horz(CT)	0.11	8	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 124 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x6 SP 2400F 2.0E *Except* T2: 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied or 4-7-15 oc purlins.
BOT CHORD 2x4 SP No.2 *Except* B2: 2x4 SP No.3	BOT CHORD Rigid ceiling directly applied or 5-11-8 oc bracing.
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
OTHERS 2x4 SP No.3	

REACTIONS. (lb/size) 3=1468/0-8-0 (min. 0-1-13), 8=1535/0-8-0 (min. 0-1-15), 15=-0/Mechanical, 16=0/Mechanical
Max Horz 3=-1099(LC 4), 15=633(LC 9), 16=-1631(LC 5)
Max Uplift 3=-1671(LC 4), 8=-1743(LC 4)
Max Grav 3=1550(LC 5), 8=1618(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-604/444, 2-17=-648/548, 3-17=-648/548, 3-4=-1932/1916, 4-18=-2642/2821, 5-18=-2636/2831, 5-6=-2489/2713, 6-19=-2503/2696, 7-19=-2516/2686, 7-8=-1919/1902, 8-20=-1674/1646, 9-20=-1674/1646, 9-10=-1569/1502
BOT CHORD 4-13=-916/919, 12-13=-907/922, 7-12=-759/739
WEBS 5-12=-404/174, 1-15=-455/633, 10-16=-1554/1631

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-0-11 to -0-0-11, Interior(1) -0-0-11 to 4-9-1, Exterior(2R) 4-9-1 to 17-7-15, Interior(1) 17-7-15 to 22-5-11, Exterior(2E) 22-5-11 to 25-5-11; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1671 lb uplift at joint 3 and 1743 lb uplift at joint 8.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	H23	HIP	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:52 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-LOs0fsz6u9RdKhK4JT2NriGEKQPh6FLwV4NB7ez9LNn




Plate Offsets (X,Y)-- [1:0-0-8,0-3-0], [3:1-0-0,Edge], [5:0-4-4,0-2-8], [7:1-0-0,Edge], [9:0-0-8,0-3-0], [13:0-1-12,0-1-0], [14:0-1-12,0-0-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.59	Vert(LL)	0.30 4-11	>862	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.57	Vert(CT)	-0.41 4-11	>634	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.60	Horz(CT)	0.12 7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S					Weight: 117 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x6 SP 2400F 2.0E	TOP CHORD Structural wood sheathing directly applied or 5-9-6 oc purlins.
BOT CHORD 2x4 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
B2: 2x4 SP No.3	
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
OTHERS 2x4 SP No.3	

REACTIONS. (lb/size) 3=1468/0-8-0 (min. 0-1-13), 7=1534/0-8-0 (min. 0-1-15), 13=0/Mechanical, 14=0/Mechanical
Max Horz 3=-1035(LC 4), 13=781(LC 9), 14=-1727(LC 5)
Max Uplift 3=-1611(LC 4), 7=-1679(LC 4)
Max Grav 3=1550(LC 5), 7=1618(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-746/503, 2-15=-782/609, 3-15=-782/609, 3-4=-2018/1891, 4-16=-2201/2204, 5-16=-2181/2215, 5-17=-2196/2230, 6-17=-2215/2219, 6-7=-2005/1878, 7-18=-1770/1644, 8-18=-1770/1644, 8-9=-1661/1500
BOT CHORD 4-11=-279/331, 6-11=-279/331
WEBS 5-11=0/342, 1-13=-516/781, 9-14=-1552/1727

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-0-11 to -0-0-11, Interior(1) -0-0-11 to 6-11-9, Exterior(2R) 6-11-9 to 15-5-7, Interior(1) 15-5-7 to 22-5-11, Exterior(2E) 22-5-11 to 25-5-11; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1611 lb uplift at joint 3 and 1679 lb uplift at joint 7.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

[illegible]

Job

12715

Truss

HG2T

Truss Type

HIP GIRDER

Qty

1

Ply

2

12715 ROLLING ROAD DR, PINECREST, FL.

Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:42:58 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-AYDIwv1tU_Bn2cnDgj9n4ZWIIqUHWzFot0qVLiz9LNh

3-0-0
3-0-0

7-0-0
7-0-0

11-7-1
4-7-1

16-1-6
4-6-5

21-1-8
5-0-2

28-1-8
7-0-0

Scale = 1:53.9

4x8 =

4

3x4 =

23

2x4 ||

24

4x6 =

7

21

22

25

26

27

28

2x4 ||

2

2x4 ||

3

2x4 ||

14

3x4 =

13

2x4 ||

29

3x4 =

30

3x4 =

31

4x6 =

32

6x8 =

33

2x4 ||

9

3x6 =

8

1826#/-1854#

3061#/-3128#

898#/-810#

517#/-500#

-0-1-8
0-1-8

7-0-0
7-0-0

11-7-1
4-7-1

16-1-6
4-6-5

21-0-0
4-10-10

21-1-8
0-1-8

28-1-8
7-0-0

Plate Offsets (X,Y)-- [3:0-4-7,0-0-9], [4:0-5-4,0-2-0], [10:0-4-0,0-4-8], [14:0-2-0,0-1-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.49	Vert(LL)	0.12 12-13	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.43	Vert(CT)	-0.10 12-13	>999	180		
BCLL 0.0	Rep Stress Incr	NO	WB 0.58	Horz(CT)	-0.03 10	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MSH					Weight: 298 lb	FT = 0%

LUMBER-

TOP CHORD 2x4 SP No.2 *Except*
T1: 2x4 SP No.1

BOT CHORD 2x6 SP No.2

WEBS 2x4 SP No.3 *Except*
W2: 2x6 SP No.2

OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.

All bearings 0-8-0 except (jt=length) 14=Mechanical.

(lb) - Max Horz 3=163(LC 16), 14=253(LC 20)

Max Uplift All uplift 100 lb or less at joint(s) except 8=500(LC 20), 3=1854(LC 4), 10=3128(LC 4), 9=810(LC 4)

Max Grav All reactions 250 lb or less at joint(s) except 8=517(LC 5), 3=1826(LC 1), 10=3061(LC 9), 9=898(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-21=-3518/3744, 4-21=-3418/3762, 4-22=-2386/2675, 22-23=-2386/2675, 5-23=-2386/2675, 5-24=-783/844, 24-25=-783/844, 25-26=-783/844, 6-26=-783/844, 6-27=-783/844, 7-27=-783/844, 7-28=-813/868, 8-28=-831/830

BOT CHORD 3-13=-3398/3242, 13-29=-3471/3308, 29-30=-3471/3308, 12-30=-3471/3308, 12-31=-2412/2386, 11-31=-2412/2386, 11-32=-2412/2386, 32-33=-2412/2386, 10-33=-2412/2386, 9-10=-844/997, 8-9=-792/921

WEBS 4-13=-1226/1241, 6-10=-418/502, 7-9=-730/818, 5-10=-3606/3881, 4-12=-1088/1201, 5-12=-1437/1383, 1-14=-163/254

NOTES-

(11-12)

1) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc clinched.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc clinched.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc clinched, 2x6 - 2 rows staggered at 0-9-0 oc clinched.

2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

3) Unbalanced roof live loads have been considered for this design.

4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-0-0, Interior(1) 0-0-0 to 2-9-1, Exterior(2R) 2-9-1 to 11-2-15, Interior(1) 11-2-15 to 16-10-9, Exterior(2R) 16-10-9 to 25-1-8, Exterior(2E) 25-1-8 to 28-1-8; porch left exposed; Lumber DOL=1.60 plate grip DOL=1.60

5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.

6) Provide adequate drainage to prevent water ponding.

7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

8) Refer to girder(s) for truss to truss connections.

9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 500 lb uplift at joint 8, 1854 lb uplift at joint 3, 3128 lb uplift at joint 10 and 810 lb uplift at joint 9.

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 143 lb down and 148 lb up at 7-0-0, 143 lb down and 148 lb up at 9-0-12, 133 lb down and 148 lb up at 11-0-12, 110 lb down and 137 lb up at 13-0-12, and 84 lb down and 117 lb up at 15-0-12, and 85 lb down and 103 lb up at 15-8-8 on top chord, and 983 lb down and 1121 lb up at 7-0-0, 351 lb down and 398 lb up at 9-0-12, 351 lb down and 398 lb up at 11-0-12, 314 lb down and 340 lb up at 13-0-12, and 362 lb down and 397 lb up at 15-0-12, and 367 lb down and 376 lb up at 15-8-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

11) All truss to truss connection by TCI are on the Truss Placement plan.

12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG2T	HIP GIRDER	1	2	Job Reference (optional)

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33

Uniform Loads (plf)

Vert: 1-4=-90, 4-7=-90, 7-8=-90, 15-18=-20

Concentrated Loads (lb)

Vert: 13=-862(F) 25=39(F) 26=40(F) 29=-311(F) 30=-311(F) 31=-314(F) 32=-362(F) 33=-367(F)

[illegible]

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG3A	Hip Girder	1	2	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:01 2025 Page 2

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-a7vQYx4lnvZMv3WoLsiUiB8hn2PCjQCFZ_2Aydz9LNe

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-4=-90, 4-5=-90, 5-6=-90, 11-14=-20

Concentrated Loads (lb)

Vert: 5=39(B) 9=-862(B) 7=-366(B) 13=-357(B) 19=33(B) 21=-311(B) 22=-324(B) 23=-357(B) 24=-357(B)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.								
12715	HG3T	HIP GIRDER	1	2	Job Reference (optional)								
Trusscorp Int., 9590 NW 89 AVE, Medley, FL			8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:04 2025 Page 1										
			ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-?ibZAY6e3qxwmXFNO_FBKqmB6FV9wmzhFyHqZyz9LNb										
-3-0-0 3-0-0 5-0-0 5-0-0 10-0-5 5-0-5 15-0-10 5-0-5 20-0-10 5-0-0 23-0-10 3-0-0			Scale = 1:46.9										
4.00 12 4 22 23 5 24 25 6 2x4 2 3 14 3x6 13 26 27 12 28 11 29 10 7 8 15 3x6 2x4 7 8 9 2x4 2272##-2768# 2295##-2796# -0-1-8 0-1-8 5-0-0 5-0-0 10-0-5 5-0-5 15-0-10 5-0-5 20-0-10 5-0-0 20-2-2 0-1-8 <tr><td colspan="6">Plate Offsets (X,Y)-- [14:0-2-0,0-1-0], [15:0-2-0,0-0-8]</td></tr><tr><td colspan="2">LOADING (psf) TCLL 30.0 TCDL 15.0 BCLL 0.0 BCDL 10.0</td><td>SPACING- 2-0-0 Plate Grip DOL 1.33 Lumber DOL 1.33 Rep Stress Incr NO Code FBC2020/TPI2014</td><td>CSI. TC 0.98 BC 0.52 WB 0.31 Matrix-MSH</td><td>DEFL. in (loc) l/defl L/d Vert(LL) 0.28 12 >856 360 Vert(CT) 0.24 12 >986 180 Horz(CT) -0.05 7 n/a n/a</td><td>PLATES MT20 GRIP 244/190 Weight: 238 lb FT = 0%</td></tr><tr><td> LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x6 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3 BRACING- TOP CHORD Structural wood sheathing directly applied or 5-6-1 oc purlins. BOT CHORD Rigid ceiling directly applied or 5-10-9 oc bracing. REACTIONS. (lb/size) 3=2001/0-8-0 (min. 0-1-8), 14=-0/Mechanical, 15=0/Mechanical, 7=2021/0-8-0 (min. 0-1-8) Max Horz 3=342(LC 9), 14=466(LC 13), 15=-542(LC 13) Max Uplift 3=-2768(LC 4), 7=-2796(LC 4) Max Grav 3=2272(LC 14), 7=2295(LC 14) FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-2=-433/344, 2-3=-434/357, 3-4=-4718/5655, 4-22=-4568/5529, 22-23=-4568/5529, 5-23=-4568/5529, 5-24=-4481/5424, 24-25=-4481/5424, 6-25=-4481/5424, 6-7=-4631/5551, 7-8=-506/465, 8-9=-504/450 BOT CHORD 3-13=-5063/4248, 13-26=-6969/5828, 26-27=-6969/5828, 12-27=-6969/5828, 12-28=-6969/5828, 11-28=-6969/5828, 11-29=-6969/5828, 10-29=-6969/5828, 7-10=-4960/4162 WEBS 4-13=-942/941, 5-13=-1603/1950, 5-12=-90/357, 5-10=-1696/2061, 6-10=-920/923, 1-14=-346/467, 9-15=-460/543 NOTES- (11-12) 1) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows: Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc clinched. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc clinched. Webs connected as follows: 2x4 - 1 row at 0-9-0 oc clinched. 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated. 3) Unbalanced roof live loads have been considered for this design. 4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-1-3 to 0-0-0, Interior(1) 0-0-0 to 0-9-1, Exterior(2R) 0-9-1 to 9-2-15, Interior(1) 9-2-15 to 10-9-11, Exterior(2R) 10-9-11 to 19-3-3, Interior(1) 19-3-3 to 20-0-10, Exterior(2E) 20-0-10 to 23-1-13; Lumber DOL=1.60 plate grip DOL=1.60 5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 6) Provide adequate drainage to prevent water ponding. 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 8) Refer to girder(s) for truss to truss connections. 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2768 lb uplift at joint 3 and 2796 lb uplift at joint 7. 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 351 lb down and 408 lb up at 5-0-0, 351 lb down and 408 lb up at 7-0-12, 337 lb down and 408 lb up at 9-0-12, 337 lb down and 408 lb up at 10-11-14, and 351 lb down and 408 lb up at 12-11-14, and 351 lb down and 408 lb up at 15-0-10 on top chord, and 450 lb down and 521 lb up at 5-0-0, 44 lb down and 25 lb up at 7-0-12, 44 lb down and 25 lb up at 9-0-12, 44 lb down and 25 lb up at 10-11-14, and 44 lb down and 25 lb up at 12-11-14, and 450 lb down and 521 lb up at 14-11-14 on bottom chord. The design/selection of such connection device(s) is the responsibility of others. 11) All truss to truss connection by TCI are on the Truss Placement plan. 12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826 LOAD CASE(S) Standard </td></tr>	Plate Offsets (X,Y)-- [14:0-2-0,0-1-0], [15:0-2-0,0-0-8]						LOADING (psf) TCLL 30.0 TCDL 15.0 BCLL 0.0 BCDL 10.0		SPACING- 2-0-0 Plate Grip DOL 1.33 Lumber DOL 1.33 Rep Stress Incr NO Code FBC2020/TPI2014	CSI. TC 0.98 BC 0.52 WB 0.31 Matrix-MSH	DEFL. in (loc) l/defl L/d Vert(LL) 0.28 12 >856 360 Vert(CT) 0.24 12 >986 180 Horz(CT) -0.05 7 n/a n/a	PLATES MT20 GRIP 244/190 Weight: 238 lb FT = 0%	LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x6 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3 BRACING- TOP CHORD Structural wood sheathing directly applied or 5-6-1 oc purlins. BOT CHORD Rigid ceiling directly applied or 5-10-9 oc bracing. REACTIONS. (lb/size) 3=2001/0-8-0 (min. 0-1-8), 14=-0/Mechanical, 15=0/Mechanical, 7=2021/0-8-0 (min. 0-1-8) Max Horz 3=342(LC 9), 14=466(LC 13), 15=-542(LC 13) Max Uplift 3=-2768(LC 4), 7=-2796(LC 4) Max Grav 3=2272(LC 14), 7=2295(LC 14) FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-2=-433/344, 2-3=-434/357, 3-4=-4718/5655, 4-22=-4568/5529, 22-23=-4568/5529, 5-23=-4568/5529, 5-24=-4481/5424, 24-25=-4481/5424, 6-25=-4481/5424, 6-7=-4631/5551, 7-8=-506/465, 8-9=-504/450 BOT CHORD 3-13=-5063/4248, 13-26=-6969/5828, 26-27=-6969/5828, 12-27=-6969/5828, 12-28=-6969/5828, 11-28=-6969/5828, 11-29=-6969/5828, 10-29=-6969/5828, 7-10=-4960/4162 WEBS 4-13=-942/941, 5-13=-1603/1950, 5-12=-90/357, 5-10=-1696/2061, 6-10=-920/923, 1-14=-346/467, 9-15=-460/543 NOTES- (11-12) 1) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows: Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc clinched. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc clinched. Webs connected as follows: 2x4 - 1 row at 0-9-0 oc clinched. 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated. 3) Unbalanced roof live loads have been considered for this design. 4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-1-3 to 0-0-0, Interior(1) 0-0-0 to 0-9-1, Exterior(2R) 0-9-1 to 9-2-15, Interior(1) 9-2-15 to 10-9-11, Exterior(2R) 10-9-11 to 19-3-3, Interior(1) 19-3-3 to 20-0-10, Exterior(2E) 20-0-10 to 23-1-13; Lumber DOL=1.60 plate grip DOL=1.60 5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 6) Provide adequate drainage to prevent water ponding. 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 8) Refer to girder(s) for truss to truss connections. 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2768 lb uplift at joint 3 and 2796 lb uplift at joint 7. 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 351 lb down and 408 lb up at 5-0-0, 351 lb down and 408 lb up at 7-0-12, 337 lb down and 408 lb up at 9-0-12, 337 lb down and 408 lb up at 10-11-14, and 351 lb down and 408 lb up at 12-11-14, and 351 lb down and 408 lb up at 15-0-10 on top chord, and 450 lb down and 521 lb up at 5-0-0, 44 lb down and 25 lb up at 7-0-12, 44 lb down and 25 lb up at 9-0-12, 44 lb down and 25 lb up at 10-11-14, and 44 lb down and 25 lb up at 12-11-14, and 450 lb down and 521 lb up at 14-11-14 on bottom chord. The design/selection of such connection device(s) is the responsibility of others. 11) All truss to truss connection by TCI are on the Truss Placement plan. 12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826 LOAD CASE(S) Standard
Plate Offsets (X,Y)-- [14:0-2-0,0-1-0], [15:0-2-0,0-0-8]													
LOADING (psf) TCLL 30.0 TCDL 15.0 BCLL 0.0 BCDL 10.0		SPACING- 2-0-0 Plate Grip DOL 1.33 Lumber DOL 1.33 Rep Stress Incr NO Code FBC2020/TPI2014	CSI. TC 0.98 BC 0.52 WB 0.31 Matrix-MSH	DEFL. in (loc) l/defl L/d Vert(LL) 0.28 12 >856 360 Vert(CT) 0.24 12 >986 180 Horz(CT) -0.05 7 n/a n/a	PLATES MT20 GRIP 244/190 Weight: 238 lb FT = 0%								
LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x6 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3 BRACING- TOP CHORD Structural wood sheathing directly applied or 5-6-1 oc purlins. BOT CHORD Rigid ceiling directly applied or 5-10-9 oc bracing. REACTIONS. (lb/size) 3=2001/0-8-0 (min. 0-1-8), 14=-0/Mechanical, 15=0/Mechanical, 7=2021/0-8-0 (min. 0-1-8) Max Horz 3=342(LC 9), 14=466(LC 13), 15=-542(LC 13) Max Uplift 3=-2768(LC 4), 7=-2796(LC 4) Max Grav 3=2272(LC 14), 7=2295(LC 14) FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-2=-433/344, 2-3=-434/357, 3-4=-4718/5655, 4-22=-4568/5529, 22-23=-4568/5529, 5-23=-4568/5529, 5-24=-4481/5424, 24-25=-4481/5424, 6-25=-4481/5424, 6-7=-4631/5551, 7-8=-506/465, 8-9=-504/450 BOT CHORD 3-13=-5063/4248, 13-26=-6969/5828, 26-27=-6969/5828, 12-27=-6969/5828, 12-28=-6969/5828, 11-28=-6969/5828, 11-29=-6969/5828, 10-29=-6969/5828, 7-10=-4960/4162 WEBS 4-13=-942/941, 5-13=-1603/1950, 5-12=-90/357, 5-10=-1696/2061, 6-10=-920/923, 1-14=-346/467, 9-15=-460/543 NOTES- (11-12) 1) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows: Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc clinched. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc clinched. Webs connected as follows: 2x4 - 1 row at 0-9-0 oc clinched. 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated. 3) Unbalanced roof live loads have been considered for this design. 4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-1-3 to 0-0-0, Interior(1) 0-0-0 to 0-9-1, Exterior(2R) 0-9-1 to 9-2-15, Interior(1) 9-2-15 to 10-9-11, Exterior(2R) 10-9-11 to 19-3-3, Interior(1) 19-3-3 to 20-0-10, Exterior(2E) 20-0-10 to 23-1-13; Lumber DOL=1.60 plate grip DOL=1.60 5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 6) Provide adequate drainage to prevent water ponding. 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 8) Refer to girder(s) for truss to truss connections. 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2768 lb uplift at joint 3 and 2796 lb uplift at joint 7. 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 351 lb down and 408 lb up at 5-0-0, 351 lb down and 408 lb up at 7-0-12, 337 lb down and 408 lb up at 9-0-12, 337 lb down and 408 lb up at 10-11-14, and 351 lb down and 408 lb up at 12-11-14, and 351 lb down and 408 lb up at 15-0-10 on top chord, and 450 lb down and 521 lb up at 5-0-0, 44 lb down and 25 lb up at 7-0-12, 44 lb down and 25 lb up at 9-0-12, 44 lb down and 25 lb up at 10-11-14, and 44 lb down and 25 lb up at 12-11-14, and 450 lb down and 521 lb up at 14-11-14 on bottom chord. The design/selection of such connection device(s) is the responsibility of others. 11) All truss to truss connection by TCI are on the Truss Placement plan. 12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826 LOAD CASE(S) Standard													

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG3T	HIP GIRDER	1	2	Job Reference (optional)

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33

Uniform Loads (plf)

Vert: 1-4=-90, 4-6=-90, 6-9=-90, 16-19=-20

Concentrated Loads (lb)

Vert: 4=-85(F) 6=-85(F) 13=-315(F) 10=-315(F) 22=-85(F) 23=-85(F) 24=-85(F) 25=-85(F) 26=-30(F) 27=-30(F) 28=-30(F) 29=-30(F)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG4T	HIP GIRDER	1	2	
Trusscorp Int., 9590 NW 89 AVE, Medley, FL			8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:06 2025 Page 1 ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-x4iJbe7ubSBe0rOm8PIfPFrbT3CoOhf_jGmwdqz9LNZ		
-3-0-0 3-0-0 5-0-0 5-0-0 8-5-13 3-5-13 11-11-10 3-5-13 16-11-10 5-0-0 Scale = 1:34.3					
4x6 == 4 3x4 == 5 4x6 == 6 18 19 20 4.00 [12] 2x4 2 2x4 3 2x4 11 2x4 1 10 21 22 23 9 8 7 3x4 == 10 3x4 == 9 3x6 == 7 2055#/-2594# -0-1-8 0-1-8 5-0-0 5-0-0 8-5-13 3-5-13 11-11-10 3-5-13 16-11-10 5-0-0					

Plate Offsets (X,Y)-- [11:0-2-0,0-1-0]						
LOADING (psf) TCLL 30.0 TCDL 15.0 BCLL 0.0 BCDL 10.0		**SPACING-** 2-0-0 Plate Grip DOL 1.33 Lumber DOL 1.33 Rep Stress Incr NO Code FBC2020/TPI2014	**CSI.** TC 0.74 BC 0.45 WB 0.17 Matrix-MSH	**DEFL.** in (loc) l/defl L/d Vert(LL) 0.20 9-10 >999 360 Vert(CT) 0.17 9-10 >999 180 Horz(CT) -0.04 7 n/a n/a	**PLATES GRIP** MT20 244/190 Weight: 182 lb FT = 0%	
LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x6 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3						**BRACING-** TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins. BOT CHORD Rigid ceiling directly applied or 6-6-12 oc bracing.
REACTIONS. (lb/size) 7=1490/0-8-0 (min. 0-1-8), 3=1799/0-8-0 (min. 0-1-8), 11=-0/Mechanical Max Horz 3=-317(LC 13), 11=474(LC 13) Max Uplift7=-2108(LC 4), 3=-2594(LC 4) Max Grav 7=1723(LC 14), 3=2055(LC 14)						
FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-2=-441/335, 2-3=-442/345, 3-4=-4147/5057, 4-18=-4016/4957, 5-18=-4016/4957, 5-19=-4115/5087, 6-19=-4115/5087, 6-20=-4223/5188, 7-20=-4246/5182 BOT CHORD 3-10=-4621/3835, 10-21=-5678/4549, 21-22=-5678/4549, 22-23=-5678/4549, 9-23=-5678/4549, 8-9=-4749/3933, 7-8=-4749/3933 WEBS 4-10=-882/861, 5-10=-731/1119, 5-9=-650/972, 6-9=-911/881, 1-11=-333/475						
NOTES- (11-12) 1) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows: Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc clinched. Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc clinched. Webs connected as follows: 2x4 - 1 row at 0-9-0 oc clinched. 2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated. 3) Unbalanced roof live loads have been considered for this design. 4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TC DL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-1-3 to 0-0-0, Interior(1) 0-0-0 to 0-9-1, Exterior(2R) 0-9-1 to 13-11-10, Exterior(2E) 13-11-10 to 16-11-10; Lumber DOL=1.60 plate grip DOL=1.60 5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 6) Provide adequate drainage to prevent water ponding. 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 8) Refer to girder(s) for truss to truss connections. 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2108 lb uplift at joint 7 and 2594 lb uplift at joint 3. 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 361 lb down and 409 lb up at 5-0-0, 361 lb down and 409 lb up at 7-0-12, 361 lb down and 409 lb up at 8-5-13, and 361 lb down and 409 lb up at 9-10-14, and 361 lb down and 409 lb up at 11-11-10 on top chord, and 450 lb down and 521 lb up at 5-0-0, 44 lb down and 25 lb up at 7-0-12, 44 lb down and 25 lb up at 8-5-13, and 44 lb down and 25 lb up at 9-10-14, and 450 lb down and 521 lb up at 11-10-14 on bottom chord. The design/selection of such connection device(s) is the responsibility of others. 11) All truss to truss connection by TCI are on the Truss Placement plan. 12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826						
LOAD CASE(S) Standard 1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33 Uniform Loads (plf) Vert: 1-4=-90, 4-6=-90, 6-7=-90, 12-15=-20						

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG4T	HIP GIRDER	1	2	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:06 2025 Page 2
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-x4iJbe7ubSBe0rOm8PIfPFrbT3CoOhf_jGmwdqz9LNZ

LOAD CASE(S) Standard
Concentrated Loads (lb)
Vert: 4=-85(B) 6=-85(B) 10=-315(B) 5=-85(B) 9=-315(B) 18=-85(B) 19=-85(B) 21=-30(B) 22=-30(B) 23=-30(B)

Job

12715

Truss

HG5T

Truss Type

HIP GIRDER

Qty

1

Ply

2

12715 ROLLING ROAD DR, PINECREST, FL.

Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:07 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-PHGhp_8WMIjVd_zyi6puySOjYTRZ7207ywVU9Hz9LNY

-3-0-0

3-0-0

5-0-0

5-0-0

10-0-9

5-0-9

14-11-7

4-10-13

20-0-0

5-0-9

25-0-0

5-0-0

28-0-0

3-0-0

Scale = 1:53.2

3.00'12"

4x6 =

4

22

5

3x4 =

4x10 =

6

23

7

4x6 =

2x4 ||

2x4 ||

2

3

20

21

16

5x8 =

15

3x4 =

14

3x4 =

13

12

7x8 WB=

3x4 =

11

5x8 =

24

2x4 ||

2x4 ||

9

25

10

3x4 =

2812#/-2792#

2812#/-2790#

5-0-0

5-0-0

10-0-9

5-0-9

14-11-7

4-10-13

20-0-0

5-0-9

25-0-0

5-0-0

Plate Offsets (X,Y)-- [3:0-4-0,0-3-10], [4:0-2-12,0-2-4], [5:0-1-12,0-1-8], [7:0-2-12,0-2-4], [8:0-4-0,0-3-10], [11:0-1-12,0-1-8], [14:0-1-12,0-1-8], [15:0-1-12,0-1-8]

LOADING (psf)

TCLL 30.0

TCDL 15.0

BCLL 0.0

BCDL 10.0

SPACING-

2-0-0

Plate Grip DOL 1.33

Lumber DOL 1.33

Rep Stress Incr NO

Code FBC2020/TPI2014

CSI.

TC 0.91

BC 0.93

WB 0.54

Matrix-SH

DEFL.

in (loc)

l/defl

L/d

Vert(LL) 0.59 13-14 >497 360

Vert(CT) -0.67 13-14 >438 180

Horz(CT) 0.10 8 n/a n/a

PLATES GRIP

MT20 244/190

Weight: 289 lb FT = 0%

LUMBER-

TOP CHORD 2x4 SP No.2 *Except*

T2: 2x4 SP No.1

BOT CHORD 2x6 SP No.2

WEBS 2x4 SP No.3

OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-10-4 oc purlins.

BOT CHORD Rigid ceiling directly applied or 4-10-0 oc bracing.

REACTIONS.

(lb/size) 3=2446/0-8-0 (min. 0-1-11), 8=2446/0-8-0 (min. 0-1-11)

Max Uplift3=-2792(LC 4), 8=-2790(LC 4)

Max Grav3=2812(LC 5), 8=2812(LC 5)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-21=-7284/6663, 4-21=-7281/6677, 4-22=-7166/6603, 5-22=-7166/6603, 5-6=-10458/10014, 6-23=-7152/6589, 7-23=-7152/6589, 7-24=-7265/6661, 8-24=-7269/6648

BOT CHORD 3-15=-6203/6873, 14-15=-9731/10325, 13-14=-9817/10410, 12-13=-9817/10410, 11-12=-9817/10410, 8-11=-6188/6859

WEBS 4-15=-1107/1507, 5-15=-3418/3541, 6-13=0/265, 6-11=-3522/3645, 7-11=-1108/1508

NOTES-

(11-12)

1) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc clinched.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc clinched.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc clinched.

2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

3) Unbalanced roof live loads have been considered for this design.

4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-0-15 to -0-0-15, Interior(1) -0-0-15 to 0-9-1, Exterior(2R) 0-9-1 to 9-2-15, Interior(1) 9-2-15 to 15-9-1, Exterior(2R) 15-9-1 to 24-2-15, Interior(1) 24-2-15 to 25-0-15, Exterior(2E) 25-0-15 to 28-0-15; Lumber DOL=1.60 plate grip DOL=1.60

5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.

6) Provide adequate drainage to prevent water ponding.

7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2792 lb uplift at joint 3 and 2790 lb uplift at joint 8.

9) Girder carries hip end with 5-0-0 end setback.

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 590 lb down and 371 lb up at 20-0-0, and 590 lb down and 371 lb up at 5-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

11) All truss to truss connection by TCI are on the Truss Placement plan.

12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S)

Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33

Uniform Loads (plf)

Vert: 1-4=-90, 4-7=-143(F=-53), 7-10=-90, 3-15=-20, 11-15=-32(F=-12), 8-11=-20

Concentrated Loads (lb)

Vert: 15=-321(F) 11=-321(F)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG6	Half Hip Girder	1	2	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:11 2025 Page 2
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-l2WCeLB1Q_qx6cHjxytq6lYRr4oJ3nhjsXThl2z9LNU

NOTES- (11-12)

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 262 lb down and 319 lb up at 5-0-0, 262 lb down and 319 lb up at 7-0-12, 252 lb down and 319 lb up at 9-0-12, 238 lb down and 319 lb up at 11-0-12, 238 lb down and 319 lb up at 13-0-12, 238 lb down and 319 lb up at 15-0-12, 238 lb down and 319 lb up at 17-0-12, 238 lb down and 319 lb up at 19-0-12, and 241 lb down and 319 lb up at 21-0-12, and 256 lb down and 319 lb up at 23-0-12 on top chord, and 373 lb down and 421 lb up at 5-0-0, 43 lb down and 22 lb up at 7-0-12, 43 lb down and 22 lb up at 9-0-12, 43 lb down and 22 lb up at 11-0-12, 43 lb down and 22 lb up at 13-0-12, 43 lb down and 22 lb up at 15-0-12, 43 lb down and 22 lb up at 17-0-12, 43 lb down and 22 lb up at 19-0-12, and 43 lb down and 22 lb up at 21-0-12, and 43 lb down and 22 lb up at 23-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

11) All truss to truss connection by TCI are on the Truss Placement plan.

12) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33

Uniform Loads (plf)

Vert: 1-4=-90, 4-9=-90, 10-17=-20

Concentrated Loads (lb)

Vert: 4=-83(B) 7=-83(B) 15=-286(B) 6=-83(B) 12=-30(B) 21=-83(B) 22=-83(B) 23=-83(B) 24=-83(B) 25=-83(B) 26=-83(B) 28=-83(B) 29=-30(B) 30=-30(B) 31=-30(B) 32=-30(B) 33=-30(B) 34=-30(B) 35=-30(B) 36=-30(B)

[illegible]

Job	Truss	Truss Type	Qty	Ply	
12715	HG7	HIP GIRDER	1	2	12715 ROLLING ROAD DR, PINECREST, FL.
Trusscorp Int., 9590 NW 89 AVE, Medley, FL			8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:17 2025 Page 2		
			ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-6CtTvPGo?qa4qXktHD_EMZoRQVriTWBbFTw0Whz9LNO		
NOTES- (13-14)					
4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 0-9-1, Exterior(2R) 0-9-1 to 9-2-15, Interior(1) 9-2-15 to 36-10-15, Exterior(2R) 36-10-15 to 45-4-13, Interior(1) 45-4-13 to 46-1-14, Exterior(2E) 46-1-14 to 49-2-13; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60					
5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.					
6) Provide adequate drainage to prevent water ponding.					
7) All plates are MT20 plates unless otherwise indicated.					
8) All plates are 4x6 MT20 unless otherwise indicated.					
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.					
10) Refer to girder(s) for truss to truss connections.					
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2459 lb uplift at joint 3, 5447 lb uplift at joint 20 and 971 lb uplift at joint 14.					
12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 262 lb down and 319 lb up at 5-0-0, 262 lb down and 319 lb up at 7-0-12, 252 lb down and 319 lb up at 9-0-12, 238 lb down and 319 lb up at 11-0-12, 238 lb down and 319 lb up at 13-0-12, 238 lb down and 319 lb up at 15-0-12, 238 lb down and 319 lb up at 17-0-12, 238 lb down and 319 lb up at 19-0-12, 238 lb down and 319 lb up at 21-0-12, 238 lb down and 319 lb up at 23-0-15, 238 lb down and 319 lb up at 25-1-2, 238 lb down and 319 lb up at 27-1-2, 238 lb down and 319 lb up at 29-1-2, 278 lb down and 359 lb up at 31-1-2, 278 lb down and 359 lb up at 33-1-2, 278 lb down and 359 lb up at 35-1-2, 292 lb down and 359 lb up at 37-1-2, and 302 lb down and 359 lb up at 39-1-2, and 302 lb down and 359 lb up at 41-1-14 on top chord, and 373 lb down and 421 lb up at 5-0-0, 43 lb down and 22 lb up at 7-0-12, 43 lb down and 22 lb up at 9-0-12, 43 lb down and 22 lb up at 11-0-12, 43 lb down and 22 lb up at 13-0-12, 43 lb down and 22 lb up at 15-0-12, 43 lb down and 22 lb up at 17-0-12, 43 lb down and 22 lb up at 19-0-12, 43 lb down and 22 lb up at 21-0-12, 43 lb down and 22 lb up at 23-0-15, 43 lb down and 22 lb up at 25-1-2, 43 lb down and 22 lb up at 27-1-2, 43 lb down and 22 lb up at 29-1-2, 43 lb down and 25 lb up at 31-1-2, 43 lb down and 25 lb up at 33-1-2, 43 lb down and 25 lb up at 35-1-2, 43 lb down and 25 lb up at 37-1-2, and 43 lb down and 25 lb up at 39-1-2, and 435 lb down and 482 lb up at 41-1-2 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.					
13) All truss to truss connection by TCI are on the Truss Placement plan.					
14) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826					
LOAD CASE(S) Standard					
1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33					
Uniform Loads (plf)					
Vert: 1-4=-90, 4-13=-90, 13-16=-90, 29-32=-20					
Concentrated Loads (lb)					
Vert: 4=-83(F) 7=-83(F) 13=-83(F) 26=-286(F) 10=-83(F) 17=-286(F) 6=-83(F) 24=-30(F) 18=-30(F) 12=-83(F) 36=-83(F) 37=-83(F) 38=-83(F) 39=-83(F) 40=-83(F) 41=-83(F) 42=-83(F) 43=-83(F) 44=-83(F) 45=-83(F) 46=-83(F) 47=-83(F) 48=-83(F) 50=-30(F) 51=-30(F) 52=-30(F) 53=-30(F) 54=-30(F) 55=-30(F) 56=-30(F) 57=-30(F) 58=-30(F) 59=-30(F) 60=-30(F) 61=-30(F) 62=-30(F) 63=-30(F) 64=-30(F)					

Job

12715

Truss

HG8

Truss Type

HIP GIRDER

Qty

1

Ply

2

12715 ROLLING ROAD DR, PINECREST, FL.

Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:20 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-XnZcXQIglyfh_TSyLYxzCQz8ixmguR2xR9g70z9LNL

-3-0-0

3-0-0

3-2-8

3-2-8

7-0-0

3-9-8

11-2-8

4-2-8

15-5-0

4-2-8

19-2-8

3-9-8

22-5-0

3-2-8

25-5-0

3-0-0

Scale = 1:50.7

3.00

12

6x8 =

5

26

6

27

6x8 =

7

28

9

10

4x10 =

11

25

2

3

2x6 =

1

0-8-12

2-2-15

0-4-3

3x8 =

4

15

29

14

30

13

3x6 =

12

3x4 ||

3x8 =

16

4x10 =

2528##-2438#

3x10 =

2691##-2596#

-0-1-8

0-1-8

3-2-8

3-2-8

7-0-0

3-9-8

11-2-8

4-2-8

15-5-0

4-2-8

19-2-8

3-9-8

22-5-0

3-2-8

22-6-8

0-1-8

PLATE OFFSETS (X,Y)--

[3:0-7-7,0-0-4], [4:0-3-3,0-0-5], [5:0-6-4,0-4-0], [7:0-6-4,0-4-0], [8:0-4-3,0-0-5], [9:0-6-15,Edge], [10:0-3-3,0-0-14], [11:0-0-8,0-4-0], [17:0-2-0,0-1-0], [18:0-2-10,0-0-6]

LOADING (psf)

TCLL 30.0

TCDL 15.0

BCLL 0.0

BCDL 10.0

SPACING-

2-0-0

Plate Grip DOL 1.33

Lumber DOL 1.33

Rep Stress Incr NO

Code FBC2020/TPI2014

CSI.

TC 0.79

BC 0.66

WB 0.72

Matrix-MSH

DEFL.

in (loc)

l/defl

L/d

Vert(LL) 0.45 14-15 >599 360

Vert(CT) -0.44 14-15 >613 180

Horz(CT) 0.10 9 n/a n/a

PLATES

GRIP

MT20

244/190

Weight: 282 lb

FT = 0%

LUMBER-

TOP CHORD 2x6 SP No.2 *Except*

T3: 2x6 SP 2400F 2.0E

BOT CHORD 2x4 SP No.2 *Except*

B2: 2x4 SP No.3, B3: 2x6 SP No.2

WEBS 2x4 SP No.3

OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-11-13 oc purlins.

BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS.

(lb/size) 3=2528/0-8-0 (min. 0-1-8), 9=2691/0-8-0 (min. 0-1-9), 17=0/Mechanical, 18=0/Mechanical

Max Horz 3=2517(LC 1), 17=1533(LC 9), 18=4029(LC 1)

Max Uplift3=2438(LC 4), 9=2596(LC 4)

Max Grav 3=2528(LC 1), 9=2691(LC 1)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1471/1304, 2-3=-1429/1315, 3-25=-4333/4185, 4-25=-4294/4186, 4-5=-7958/7858, 5-26=-8775/8826, 6-26=-8775/8826, 6-27=-8775/8826, 7-27=-8775/8826, 7-8=-7327/7250, 8-28=-4102/4000, 9-28=-4139/3995, 9-10=-3850/3679, 10-11=-3874/3651

BOT CHORD 4-15=-3650/3770, 15-29=-3742/3880, 14-29=-3742/3880, 14-30=-3092/3239, 13-30=-3092/3239, 8-13=-3026/3155, 8-12=-369/391

WEBS 5-15=-685/826, 5-14=-1117/1233, 6-14=-722/890, 7-14=-1731/1876, 7-13=-523/666, 1-17=-1348/1534, 11-18=-3786/4031

NOTES-

(13-14)

1) Special connection required to distribute web loads equally between all plies.

2) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows:
Top chords connected as follows: 2x6 - 3 rows staggered at 0-2-0 oc clinched.
Bottom chords connected as follows: 2x4 - 1 row at 0-9-0 oc clinched, 2x6 - 3 rows staggered at 0-2-0 oc clinched.
Webs connected as follows: 2x4 - 2 rows staggered at 0-2-0 oc clinched, Except member 14-5 2x4 - 1 row at 0-9-0 oc clinched, member 14-7 2x4 - 1 row at 0-9-0 oc clinched.

3) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

4) Unbalanced roof live loads have been considered for this design.

5) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-11 to 0-0-0, Interior(1) 0-0-0 to 2-9-1, Exterior(2R) 2-9-1 to 19-7-15, Interior(1) 19-7-15 to 22-5-0, Exterior(2E) 22-5-0 to 25-5-11; Lumber DOL=1.60 plate grip DOL=1.60

6) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.

7) Provide adequate drainage to prevent water ponding.

8) All plates are 2x4 MT20 unless otherwise indicated.

9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

10) Refer to girder(s) for truss to truss connections.

11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2438 lb uplift at joint 3 and 2596 lb uplift at joint 9.

12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 327 lb down and 368 lb up at 7-0-0, 327 lb down and 368 lb up at 9-0-12, 327 lb down and 368 lb up at 11-0-12, 327 lb down and 368 lb up at 11-4-4, and 327 lb down and 368 lb up at 13-4-4, and 327 lb down and 368 lb up at 15-5-0 on top chord, and 525 lb down and 537 lb up at 7-0-0, 50 lb down and 48 lb up at 9-0-12, 50 lb down and 48 lb up at 11-0-12, 50 lb down and 48 lb up at 11-4-4, and 50 lb down and 48 lb up at 13-4-4, and 525 lb down and 537 lb up at 15-4-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG8	HIP GIRDER	1	2	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:20 2025 Page 2

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-XnZcXQ!gilyfh_TSyLYxzCQz8ixmguR2xR9g70z9LNL

- 13) All truss to truss connection by TCI are on the Truss Placement plan.
- 14) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

- 1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33
- Uniform Loads (plf)
- Vert: 1-4=-90, 4-5=-90, 5-7=-90, 7-8=-90, 8-11=-90, 16-19=-20, 4-8=-20, 12-22=-20
- Concentrated Loads (lb)
- Vert: 5=-162(F) 7=-162(F) 15=-525(F) 14=-90(F) 6=-324(F) 13=-525(F) 26=-162(F) 27=-162(F) 29=-45(F) 30=-45(F)

Job

12715

Truss

HG9

Truss Type

HIP GIRDER

Qty

1

Ply

3

12715 ROLLING ROAD DR, PINECREST, FL.

Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:23 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-xMEkASLYbgKEYSC1eT5ebq2WEV_7tLLUdPOKKLz9LNl

-3-0-0

3-0-0

3-8-0

3-8-0

5-0-0

1-4-0

9-2-4

4-2-4

13-2-12

4-0-8

17-5-0

4-2-4

18-9-0

1-4-0

22-5-0

3-8-0

25-5-0

3-0-0

Scale = 1:50.3

3.00

12

5x10 ||

3x6 ||

3x6 ||

5x10 ||

2x4 ||

2x4 ||

2x6 =

4x14 =

5

23

6

24

7

25

8

4x14 =

2x4 ||

2x4 ||

2x6 =

1

2

22

3

4

17

27

16

28

15

14

29

13

10

26

11

12

0-8-12

0-4-3

0-4-3

0-8-12

0-8-0

2572#/-2915#

2674#/-3027#

-0-1-8

0-1-8

3-8-0

3-8-0

5-0-0

1-4-0

9-2-4

4-2-4

13-2-12

4-0-8

17-5-0

4-2-4

18-9-0

1-4-0

22-5-0

3-8-0

22-6-8

0-1-8

Plate Offsets (X,Y)-- [3:0-11-15,0-0-2], [5:0-4-0,0-2-3], [8:0-4-0,0-2-3], [10:0-11-15,0-0-2], [20:0-2-0,0-1-0], [21:0-2-0,0-0-8]

LOADING (psf)

TCLL 30.0

TCDL 15.0

BCLL 0.0

BCDL 10.0

SPACING-

2-0-0

Plate Grip DOL 1.33

Lumber DOL 1.33

Rep Stress Incr YES

Code FBC2020/TPI2014

CSI.

TC 0.67

BC 0.55

WB 0.26

Matrix-SH

DEFL.

in (loc)

l/defl

L/d

Vert(LL) 0.67 15-16 >372 360

Vert(CT) -0.58 15-16 >431 180

Horz(CT) -0.08 10 n/a n/a

PLATES GRIP

MT20 244/190

Weight: 409 lb FT = 0%

LUMBER-

TOP CHORD 2x6 SP No.1

BOT CHORD 2x6 SP No.1 *Except*

B1: 2x6 SP No.2

WEBS 2x4 SP No.3

OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 9-10-2 oc bracing.

REACTIONS.

(lb/size) 3=2268/0-8-0 (min. 0-1-8), 10=2358/0-8-0 (min. 0-1-8), 20=0/Mechanical, 21=0/Mechanical

Max Horz 3=-1122(LC 4), 20=1430(LC 13), 21=2434(LC 4)

Max Uplift3=-2915(LC 4), 10=-3027(LC 4)

Max Grav 3=2572(LC 14), 10=2674(LC 14)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-1377/1312, 2-22=-1381/1325, 3-22=-1380/1330, 3-4=-2887/3080, 4-5=-9494/10377, 5-23=-9599/10504, 6-23=-9599/10504, 6-24=-9599/10504, 7-24=-9599/10504, 7-25=-9599/10505, 8-25=-9599/10505, 8-9=-9499/10383, 9-10=-2911/3106, 10-26=-2270/2371, 11-26=-2277/2369, 11-12=-2279/2350

BOT CHORD 4-17=-7423/6753, 17-27=-7782/7098, 16-27=-7782/7098, 16-28=-7782/7098, 15-28=-7782/7098, 14-15=-7782/7098, 14-29=-7782/7098, 13-29=-7782/7098, 9-13=-7396/6728

WEBS 5-17=-1558/1496, 8-13=-1678/1606, 1-20=-1343/1431, 12-21=-2435/2369

NOTES-

(12-13)

1) 3-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows:
Top chords connected as follows: 2x6 - 3 rows staggered at 0-4-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Webs connected as follows: 2x4 - 2 rows staggered at 0-4-0 oc.

2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

3) Unbalanced roof live loads have been considered for this design.

4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-0-11 to -0-0-11, Interior(1) -0-0-11 to 0-9-1, Exterior(2R) 0-9-1 to 9-2-4, Interior(1) 9-2-4 to 13-2-1, Exterior(2R) 13-2-1 to 21-7-3, Interior(1) 21-7-3 to 22-5-11, Exterior(2E) 22-5-11 to 25-5-11; Lumber DOL=1.60 plate grip DOL=1.60

5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.

6) Provide adequate drainage to prevent water ponding.

7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

8) Refer to girder(s) for truss to truss connections.

9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2915 lb uplift at joint 3 and 3027 lb uplift at joint 10.

10) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 3, 10.

11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 242 lb down and 211 lb up at 5-0-0, 242 lb down and 211 lb up at 7-0-12, 230 lb down and 211 lb up at 9-0-12, 214 lb down and 211 lb up at 11-2-8, 231 lb down and 211 lb up at 13-4-4, and 242 lb down and 211 lb up at 15-4-4, and 242 lb down and 211 lb up at 17-5-0 on top chord, and 547 lb down and 641 lb up at 5-0-0, 190 lb down and 226 lb up at 7-0-12, 190 lb down and 226 lb up at 9-0-12, 190 lb down and 226 lb up at 11-2-8, 190 lb down and 226 lb up at 13-4-4, and 190 lb down and 226 lb up at 15-4-4, and 547 lb down and 641 lb up at 17-4-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

12) All truss to truss connection by TCI are on the Truss Placement plan.

13) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG9	HIP GIRDER	1	3	Job Reference (optional)

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33

Uniform Loads (plf)

Vert: 1-3=-90, 3-4=-111, 4-5=-90, 5-8=-90, 8-9=-90, 9-10=-111, 10-12=-90, 4-9=-20

Concentrated Loads (lb)

Vert: 5=-6(B) 8=-6(B) 17=-401(B) 6=-6(B) 16=-159(B) 7=-6(B) 15=-159(B) 13=-401(B) 23=-6(B) 24=-6(B) 25=-6(B) 27=-159(B) 28=-159(B) 29=-159(B)

Job

12715

Truss

HG10

Truss Type

HIP GIRDER

Qty

1

Ply

2

12715 ROLLING ROAD DR, PINECREST, FL.

Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:25 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-tkMvA8Mp7HbynLQlu86gF7vVjktLlvn5jtRoEz9LNG

-1-4-4

1-4-4

5-0-0

5-0-0

6-6-0

1-6-0

11-6-0

5-0-0

12-10-4

1-4-4

Scale: 1/2"=1'

4x6 =

4

4x6 =

5

3.00

12

21

22

1

2

3

11

13

10

9

6

7

8

12

0-1-14

0-1-14

0-8-12

0-8-12

1110#/-1438#

1110#/-1438#

-0-1-8

0-1-8

5-0-0

5-0-0

6-6-0

1-6-0

11-6-0

5-0-0

11-7-8

0-1-8

Plate Offsets (X,Y)-- [11:0-1-12,0-1-0], [12:0-1-12,0-1-0], [13:0-2-0,0-1-0], [14:0-2-0,0-0-8]

LOADING (psf)

TCLL 30.0

TCDL 15.0

BCLL 0.0

BCDL 10.0

SPACING-

Plate Grip DOL 1.33

Lumber DOL 1.33

Rep Stress Incr NO

Code FBC2020/TPI2014

CSI.

TC 0.49

BC 0.28

WB 0.07

Matrix-MSH

DEFL.

in (loc)

l/defl

L/d

Vert(LL) 0.08 9-10 >999 360

Vert(CT) -0.07 10 >999 180

Horz(CT) -0.01 6 n/a n/a

PLATES

GRIP

MT20 244/190

Weight: 116 lb FT = 0%

LUMBER-

TOP CHORD 2x4 SP No.2

BOT CHORD 2x6 SP No.2

WEBS 2x4 SP No.3

OTHERS 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 8-10-10 oc bracing.

REACTIONS.

(lb/size) 3=1110/0-8-0 (min. 0-1-8), 6=1110/0-8-0 (min. 0-1-8), 13=0/Mechanical, 14=0/Mechanical

Max Uplift3=-1438(LC 4), 6=-1438(LC 4)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 3-21=-2705/3442, 4-21=-2689/3450, 4-5=-2669/3449, 5-22=-2689/3450, 6-22=-2705/3442

BOT CHORD 3-10=-3176/2553, 9-10=-3214/2594, 6-9=-3176/2553

WEBS 4-10=-363/385, 5-9=-363/385

NOTES-

(12-13)

1) 2-ply truss to be connected together with 16d (0.131"x 3.5") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc clinched.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc clinched.
Webs connected as follows: 2x4 - 2 rows staggered at 0-3-0 oc clinched, Except member 1-11 2x4 - 1 row at 0-9-0 oc clinched, member 2-13 2x4 - 1 row at 0-9-0 oc clinched, member 8-12 2x4 - 1 row at 0-9-0 oc clinched, member 7-14 2x4 - 1 row at 0-9-0 oc clinched.

2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.

3) Unbalanced roof live loads have been considered for this design.

4) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -1-2-8 to 1-9-8, Exterior(2R) 1-9-8 to 9-8-8, Exterior(2E) 9-8-8 to 12-8-8; Lumber DOL=1.60 plate grip DOL=1.60

5) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.

6) Provide adequate drainage to prevent water ponding.

7) All plates are 2x4 MT20 unless otherwise indicated.

8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

9) Refer to girder(s) for truss to truss connections.

10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1438 lb uplift at joint 3 and 1438 lb uplift at joint 6.

11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 305 lb down and 330 lb up at 5-0-0, and 305 lb down and 330 lb up at 6-6-0 on top chord, and 373 lb down and 421 lb up at 5-0-0, and 373 lb down and 421 lb up at 6-5-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

12) All truss to truss connection by TCI are on the Truss Placement plan.

13) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S)

Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33

Uniform Loads (plf)

Vert: 1-4=-90, 4-5=-90, 5-8=-90, 15-18=-20

Concentrated Loads (lb)

Vert: 4=-83(B) 5=-83(B) 10=-286(B) 9=-286(B)

[illegible]

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	HG11T	HIP GIRDER	1	2	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:28 2025 Page 2
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-IJ2dD9OhQCzXeD4_Q0hpttl6werYazDnh55PZz9LND

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.33, Plate Increase=1.33

Uniform Loads (plf)

Vert: 1-4=-90, 4-7=-90, 7-10=-90, 18-21=-20

Concentrated Loads (lb)

Vert: 4=-83(F) 7=-83(F) 13=-30(F) 15=-286(F) 5=-83(F) 14=-30(F) 11=-286(F) 25=-83(F) 27=-83(F) 28=-83(F) 29=-83(F) 31=-30(F) 32=-30(F) 33=-30(F)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J1	Jack-Open	16	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:30 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-Ei9OerQxyqDEuXENYRjHNIropkUL?YVWE?aCTRz9LNB




Plate Offsets (X,Y)-- [1:0-2-7,0-1-1], [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.33		Vert(LL)	-0.01	5	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.07		Vert(CT)	-0.01	5	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.17		Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP							Weight: 14 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD
Structural wood sheathing directly applied or 1-0-0 oc purlins.
Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=-108/Mechanical, 3=496/0-8-0 (min. 0-1-8), 6=-0/Mechanical
Max Horz 3=-337(LC 4), 6=580(LC 4)
Max Uplift 4=-110(LC 5), 3=-881(LC 4)
Max Grav 4=203(LC 4), 3=531(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-539/334, 2-3=-541/352
WEBS 1-6=-325/581

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 110 lb uplift at joint 4 and 881 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J1A	JACK-OPEN	26	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:33 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-eHrWGtSqElbpl_zyDaH_?xTJvxW5Cunywzps4mz9LN8




Plate Offsets (X,Y)-- [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.34		Vert(LL)	0.00	5	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.07		Vert(CT)	0.00	5	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.20		Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP							Weight: 13 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied or 1-0-0 oc purlins.
Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=-127/Mechanical, 3=512/0-8-0 (min. 0-1-8), 6=0/Mechanical
Max Horz 3=-495(LC 4), 6=676(LC 4)
Max Uplift4=-132(LC 5), 3=-916(LC 4)
Max Grav4=242(LC 4), 3=551(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-645/387, 2-3=-649/395
WEBS 1-6=-385/677

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 132 lb uplift at joint 4 and 916 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J2	JACK-OPEN	16	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:36 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-3sWfuvVIXgzOcShXuiqhdZ5sG9VQPigOcw1Wh5z9LN5



Scale = 1:9.6

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.14	Vert(LL)	-0.00	6	n/r	180	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.22	Vert(CT)	-0.00	6	n/r	80		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00		n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						Weight: 6 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied or 2-0-0 oc purlins.
Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=178/Mechanical, 3=46/Mechanical
Max Horz 2=-317(LC 4), 3=438(LC 4)
Max Uplift2=-276(LC 4), 3=-48(LC 4)
Max Grav2=190(LC 5), 3=51(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-392/308
BOT CHORD 1-3=-309/438

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 276 lb uplift at joint 2 and 48 lb uplift at joint 3.
 - 6) Non Standard bearing condition. Review required.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J2A	JACK-OPEN	26	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:39 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-TRCoWwXbqbLzTvQ6aqOOFcJNKMxXcfPrJuGAIQz9LN2



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.15	Vert(LL)	-0.00	6	n/r	180	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.23	Vert(CT)	-0.00	6	n/r	80	
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00		n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP						
								Weight: 6 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied or 2-0-0 oc purlins. Rigid ceiling directly applied or 6-0-0 oc bracing.
		MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=173/Mechanical, 3=50/Mechanical
Max Horz 2=-428(LC 4), 3=519(LC 4)
Max Uplift2=-269(LC 4), 3=-53(LC 4)
Max Grav 2=186(LC 5), 3=54(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-484/373
BOT CHORD 1-3=-374/519

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 269 lb uplift at joint 2 and 53 lb uplift at joint 3.
 - 6) Non Standard bearing condition. Review required.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J3	Jack-Open	6	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:40 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-xdmAkGYDbuUq53?i7YvdnPFVumvsL41_XY?qksz9LN1




Plate Offsets (X,Y)-- [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.35		Vert(LL)	-0.00	5-9	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.06		Vert(CT)	-0.00	5-9	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.17		Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP							Weight: 20 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied or 3-0-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.
--	---	---

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=88/Mechanical, 3=498/0-8-0 (min. 0-1-8), 5=17/Mechanical, 6=-0/Mechanical
Max Horz 3=270(LC 1), 6=565(LC 4)
Max Uplift4=-184(LC 4), 3=-820(LC 4)
Max Grav4=106(LC 5), 3=525(LC 5), 5=46(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-525/327, 2-3=-528/345
WEBS 1-6=-314/566

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 184 lb uplift at joint 4 and 820 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J3A	Jack-Open	12	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:42 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-u0uw9yZT7WkXKN9hFzx5sqLrYaa6py1H?sUqviz9LN?




Plate Offsets (X,Y)-- [1:0-2-6,0-1-8], [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	2-0-0	TC 0.34	Vert(LL)	-0.00	5-9	>999	360	MT20	244/190
TCDL 15.0	Plate Grip DOL 1.33	BC 0.07	Vert(CT)	-0.00	5-9	>999	180		
BCLL 0.0	Lumber DOL 1.33	WB 0.20	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP						Weight: 19 lb	FT = 0%
	Code FBC2020/TPI2014								

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD
BOT CHORD 2x4 SP No.2	BOT CHORD
OTHERS 2x4 SP No.3	Structural wood sheathing directly applied or 3-0-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.
	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=84/Mechanical, 3=500/0-8-0 (min. 0-1-8), 5=16/Mechanical, 6=-0/Mechanical
Max Horz 3=-403(LC 4), 6=671(LC 4)
Max Uplift4=-165(LC 4), 3=-839(LC 4)
Max Grav 4=98(LC 5), 3=534(LC 5), 5=45(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-641/379, 2-3=-645/391
WEBS 1-6=-377/673

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 165 lb uplift at joint 4 and 839 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J3AT	JACK-OPEN	12	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:44 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-qO?haebkf7_FZgl3MNzZyFQA7NGNHs0aSAzxydz9LMz




Plate Offsets (X,Y)--	[6:0-2-0,0-1-0]
-----------------------	-----------------

LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 1.33	TC 0.40	Vert(LL) -0.00	5-9	>999	360		MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.09	Vert(CT) -0.00	5-9	>999	180			
BCLL 0.0	Rep Stress Incr YES	WB 0.23	Horz(CT) 0.00	3	n/a	n/a			
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MP						Weight: 19 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied or 3-0-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.
--	---	---

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=84/Mechanical, 3=500/0-8-0 (min. 0-1-8), 5=16/Mechanical, 6=-0/Mechanical
Max Horz 3=-473(LC 4), 6=785(LC 4)
Max Uplift 4=-193(LC 4), 3=-985(LC 4)
Max Grav 4=126(LC 5), 3=679(LC 5), 5=45(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-749/487, 2-3=-755/498
WEBS 1-6=-491/786

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 193 lb uplift at joint 4 and 985 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J3B	JACK-OPEN	2	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:46 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-mn7R_Jc_AkEzp_SSUo011gVS5ByVlp8twUS21Wz9LMx




Plate Offsets (X,Y)-- [3:0-5-5,0-0-12], [6:0-2-14,0-1-1], [7:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.69		Vert(LL)	-0.00	5-10	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.11		Vert(CT)	-0.01	5-10	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00		Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-MP							Weight: 17 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD
BOT CHORD 2x4 SP No.2	BOT CHORD
WEBS 2x4 SP No.3	Structural wood sheathing directly applied or 3-0-0 oc purlins.
OTHERS 2x4 SP No.3	Rigid ceiling directly applied or 10-0-0 oc bracing.
	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=81/Mechanical, 3=418/0-8-0 (min. 0-1-8), 5=13/Mechanical, 7=0/Mechanical
Max Horz 3=261(LC 4)
Max Uplift4=-184(LC 4), 3=-810(LC 4)
Max Grav4=122(LC 5), 3=564(LC 5), 5=45(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 184 lb uplift at joint 4 and 810 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J3T	JACK-OPEN	9	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:48 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-i9FBP?eEiMUh2lcqbD2V65att_ekDh09Nox95Oz9LMv




Plate Offsets (X,Y)-- [1:0-1-14,0-1-0], [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 1.33	TC 0.35	Vert(LL)	-0.00	5-9	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.06	Vert(CT)	-0.00	5-9	>999	180		
BCLL 0.0	Rep Stress Incr YES	WB 0.17	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-MP						Weight: 20 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied or 3-0-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.
--	---	---

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=88/Mechanical, 3=497/0-8-0 (min. 0-1-8), 5=17/Mechanical, 6=-0/Mechanical
Max Horz 3=270(LC 1), 6=565(LC 4)
Max Uplift4=-184(LC 4), 3=-820(LC 4)
Max Grav4=106(LC 5), 3=525(LC 5), 5=46(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-525/327, 2-3=-528/345
WEBS 1-6=-314/566

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 184 lb uplift at joint 4 and 820 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J3TA	JACK-OPEN	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:49 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-AMpadLfsTfcYgRB19xZkfJ70cOztyAuJcShidrz9LMu




Plate Offsets (X,Y)-- [3:Edge,0-0-10], [6:0-2-15,0-0-9], [7:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	30.0	2-0-0	TC	0.48	Vert(LL)	-0.00	5-10	>999	360	MT20	244/190
TCDL	15.0	Plate Grip DOL	BC	0.06	Vert(CT)	-0.01	5-10	>999	180		
BCLL	0.0	Lumber DOL	WB	0.00	Horz(CT)	0.00	4	n/a	n/a		
BCDL	10.0	Rep Stress Incr	Matrix-MP							Weight: 17 lb	FT = 0%
		Code FBC2020/TPI2014									

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD
BOT CHORD 2x4 SP No.2	BOT CHORD
WEBS 2x4 SP No.3	Structural wood sheathing directly applied or 3-0-0 oc purlins.
OTHERS 2x4 SP No.3	Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings Mechanical except (jt=length) 3=0-8-0, 7=Mechanical.
(lb) - Max Horz 3=285(LC 4)
Max Uplift All uplift 100 lb or less at joint(s) except 4=-187(LC 4), 3=-605(LC 4)
Max Grav All reactions 250 lb or less at joint(s) 4, 5, 5 except 3=398(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (7-8)
1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) Refer to girder(s) for truss to truss connections.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 187 lb uplift at joint 4 and 605 lb uplift at joint 3.
7) All truss to truss connection by TCI are on the Truss Placement plan.
8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J5	Jack-Open	9	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:51 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-7kwK21g7?HsGvILPHMbCkkCICCcTQ2Mc3mApijz9LMs




Plate Offsets (X,Y)-- [3:0-1-8,0-1-8], [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.67		Vert(LL)	0.04	5-9	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.31		Vert(CT)	-0.05	5-9	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.13		Horz(CT)	-0.01	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 26 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied. Rigid ceiling directly applied.
		MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=175/Mechanical, 3=597/0-8-0 (min. 0-1-8), 5=50/Mechanical, 6=0/Mechanical
Max Horz 3=205(LC 1), 6=433(LC 4)
Max Uplift4=-406(LC 4), 3=-943(LC 4), 5=-12(LC 4)
Max Grav 4=207(LC 5), 3=626(LC 5), 5=83(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-402/266, 2-3=-402/282
WEBS 1-6=-233/434

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 0-8-5, Exterior(2R) 0-8-5 to 4-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 406 lb uplift at joint 4, 943 lb uplift at joint 3 and 12 lb uplift at joint 5.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J5A	Jack-Open	25	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:54 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-XJcSg2j?lCEqmD3_yU9vMMqqCPdNdPj2lkOTJ2z9LMp




Plate Offsets (X,Y)-- [1:0-2-6,0-1-9], [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.62		Vert(LL)	0.04	5-9	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.30		Vert(CT)	-0.04	5-9	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.15		Horz(CT)	-0.01	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 25 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
OTHERS 2x4 SP No.3	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=173/Mechanical, 3=597/0-8-0 (min. 0-1-8), 5=50/Mechanical, 6=0/Mechanical
Max Horz 3=254(LC 1), 6=519(LC 4)
Max Uplift4=-381(LC 4), 3=-985(LC 4), 5=-12(LC 4)
Max Grav4=198(LC 5), 3=634(LC 5), 5=83(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-496/300, 2-3=-497/314
WEBS 1-6=-284/520

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 0-4-12, Exterior(2R) 0-4-12 to 4-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 381 lb uplift at joint 4, 985 lb uplift at joint 3 and 12 lb uplift at joint 5.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J5AT	JACK-OPEN	22	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:56 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-TikD5kkFqpVY?WDN3vBNRnw8BDIF5JoLD2taNxz9LMn




Plate Offsets (X,Y)-- [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.71		Vert(LL)	0.05	5-9	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.34		Vert(CT)	-0.04	5-9	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.18		Horz(CT)	-0.01	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 25 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
OTHERS 2x4 SP No.3	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=173/Mechanical, 3=597/0-8-0 (min. 0-1-8), 5=50/Mechanical, 6=0/Mechanical
Max Horz 3=254(LC 1), 6=610(LC 4)
Max Uplift4=-439(LC 4), 3=-1153(LC 4), 5=-16(LC 4)
Max Grav4=255(LC 5), 3=802(LC 5), 5=83(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-582/377, 2-3=-585/385
WEBS 1-6=-375/611

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 0-4-12, Exterior(2R) 0-4-12 to 4-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 439 lb uplift at joint 4, 1153 lb uplift at joint 3 and 16 lb uplift at joint 5.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J5B	Jack-Open	2	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:43:58 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-Q5szWQmWLQIGFqNIBKDrWC?Wz02gZD?egLMhSpz9LM




Plate Offsets (X,Y)-- [4:0-5-0,0-2-4], [8:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.63		Vert(LL)	0.12	7	>488	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.08		Vert(CT)	0.10	4	>564	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.14		Horz(CT)	-0.04	6	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 25 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied.
B2: 2x4 SP No.3	
OTHERS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=183/Mechanical, 3=594/0-8-0 (min. 0-1-8), 6=24/Mechanical, 8=0/Mechanical
Max Horz 3=223(LC 1), 8=456(LC 4)
Max Uplift5=-375(LC 4), 3=-984(LC 4)
Max Grav5=209(LC 5), 3=631(LC 5), 6=48(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-435/271, 2-3=-436/284
WEBS 1-8=-248/457

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 0-4-12, Exterior(2R) 0-4-12 to 4-9-2; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 375 lb uplift at joint 5 and 984 lb uplift at joint 3.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J5C	JACK-OPEN	7	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:00 2025 Page 1
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-MTzKx6nmt2?_U8X8lIGJbd4oTqav18cw8frnWiz9LMj




Plate Offsets (X,Y)-- [1:0-0-6,0-0-13], [2:0-2-4,0-2-12], [5:Edge,0-1-8]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.89		Vert(LL)	0.13	5	>442	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.67		Vert(CT)	0.12	5	>499	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00		Horz(CT)	-0.08	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 18 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2 *Except*
B2: 2x4 SP No.3, B3: 2x6 SP No.2

BRACING-
TOP CHORD
BOT CHORD
Structural wood sheathing directly applied.
Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=272/0-8-0 (min. 0-1-8), 3=92/Mechanical, 4=179/Mechanical
Max Horz 1=256(LC 4)
Max Uplift1=-420(LC 4), 3=-194(LC 4), 4=-310(LC 4)
Max Grav 1=343(LC 5), 3=133(LC 5), 4=249(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (7-8)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 420 lb uplift at joint 1, 194 lb uplift at joint 3 and 310 lb uplift at joint 4.
 - 6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J5E	Jack-Open	2	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:01 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-qfX68SoOeL7r6I6KsSnY8rd02E3CmZn4MJbL28z9LMi




Plate Offsets (X,Y)--	[8:0-2-0,0-1-0]
-----------------------	-----------------

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.64		Vert(LL)	0.13	7	>440	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.09		Vert(CT)	0.12	7	>508	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.13		Horz(CT)	-0.06	6	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 28 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied.
B2: 2x4 SP No.3, B3: 2x6 SP No.2	
OTHERS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=199/Mechanical, 3=602/0-8-0 (min. 0-1-8), 6=19/Mechanical, 8=-0/Mechanical
Max Horz 3=218(LC 1), 8=448(LC 4)
Max Uplift5=-392(LC 4), 3=-996(LC 4)
Max Grav5=226(LC 5), 3=640(LC 5), 6=38(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-428/266, 2-3=-429/278
WEBS 1-8=-242/449

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 0-4-12, Exterior(2R) 0-4-12 to 4-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 392 lb uplift at joint 5 and 996 lb uplift at joint 3.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J5T	JACK-OPEN	13	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:03 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-m2fsZ7qeAzNZLbFj_tp0DGiKU1hdET?Nqd4S71z9LMg




Plate Offsets (X,Y)-- [3:0-0-4,0-0-12], [6:0-2-0,0-1-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 2-0-0	TC 0.77	Vert(LL) 0.05	5-9	>999	360		MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.35	Vert(CT) -0.05	5-9	>999	180			
BCLL 0.0	Rep Stress Incr YES	WB 0.15	Horz(CT) -0.01	4	n/a	n/a			
BCDL 10.0	Code FBC2020/TPI2014	Matrix-AS						Weight: 26 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 OTHERS 2x4 SP No.3	BRACING- TOP CHORD Structural wood sheathing directly applied. BOT CHORD Rigid ceiling directly applied.
--	---

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=175/Mechanical, 3=597/0-8-0 (min. 0-1-8), 5=50/Mechanical, 6=0/Mechanical
Max Horz 3=205(LC 1), 6=508(LC 4)
Max Uplift4=-468(LC 4), 3=-1108(LC 4), 5=-16(LC 4)
Max Grav4=268(LC 5), 3=790(LC 5), 5=83(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-472/312, 2-3=-474/322
WEBS 1-6=-309/509

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 0-8-5, Exterior(2R) 0-8-5 to 4-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 468 lb uplift at joint 4, 1108 lb uplift at joint 3 and 16 lb uplift at joint 5.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J7	JACK-OPEN	2	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:04 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-EEDEmTqGxGVQzIqvXaKFITFdOR1kzv1W2Hp?fTz9LMf




Plate Offsets (X,Y)-- [3:0-0-14,Edge], [7:0-3-0,0-0-8], [8:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.32		Vert(LL)	-0.05	7-11	>999	360	MT20
TCDL 15.0	Lumber DOL	1.33	BC 0.36		Vert(CT)	-0.11	7-11	>742	180	244/190
BCLL 0.0	Rep Stress Incr	YES	WB 0.23		Horz(CT)	-0.00	7	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 35 lb FT = 0%

LUMBER- TOP CHORD 2x4 SP No.1 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD Structural wood sheathing directly applied. Rigid ceiling directly applied. MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
--	--

REACTIONS. (lb/size) 5=26/Mechanical, 3=687/0-8-0 (min. 0-1-8), 8=0/Mechanical, 7=331/Mechanical
Max Horz 3=181(LC 1), 8=466(LC 4)
Max Uplift5=-102(LC 4), 3=-907(LC 4), 7=-478(LC 4)
Max Grav5=28(LC 5), 3=687(LC 1), 7=356(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-433/244, 2-3=-434/260, 3-12=-373/353, 4-12=-331/360
BOT CHORD 3-7=-586/349
WEBS 1-8=-201/467, 4-7=-458/768

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-0-0, Interior(1) 0-0-0 to 2-8-5, Exterior(2R) 2-8-5 to 6-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 102 lb uplift at joint 5, 907 lb uplift at joint 3 and 478 lb uplift at joint 7.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J7D	Jack-Open	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:05 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-iRnd_prviadHbvP65lrUlhnlrMyiMHgHxZYCvz9LMe




Plate Offsets (X,Y)-- [3:0-0-4,0-0-14], [7:0-3-0,0-0-8], [8:0-2-11,0-1-0], [9:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.46		Vert(LL)	-0.07	7-12	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.43		Vert(CT)	-0.14	7-12	>566	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.23		Horz(CT)	0.01	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 33 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD Structural wood sheathing directly applied. Rigid ceiling directly applied.
--	---

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=22/Mechanical, 3=567/0-8-0 (min. 0-1-8), 9=0/Mechanical, 7=344/Mechanical
Max Horz 3=498(LC 4)
Max Uplift5=-92(LC 4), 3=-739(LC 4), 7=-504(LC 4)
Max Grav5=22(LC 1), 3=567(LC 1), 7=378(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-13=-377/314, 13-14=-316/320, 4-14=-309/327
BOT CHORD 3-7=-559/334
WEBS 4-7=-460/769

- NOTES-** (9-10)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ: TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 2-8-5, Exterior(2R) 2-8-5 to 6-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 92 lb uplift at joint 5, 739 lb uplift at joint 3 and 504 lb uplift at joint 7.
 - 8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 9) All truss to truss connection by TCI are on the Truss Placement plan.
 - 10) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J7E	Jack-Open	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:07 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-fpuNPvt9EBt_qDZUDjuyN6t4zf16AGUyIF2fGoz9LMc




Plate Offsets (X,Y)-- [5:0-3-0,0-0-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 2-0-0	TC 0.49	Vert(LL)	-0.07	5-8	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.45	Vert(CT)	-0.16	5-8	>528	180		
BCLL 0.0	Rep Stress Incr YES	WB 0.25	Horz(CT)	-0.01	1	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-AS						Weight: 25 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied. Rigid ceiling directly applied.
--	---	--

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=375/0-8-0 (min. 0-1-8), 3=3/Mechanical, 5=386/Mechanical
Max Horz 1=386(LC 4)
Max Uplift1=-425(LC 4), 3=-33(LC 4), 5=-562(LC 4)
Max Grav 1=375(LC 1), 3=3(LC 1), 5=422(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-394/376
BOT CHORD 1-5=-604/373
WEBS 2-5=-513/831

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 425 lb uplift at joint 1, 33 lb uplift at joint 3 and 562 lb uplift at joint 5.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J7F	Jack-Open	6	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:09 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-bC07pBuPmp7i3WjtK8wQSXyR9SjzeD0FCZXmLhz9LMa




Plate Offsets (X,Y)-- [3:0-1-12,Edge], [8:0-2-8,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.44		Vert(LL)	0.10	15	>872	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.42		Vert(CT)	-0.08	15	>999	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.05		Horz(CT)	-0.02	7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 40 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied.
B2: 2x4 SP No.3	
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
OTHERS 2x4 SP No.3	

REACTIONS. (lb/size) 6=252/Mechanical, 3=716/0-8-0 (min. 0-1-8), 7=65/Mechanical, 9=0/Mechanical
Max Horz 3=280(LC 4), 9=141(LC 3)
Max Uplift6=-447(LC 4), 3=-993(LC 4), 7=-49(LC 4)
Max Grav6=267(LC 5), 3=716(LC 1), 7=75(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (8-9)

- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-11 to 0-0-0, Interior(1) 0-0-0 to 2-7-0, Exterior(2R) 2-7-0 to 6-11-4; Lumber DOL=1.60 plate grip DOL=1.60
- 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) Refer to girder(s) for truss to truss connections.
- 5) Refer to girder(s) for truss to truss connections.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 447 lb uplift at joint 6, 993 lb uplift at joint 3 and 49 lb uplift at joint 7.
- 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 8) All truss to truss connection by TCI are on the Truss Placement plan.
- 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J7T	JACK-OPEN	3	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:09 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-bC07pBuPmp7i3WjtK8wQSXyS4Skve9eFCZXmLhz9LMa




Plate Offsets (X,Y)-- [3:0-0-14,Edge], [7:0-3-0,0-0-8], [8:0-2-0,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.38		Vert(LL)	-0.05	7-11	>999	360	MT20
TCDL 15.0	Lumber DOL	1.33	BC 0.36		Vert(CT)	-0.11	7-11	>742	180	244/190
BCLL 0.0	Rep Stress Incr	YES	WB 0.27		Horz(CT)	-0.01	7	n/a	n/a	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 35 lb FT = 0%

LUMBER- TOP CHORD 2x4 SP No.1 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD Structural wood sheathing directly applied. Rigid ceiling directly applied.
--	---

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=26/Mechanical, 3=687/0-8-0 (min. 0-1-8), 8=0/Mechanical, 7=331/Mechanical
Max Horz 3=181(LC 1), 8=544(LC 4)
Max Uplift5=-115(LC 4), 3=-1091(LC 4), 7=-569(LC 4)
Max Grav5=41(LC 5), 3=859(LC 5), 7=446(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-505/284, 2-3=-507/293, 3-12=-373/420, 4-12=-336/427
BOT CHORD 3-7=-690/454
WEBS 1-8=-278/544, 4-7=-594/904

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-1-3 to 0-0-0, Interior(1) 0-0-0 to 2-8-5, Exterior(2R) 2-8-5 to 6-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) Refer to girder(s) for truss to truss connections.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 115 lb uplift at joint 5, 1091 lb uplift at joint 3 and 569 lb uplift at joint 7.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J7TB	JACK-OPEN	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:13 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-TzGefYxwp1e8Y80eZz?MdN76i34_azir7BVzUSz9LMWV




Plate Offsets (X,Y)-- [2:0-0-6,Edge], [6:0-3-0,0-0-8]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.47		Vert(LL)	0.09	6-9	>933	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.42		Vert(CT)	-0.14	6-9	>581	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.26		Horz(CT)	-0.01	6	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 26 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD
Structural wood sheathing directly applied.
Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 4=5/Mechanical, 2=437/0-8-0 (min. 0-1-8), 6=382/Mechanical
Max Horz 2=452(LC 4)
Max Uplift4=-63(LC 4), 2=-575(LC 4), 6=-572(LC 4)
Max Grav 4=5(LC 1), 2=437(LC 1), 6=417(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-10=-413/427, 10-11=-380/427, 3-11=-371/435
BOT CHORD 2-6=-677/408
WEBS 3-6=-534/887

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ: TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -0-7-14 to 2-4-2, Interior(1) 2-4-2 to 2-8-5, Exterior(2R) 2-8-5 to 6-11-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 63 lb uplift at joint 4, 575 lb uplift at joint 2 and 572 lb uplift at joint 6.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	J7TC	JACK-OPEN	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:14 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-yAp0tuyYaLm?AHbq7hWb9afHMTQAJRB_MrEX0uz9LMV




Plate Offsets (X,Y)-- [2-0-2-0,0-0-4], [5-0-3-0,0-0-8]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.48		Vert(LL)	0.09	5-8	>876	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.42		Vert(CT)	-0.14	5-8	>576	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.25		Horz(CT)	-0.01	5	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 25 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied. Rigid ceiling directly applied.
--	---	--

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=375/0-8-0 (min. 0-1-8), 3=3/Mechanical, 5=387/Mechanical
Max Horz 1=386(LC 4)
Max Uplift1=-435(LC 4), 3=-43(LC 4), 5=-541(LC 4)
Max Grav 1=375(LC 1), 3=4(LC 5), 5=416(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-416/415
BOT CHORD 1-5=-639/406
WEBS 2-5=-532/838

- NOTES-** (8-9)
- 1) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 3) This truss is not designed to support a ceiling and is not intended for use where aesthetics are a consideration.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) Refer to girder(s) for truss to truss connections.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 435 lb uplift at joint 1, 43 lb uplift at joint 3 and 541 lb uplift at joint 5.
 - 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

[illegible]

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T2	Common	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:18 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-qx3XiG?2eaGQevvbMWaXKQqv64jDFERaHTCk9fz9LMR




Plate Offsets (X,Y)-- [14:0-2-0,0-1-0], [15:0-2-0,0-0-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.75	Vert(LL)	0.20 10-12	>999	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.73	Vert(CT)	-0.32 10-12	>794	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.23	Horz(CT)	0.07 7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS						
								Weight: 104 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=1457/0-8-0 (min. 0-1-11), 14=-0/Mechanical, 15=0/Mechanical, 7=1281/0-8-0 (min. 0-1-8)
Max Horz 3=-338(LC 4), 14=395(LC 4)
Max Uplift 3=-1185(LC 4), 7=-1022(LC 4)
Max Grav 3=1457(LC 1), 7=1281(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-367/332, 2-3=-366/349, 3-4=-2554/1929, 4-22=-2235/1745, 5-22=-2163/1754, 5-23=-2184/1781, 6-23=-2256/1771, 6-24=-2498/1964, 7-24=-2582/1950
BOT CHORD 3-12=-1662/2340, 11-12=-1118/1659, 10-11=-1118/1659, 7-10=-1700/2370
WEBS 5-10=-372/649, 6-10=-476/485, 5-12=-337/620, 4-12=-460/465, 1-14=-275/396

- NOTES-** (9-10)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 7-8-0, Exterior(2R) 7-8-0 to 13-8-0, Interior(1) 13-8-0 to 19-7-0, Exterior(2E) 19-7-0 to 22-7-0; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1185 lb uplift at joint 3 and 1022 lb uplift at joint 7.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T3	Common	6	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:20 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAxzKvJz-mJBI7x1JABW8uC3_Txd?PrvFXuOej8qtknhrDYz9LMP




Plate Offsets (X,Y)-- [7:0-0-0,0-0-11], [11:0-2-0,0-1-0]												
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d			PLATES GRIP			
TCLL	30.0	Plate Grip DOL	1.33	TC	0.75	Vert(LL)	0.20	8-10	>999	360	MT20	244/190
TCDL	15.0	Lumber DOL	1.33	BC	0.74	Vert(CT)	-0.32	8-10	>805	180		
BCLL	0.0	Rep Stress Incr	YES	WB	0.24	Horz(CT)	0.07	7	n/a	n/a		
BCDL	10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 98 lb	FT = 0%

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied.
BOT CHORD	2x4 SP No.2	BOT CHORD	Rigid ceiling directly applied.
WEBS	2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.	
OTHERS	2x4 SP No.3		
WEDGE			
Right: 2x2 SP No.3			

REACTIONS. (lb/size) 3=1460/0-8-0 (min. 0-1-12), 11=0/Mechanical, 7=1166/0-8-0 (min. 0-1-8)
Max Horz 3=-300(LC 4), 11=395(LC 4)
Max Uplift 3=-1193(LC 4), 7=-912(LC 4)
Max Grav 3=1460(LC 1), 7=1166(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-367/332, 2-3=-366/349, 3-4=-2563/1950, 4-18=-2243/1765, 5-18=-2172/1774, 5-19=-2208/1836,
6-19=-2282/1827, 6-20=-2532/2033, 7-20=-2612/2018
BOT CHORD 3-10=-1720/2348, 9-10=-1178/1669, 8-9=-1178/1669, 7-8=-1811/2402
WEBS 5-8=-416/669, 6-8=-489/517, 5-10=-333/620, 4-10=-460/466, 1-11=-276/396

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 7-8-0, Exterior(2R) 7-8-0 to 13-8-0, Interior(1) 13-8-0 to 18-4-0, Exterior(2E) 18-4-0 to 21-4-0; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1193 lb uplift at joint 3 and 912 lb uplift at joint 7.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T4	COMMON	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:22 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-jil2Yd2Zioms7WCNbmFTUG?Xdi59Bs3AB4AyIQz9LMN



LOADING (psf)						SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL	30.0					Plate Grip DOL	1.33	TC	0.97	Vert(LL)	0.14	10-11	>999	360	MT20	244/190	
TCDL	15.0					Lumber DOL	1.33	BC	0.67	Vert(CT)	-0.22	10-11	>999	180			
BCLL	0.0					Rep Stress Incr	YES	WB	0.96	Horz(CT)	0.05	9	n/a	n/a			
BCDL	10.0					Code FBC2020/TPI2014		Matrix-AS							Weight: 110 lb FT = 0%		

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied. Rigid ceiling directly applied. 1 Row at midpt 4-10
BOT CHORD	2x4 SP No.2	BOT CHORD	
WEBS	2x4 SP No.3	WEBS	
OTHERS	2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.	

REACTIONS. (lb/size) 3=1443/0-8-0 (min. 0-1-11), 9=1175/0-8-0 (min. 0-1-8), 12=0/Mechanical
Max Horz 3=233(LC 9), 12=342(LC 4)
Max Uplift 3=-1141(LC 4), 9=-988(LC 4)
Max Grav 3=1443(LC 1), 9=1175(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-318/292, 2-3=-316/309, 3-4=-2403/1684, 4-5=-1332/1069, 5-16=-1234/1078, 6-16=-1220/1088, 6-17=-1206/1069, 17-18=-1234/1056, 7-18=-1298/1055
BOT CHORD 3-11=-1648/2184, 10-11=-1648/2184
WEBS 4-11=0/255, 4-10=-1137/828, 6-10=0/278, 7-10=-930/1248, 7-9=-1122/1016, 1-12=-233/343

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 11-0-12, Exterior(2R) 11-0-12 to 17-0-12, Interior(1) 17-0-12 to 18-4-0, Exterior(2E) 18-4-0 to 21-4-0; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1141 lb uplift at joint 3 and 988 lb uplift at joint 9.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T4A	Common	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:24 2025 Page 1

ID_ GLN6EJBZ1GCD23RDL_tAxzKvJz-f5QozJ4pEQ0aMqMlinhxZh4yLVqnfubTfOf3NJz9LML




Plate Offsets (X,Y)-- [11:0-3-0,0-3-0], [12:0-5-0,0-3-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 30.0	2-0-0	TC 0.64	in (loc) l/defl L/d	MT20	244/190
TCDL 15.0	Plate Grip DOL 1.33	BC 0.47	Vert(LL) 0.06 13 >999 360		
BCLL 0.0	Lumber DOL 1.33	WB 0.51	Vert(CT) -0.12 12-13 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS	Horz(CT) 0.02 11 n/a n/a		
	Code FBC2020/TPI2014			Weight: 120 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	WEBS 1 Row at midpt 4-12
OTHERS 2x4 SP No.3	


MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=1037/0-8-0 (min. 0-1-8), 11=1752/0-8-0 (min. 0-2-1), 10=-170/0-8-0 (min. 0-1-8), 14=0/Mechanical
Max Horz 3=203(LC 1), 14=320(LC 4)
Max Uplift3=-817(LC 4), 11=-1397(LC 4), 10=-320(LC 9)
Max Grav 3=1037(LC 1), 11=1752(LC 1), 10=85(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-297/265, 2-3=-295/281, 3-4=-1255/768, 7-20=-329/595, 20-21=-334/531, 8-21=-341/525
BOT CHORD 3-13=-787/1103, 12-13=-787/1103, 11-12=-498/415
WEBS 4-13=0/290, 4-12=-1225/946, 6-12=-405/375, 8-11=-563/470, 8-10=-60/356, 1-15=-204/320, 14-15=-203/320, 7-11=-1408/1196, 7-12=-720/1020

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 11-0-12, Exterior(2R) 11-0-12 to 17-0-12, Interior(1) 17-0-12 to 18-4-0, Exterior(2E) 18-4-0 to 21-4-0; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 817 lb uplift at joint 3, 1397 lb uplift at joint 11 and 320 lb uplift at joint 10.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard



LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T7	Common	9	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:27 2025 Page 1

ID:_GLN6EJBZ1GCD23RDL_tAzKvJz-3g6xbL6IWLP9DH5KOVfEBKiQJofmsJ36VLmujze9LMI

-3-0-0
5-1-14
10-0-5
14-10-12
20-0-10
23-0-10

3-0-0
5-1-14
4-10-7
4-10-7
5-1-14
3-0-0




Plate Offsets (X,Y)-- [13:0-2-0,0-1-0], [14:0-2-0,0-0-8]										
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d			PLATES	GRIP
TCLL	30.0	Plate Grip DOL	1.33	TC	0.78	Vert(LL)	0.20 10-12	>999	360	MT20 244/190
TCDL	15.0	Lumber DOL	1.33	BC	0.78	Vert(CT)	-0.30 10-12	>808	180	
BCLL	0.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.07 7	n/a	n/a	
BCDL	10.0	Code FBC2020/TPI2014		Matrix-AS						Weight: 103 lb FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied. Rigid ceiling directly applied.
		MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=1375/0-8-0 (min. 0-1-10), 13=-0/Mechanical, 14=-0/Mechanical, 7=1388/0-8-0 (min. 0-1-10)
Max Horz 3=279(LC 9), 13=400(LC 4), 14=-297(LC 4)
Max Uplift 3=-1148(LC 4), 7=-1159(LC 4)
Max Grav 3=1375(LC 1), 7=1388(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-371/330, 2-3=-371/347, 3-4=-2339/1801, 4-21=-2046/1631, 5-21=-1981/1641, 5-22=-1950/1616, 6-22=-2014/1606, 6-7=-2298/1769, 7-8=-273/250, 8-9=-276/234
BOT CHORD	3-12=-1782/2281, 11-12=-1282/1659, 10-11=-1282/1659, 7-10=-1747/2236
WEBS	5-10=-277/539, 6-10=-403/410, 5-12=-310/572, 4-12=-421/428, 1-13=-273/400, 9-14=-171/298

NOTES- (9-10)

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 7-0-5, Exterior(2R) 7-0-5 to 13-0-5, Interior(1) 13-0-5 to 20-0-10, Exterior(2E) 20-0-10 to 23-1-13; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 4) All plates are 2x4 MT20 unless otherwise indicated.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Refer to girder(s) for truss to truss connections.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1148 lb uplift at joint 3 and 1159 lb uplift at joint 7.
- 8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
- 9) All truss to truss connection by TCI are on the Truss Placement plan.
- 10) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T7A	COMMON	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:29 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-?2Dh008y2yftTbFjVKH6GlnnpWUTKDNCogNq2Wz9LMG

20-8-80-7-14




Plate Offsets (X,Y)-- [7:Edge,0-0-11], [12:0-2-0,0-1-0]					
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	PLATES GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.72	in (loc) l/defl L/d	MT20 244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.69	Vert(LL) 0.18 9-11 >999 360	
BCLL 0.0	Rep Stress Incr	YES	WB 0.22	Vert(CT) -0.28 9-11 >870 180	
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS	Horz(CT) 0.06 7 n/a n/a	Weight: 94 lb FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3
WEDGE
Right: 2x2 SP No.3

BRACING-
TOP CHORD
BOT CHORD
Structural wood sheathing directly applied.
Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=1389/0-8-0 (min. 0-1-10), 12=-0/Mechanical, 7=1155/0-8-0 (min. 0-1-8)
Max Horz 3=-343(LC 4), 12=405(LC 4)
Max Uplift3=-1164(LC 4), 7=-980(LC 4)
Max Grav 3=1389(LC 1), 7=1155(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-376/333, 2-3=-376/351, 3-4=-2378/1847, 4-19=-2084/1676, 5-19=-2018/1685, 5-20=-2051/1736, 6-20=-2119/1727, 6-21=-2346/1915, 7-21=-2424/1901
BOT CHORD 3-11=-1591/2176, 10-11=-1093/1558, 9-10=-1093/1558, 7-9=-1665/2226
WEBS 5-9=-372/614, 6-9=-449/473, 5-11=-304/568, 4-11=-423/432, 1-12=-277/406

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 7-0-5, Exterior(2R) 7-0-5 to 13-0-5, Interior(1) 13-0-5 to 17-8-8, Exterior(2E) 17-8-8 to 20-8-8; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1164 lb uplift at joint 3 and 980 lb uplift at joint 7.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T7B	Common	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:31 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-yRLSRi9CaZvaivO5dIJalAs7GK9wo7qVG_sw6Pz9LME



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 30.0	2-0-0	TC 0.72	in (loc) l/defl L/d	MT20	244/190
TCDL 15.0	Plate Grip DOL 1.33	BC 0.69	Vert(LL) 0.18 8-10 >999 360		
BCLL 0.0	Lumber DOL 1.33	WB 0.22	Vert(CT) -0.28 8-10 >874 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS	Horz(CT) 0.06 7 n/a n/a		
	Code FBC2020/TPI2014			Weight: 93 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3 WEDGE Right: 2x2 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied. Rigid ceiling directly applied.
---	---	--

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 7=1095/0-8-0 (min. 0-1-8), 3=1390/0-8-0 (min. 0-1-10), 11=-0/Mechanical
Max Horz 3=-310(LC 4), 11=405(LC 4)
Max Uplift 7=-884(LC 4), 3=-1168(LC 4)
Max Grav 7=1095(LC 1), 3=1390(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-376/333, 2-3=-376/351, 3-4=-2381/1858, 4-18=-2086/1687, 5-18=-2020/1697, 5-19=-2058/1766,
6-19=-2126/1757, 6-20=-2355/1952, 7-20=-2433/1938
BOT CHORD 3-10=-1634/2179, 9-10=-1137/1561, 8-9=-1137/1561, 7-8=-1737/2235
WEBS 5-8=-396/620, 6-8=-453/491, 5-10=-302/568, 4-10=-423/432, 1-11=-277/406

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 7-0-5, Exterior(2R) 7-0-5 to 13-0-5, Interior(1) 13-0-5 to 17-0-10, Exterior(2E) 17-0-10 to 20-0-10; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 884 lb uplift at joint 7 and 1168 lb uplift at joint 3.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

[illegible]


Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T9T	COMMON	1	1	Job Reference (optional)
Trusscorp Int., 9590 NW 89 AVE, Medley, FL			8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:34 2025 Page 1		
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-M01a3kC5tUH9ZM7glutHzoUbQXB1?UVxyy4bjkz9LMB					
-2-10-8 2-10-8 4-9-12 4-9-12 8-5-13 3-8-1 12-1-14 3-8-1 16-11-10 4-9-12 Scale = 1:34.0					
4x6 = 5 2x4 = 17 4 2x4 2 2x4 1 2x4 3 2x4 10 3x6 = 3 4.00' 12" 3x6 = 9 3x6 = 8 3x6 = 7 4x10 = 6 2x4 = 18 6 19 3'-4"-0" 0'-3'-11" 0'-11'-12" 0'-6'-1" 1297#/-1462# 976#/-1062#					
Plate Offsets (X,Y)-- [7:0-0-0,0-0-11], [10:0-2-0,0-1-0]					
LOADING (psf) TCLL 30.0 TCDL 15.0 BCLL 0.0 BCDL 10.0		SPACING- 2-0-0 Plate Grip DOL 1.33 Lumber DOL 1.33 Rep Stress Incr YES Code FBC2020/TPI2014	CSI. TC 0.92 BC 0.66 WB 0.23 Matrix-AS	DEFL. in (loc) l/defl L/d Vert(LL) 0.14 9-13 >999 360 Vert(CT) -0.19 9-13 >999 180 Horz(CT) 0.04 7 n/a n/a	PLATES GRIP MT20 244/190 Weight: 79 lb FT = 0%
LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3 OTHERS 2x4 SP No.3 WEDGE Right: 2x2 SP No.3			BRACING- TOP CHORD Structural wood sheathing directly applied. BOT CHORD Rigid ceiling directly applied. MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.		
REACTIONS. (lb/size) 7=923/0-8-0 (min. 0-1-8), 3=1222/0-8-0 (min. 0-1-8), 10=-0/Mechanical Max Horz 3=-418(LC 4), 10=544(LC 4) Max Uplift 7=-1069(LC 4), 3=-1462(LC 4) Max Grav 7=976(LC 5), 3=1297(LC 5)					
FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown. TOP CHORD 1-2=-505/320, 2-3=-507/337, 3-4=-1974/2175, 4-17=-1563/1716, 5-17=-1545/1725, 5-18=-1548/1731, 6-18=-1566/1722, 6-19=-2000/2280, 7-19=-2026/2267 BOT CHORD 3-9=-1898/1783, 8-9=-2021/1843, 7-8=-2021/1843 WEBS 5-9=-453/592, 6-9=-569/762, 4-9=-504/628, 1-10=-299/545					
NOTES- (8-9) 1) Unbalanced roof live loads have been considered for this design. 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -3-1-3 to 0-3-7, Interior(1) 0-3-7 to 5-5-13, Exterior(2R) 5-5-13 to 11-5-13, Interior(1) 11-5-13 to 13-11-10, Exterior(2E) 13-11-10 to 16-11-10; Lumber DOL=1.60 plate grip DOL=1.60 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component. 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 5) Refer to girder(s) for truss to truss connections. 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1069 lb uplift at joint 7 and 1462 lb uplift at joint 3. 7) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord. 8) All truss to truss connection by TCi are on the Truss Placement plan. 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826					
LOAD CASE(S) Standard					

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T10	COMMON	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:36 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-IO8LUQDLP6XtpgH3PivI2Da1hLwyTIKEPGZhocz9LM9



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 30.0	2-0-0	TC 0.55	in (loc)	MT20	244/190
TCDL 15.0	Plate Grip DOL 1.33	BC 0.47	Vert(LL) 0.06 8-15 >999 360		
BCLL 0.0	Lumber DOL 1.33	WB 0.52	Vert(CT) -0.12 11-18 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-AS	Horz(CT) 0.02 9 n/a n/a		
	Code FBC2020/TPI2014			Weight: 97 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied.
WEBS 2x4 SP No.3	
OTHERS 2x4 SP No.3	

REACTIONS. (lb/size) 7=208/0-8-0 (min. 0-1-8), 3=930/0-8-0 (min. 0-1-8), 9=1485/0-8-0 (min. 0-1-12), 12=0/Mechanical

Max Horz 3=-403(LC 4), 12=474(LC 4)

Max Uplift 7=-414(LC 4), 3=-760(LC 4), 9=-1487(LC 4)

Max Grav 7=293(LC 10), 3=930(LC 1), 9=1485(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-452/377, 2-3=-453/392, 3-4=-1392/989, 4-19=-772/487, 5-19=-708/494, 5-20=-670/869, 6-20=-677/758, 6-21=-226/317, 7-21=-307/310

BOT CHORD 3-11=-874/1304, 8-9=-275/272, 7-8=-275/272

WEBS 4-11=-702/672, 5-11=-300/637, 5-9=-1396/1246, 6-9=-893/1265, 6-8=-321/150, 1-12=-335/475

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 7-8-0, Exterior(2R) 7-8-0 to 13-8-0, Interior(1) 13-8-0 to 18-4-0, Exterior(2E) 18-4-0 to 21-4-0; porch right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 414 lb uplift at joint 7, 760 lb uplift at joint 3 and 1487 lb uplift at joint 9.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T10T	COMMON	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:38 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-FnG5v5Fbxjnb2zRRXjxD8efJv8YkxHUWta2osVz9LM7



1014#/-1220#

8-5-13

8-5-13

16-11-10

8-5-13

987#/-108

LOADING (psf)	SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES	GRIP
	TCLL 30.0	Plate Grip DOL 1.33	TC 0.82		Vert(LL) 0.14 8	>999	360	MT20	244/190	
	TCDL 15.0	Lumber DOL 1.33	BC 0.68		Vert(CT) -0.19 8-11	>999	180			
	BCLL 0.0	Rep Stress Incr YES	WB 0.23		Horz(CT) 0.04 6	n/a	n/a			
	BCDL 10.0	Code FBC2020/TPI2014	Matrix-AS							
								Weight: 70 lb	FT = 0%	

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
WEDGE
Left: 2x2 SP No.3 , Right: 2x2 SP No.3

BRACING-
TOP CHORD
BOT CHORD
Structural wood sheathing directly applied.
Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 6=931/0-8-0 (min. 0-1-8), 2=1014/0-8-0 (min. 0-1-8)
Max Horz 2=43(LC 4)
Max Uplift 6=-1083(LC 4), 2=-1220(LC 4)
Max Grav 6=987(LC 5), 2=1014(LC 1)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-15=-2059/2269, 3-15=-2036/2282, 3-16=-1602/1764, 4-16=-1584/1774, 4-17=-1584/1776, 5-17=-1602/1766,
5-18=-2034/2322, 6-18=-2060/2309
BOT CHORD 2-8=-2013/1874, 7-8=-2060/1874, 6-7=-2060/1874
WEBS 4-8=-495/626, 5-8=-567/759, 3-8=-566/708

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-5-13, Exterior(2R) 5-5-13 to 11-5-13, Interior(1) 11-5-13 to 13-11-10, Exterior(2E) 13-11-10 to 16-11-10; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1083 lb uplift at joint 6 and 1220 lb uplift at joint 2.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T12	COMMON	3	1	Job Reference (optional)



LUMBER- TOP CHORD 2x4 SP No.2 *Except* T3: 2x4 SP No.1 BOT CHORD 2x4 SP No.2 *Except* B1: 2x4 SP No.1 WEBS 2x4 SP No.3	BRACING- TOP CHORD Structural wood sheathing directly applied. BOT CHORD Rigid ceiling directly applied or 3-9-14 oc bracing.	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
---	--	---

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	1-2=-337/296, 2-20=-251/220, 3-20=-251/214, 3-4=-3498/2427, 4-5=-2527/1886, 5-21=-2459/1888, 6-21=-2457/1895, 6-22=-2457/1894, 7-22=-2458/1887, 7-8=-2525/1884, 8-9=-3408/2364
BOT CHORD	3-15=-2286/3159, 14-15=-2286/3159, 13-14=-2219/3063, 12-13=-2219/3063, 9-12=-2219/3063
WEBS	6-14=-334/659, 8-14=-956/602, 4-14=-1035/672, 1-18=-250/354, 16-18=-249/353

- NOTES-** (8-9)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to -0-0-15, Interior(1) -0-0-15 to 9-6-0, Exterior(2R) 9-6-0 to 15-6-0, Interior(1) 15-6-0 to 25-0-15, Exterior(2E) 25-0-15 to 28-0-15; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) All plates are 2x4 MT20 unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1261 lb uplift at joint 3 and 1274 lb uplift at joint 9.
 - 8) All truss to truss connection by TCI are on the Truss Placement plan.
 - 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T13	COMMON	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:44 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-3xdMA9JMWZYkmuubt_2eNvvJuZYlRrAPFVV649z9LM1

18-7-125-0-06-4-151-8-0

Scale = 1:52.0




Plate Offsets (X,Y)-- [3:0-3-0,0-2-6], [5:0-3-0,Edge], [8:0-3-0,0-2-6], [10:0-2-4,0-1-0], [16:0-2-0,0-1-0], [17:0-2-0,0-0-8]													
LOADING (psf)		SPACING- 2-0-0		CSI.		DEFL. in (loc) l/defl L/d				PLATES		GRIP	
TCLL	30.0	Plate Grip DOL	1.33	TC	0.85	Vert(LL)	0.28	11-13	>999	360	MT20	244/190	
TCDL	15.0	Lumber DOL	1.33	BC	0.90	Vert(CT)	-0.46	11-13	>632	180			
BCLL	0.0	Rep Stress Incr	YES	WB	0.85	Horz(CT)	0.12	8	n/a	n/a			
BCDL	10.0	Code FBC2020/TPI2014		Matrix-S							Weight: 119 lb	FT = 0%	

LUMBER-		BRACING-	
TOP CHORD	2x4 SP No.2	TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins.
BOT CHORD	2x4 SP No.2 *Except*	BOT CHORD	Rigid ceiling directly applied or 3-9-2 oc bracing.
	B1: 2x4 SP No.1		
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3		

REACTIONS. (lb/size) 3=1654/0-8-0 (min. 0-1-15), 16=0/Mechanical, 8=1496/0-8-0 (min. 0-1-12), 17=0/Mechanical

Max Horz 3=-315(LC 4), 16=352(LC 4)

Max Uplift 3=-1275(LC 4), 8=-1133(LC 4)

Max Grav 3=1654(LC 1), 8=1496(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-2=-336/289, 3-4=-3561/2479, 4-5=-2591/1935, 5-19=-2524/1937, 6-19=-2522/1945, 6-20=-2522/1946, 7-20=-2592/1938, 7-21=-3572/2546, 8-21=-3645/2531

BOT CHORD 3-14=-2258/3337, 13-14=-2258/3337, 12-13=-2329/3425, 11-12=-2329/3425, 8-11=-2329/3425

WEBS 6-13=-368/705, 7-13=-1112/748, 4-13=-1030/674, 1-16=-242/352

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to -0-0-15, Interior(1) -0-0-15 to 9-6-0, Exterior(2R) 9-6-0 to 15-6-0, Interior(1) 15-6-0 to 23-6-4, Exterior(2E) 23-6-4 to 26-6-4; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1275 lb uplift at joint 3 and 1133 lb uplift at joint 8.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T14	Roof Special	3	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:48 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-yitt?WMtao2AFWCM6q7aYI36mAwFHnN?A7TKCwz9LLz




Plate Offsets (X,Y)-- [1:0-0-11,0-1-8], [6:0-3-0,0-3-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.41		Vert(LL)	0.19	6-9	>444	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.86		Vert(CT)	-0.18	6-9	>447	180		
BCLL 0.0	Rep Stress Incr	YES	WB 0.33		Horz(CT)	0.01	1	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 32 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied, except end verticals.
Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=377/0-8-0 (min. 0-1-8), 5=377/Mechanical
Max Horz 1=362(LC 4)
Max Uplift1=-497(LC 4), 5=-684(LC 4)
Max Grav 1=377(LC 1), 5=401(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-532/769
BOT CHORD 1-6=-1016/545
WEBS 3-6=-127/317, 2-6=-592/1104

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 0-0-0 to 3-2-4, Exterior(2R) 3-2-4 to 6-2-1, Exterior(2E) 6-2-1 to 6-10-4; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 497 lb uplift at joint 1 and 684 lb uplift at joint 5.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T18	COMMON	7	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:52 2025 Page 1
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-qT6OruPNe0Ycj7V8LfBWibEjyoJZDURa5lRXLhz9LLV




Plate Offsets (X,Y)-- [7:0-3-0,0-3-0], [10:0-2-0,0-1-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 2-0-0	TC 0.72	Vert(LL) -0.14	7-9	>999	360		MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.71	Vert(CT) -0.32	7-9	>581	180			
BCLL 0.0	Rep Stress Incr YES	WB 0.77	Horz(CT) 0.04	7	n/a	n/a			
BCDL 10.0	Code FBC2020/TPI2014	Matrix-AS						Weight: 79 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD
Structural wood sheathing directly applied.
Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=1148/0-8-0 (min. 0-1-8), 10=-0/Mechanical, 7=849/0-8-0 (min. 0-1-8)
Max Horz 3=355(LC 9), 10=549(LC 4)
Max Uplift 3=-1068(LC 4), 7=-843(LC 4)
Max Grav 3=1148(LC 1), 7=849(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-524/397, 2-3=-526/412, 3-4=-2156/1841, 4-14=-1599/1345, 5-14=-1537/1352
BOT CHORD 3-9=-1833/2035, 8-9=-1048/1036, 7-8=-1048/1036
WEBS 4-9=-645/664, 1-10=-356/550, 5-9=-262/654, 5-7=-1195/1210, 6-7=-196/263

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -3-0-15 to 0-0-0, Interior(1) 0-0-0 to 7-8-0, Exterior(2R) 7-8-0 to 12-7-10, Exterior(2E) 12-7-10 to 15-7-10; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1068 lb uplift at joint 3 and 843 lb uplift at joint 7.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T19	ROOF SPECIAL	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:54 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-nsE8GaRe9eoKzRfWT4E_n0J0Qb?ehOutY3wePaz9LLt



Scale = 1:44.7




Plate Offsets (X,Y)-- [2:0-2-12,Edge], [3:0-0-4,0-0-11], [7:0-0-4,0-0-11], [8:0-7-12,Edge], [9:0-3-0,0-1-2], [10:0-0-8,0-0-4], [14:0-2-9,0-0-7]

LOADING (psf)	SPACING-		CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.91		Vert(LL)	0.36	3-12	>750	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.73		Vert(CT)	-0.60	3-12	>448		
BCLL 0.0	Rep Stress Incr	YES	WB 0.77		Horz(CT)	0.14	8	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS						Weight: 118 lb	FT = 0%

LUMBER-		BRACING-	
TOP CHORD	2x6 SP No.2 *Except* T2: 2x6 SP 2400F 2.0E	TOP CHORD	Structural wood sheathing directly applied.
BOT CHORD	2x4 SP No.2 *Except* B2: 2x4 SP No.3	BOT CHORD	Rigid ceiling directly applied.
WEBS	2x4 SP No.3		MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
OTHERS	2x4 SP No.3		

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=1224/0-8-0 (min. 0-1-8), 8=1595/0-8-0 (min. 0-1-14), 14=0/Mechanical
Max Horz 2=-2162(LC 1), 14=-2162(LC 1)
Max Uplift 2=-1005(LC 4), 8=-1266(LC 4)
Max Grav 2=1224(LC 1), 8=1595(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-21=-2438/1734, 3-21=-2403/1736, 3-4=-3394/2664, 4-22=-2207/1728, 5-22=-2126/1737, 5-23=-2159/1727,
6-23=-2185/1720, 6-7=-2684/2108, 7-8=-2140/1502, 8-9=-2040/1373, 9-10=-2077/1362
BOT CHORD 3-12=-1016/1215, 7-12=-410/664
WEBS 5-12=-339/649, 10-14=-1408/2163, 4-12=-1345/1087, 6-12=-728/455

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ: TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 8-2-8, Exterior(2R) 8-2-8 to 14-2-8, Interior(1) 14-2-8 to 22-5-0, Exterior(2E) 22-5-0 to 25-5-11; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1005 lb uplift at joint 2 and 1266 lb uplift at joint 8.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T19A	ROOF SPECIAL	10	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:56 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-jFMvhFTuhF21CkpvaVGSsRPMzPit9JvA0NPIUSz9LLr



Scale = 1:39.4




Plate Offsets (X,Y)--	[1:1-0-0,0-0-2], [2:0-9-12,0-0-2], [6:0-9-12,0-0-2], [7:0-0-0,0-0-10], [9:0-5-0,0-3-0]
-----------------------	--

LOADING (psf)	SPACING-		CSI.		DEFL.	in (loc)	I/defl	L/d		PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.85		Vert(LL)	0.49	10-18	>524	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.68		Vert(CT)	-0.75	10-18	>343	180	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.68		Horz(CT)	0.31	7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS							Weight: 111 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x6 SP 2400F 2.0E	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x6 SP No.2 *Except*	BOT CHORD Rigid ceiling directly applied.
B2: 2x4 SP 2400F 2.0E	
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=1208/0-8-0 (min. 0-1-8), 7=1191/0-8-0 (min. 0-1-8)
Max Horz 1=2(LC 4)
Max Uplift1=-918(LC 4), 7=-931(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-287/232, 2-19=-5087/3804, 2-3=-4768/3644, 3-20=-3088/2461, 4-20=-3048/2468, 4-21=-3048/2468, 5-21=-3087/2460, 5-6=-4665/3608, 6-7=-283/237
BOT CHORD 2-10=-3476/4690, 9-10=-3476/4690, 8-9=-3437/4580, 6-8=-3437/4580
WEBS 4-9=-693/1048, 3-9=-1802/1356, 5-9=-1687/1316

- NOTES-** (9-10)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 0-4-0 to 3-4-0, Interior(1) 3-4-0 to 8-2-8, Exterior(2R) 8-2-8 to 14-2-8, Interior(1) 14-2-8 to 18-8-0, Exterior(2E) 18-8-0 to 21-11-0; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 918 lb uplift at joint 1 and 931 lb uplift at joint 7.
 - Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 1, 7.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T20	Common	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:44:58 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-fdUf6xU8DsIIIS2yHiwlwysUkaCSBdMbTThusYLz9LLp




Plate Offsets (X,Y)-- [2-0-3-0,0-2-8]					
LOADING (psf)		SPACING-	CSI.	DEFL.	PLATES
TCLL	30.0	2-0-0	TC 0.71	in (loc) l/defl L/d	MT20
TCDL	15.0	Plate Grip DOL 1.33	BC 0.37	Vert(LL) 0.07 4-10 >999 360	GRIP 244/190
BCLL	0.0	Lumber DOL 1.33	WB 0.09	Vert(CT) -0.09 4-10 >999 180	
BCDL	10.0	Rep Stress Incr YES	Matrix-AS	Horz(CT) 0.02 3 n/a n/a	
		Code FBC2020/TPI2014			Weight: 37 lb FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied.
Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=632/0-8-0 (min. 0-1-8), 3=632/0-8-0 (min. 0-1-8)
Max Uplift1=-797(LC 4), 3=-797(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-11=-1345/1735, 2-11=-1287/1742, 2-12=-1287/1742, 3-12=-1345/1735
BOT CHORD 1-4=-1568/1249, 3-4=-1568/1249

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 0-0-0 to 3-0-0, Exterior(2R) 3-0-0 to 8-6-0, Exterior(2E) 8-6-0 to 11-6-0; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 797 lb uplift at joint 1 and 797 lb uplift at joint 3.
 - This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job

12715

Truss

T21

Truss Type

Common

Qty

1

Ply

1

12715 ROLLING ROAD DR, PINECREST, FL.

Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:00 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-b0bPWdWPITZThM6gpLLO1HZ0200T5D5mx?NzdDz9LLn

16-7-6

21-9-0

5-1-10

5-9-10

5-9-10

11-2-8

5-4-14

16-7-6

5-4-14

21-9-0

5-1-10

Scale = 1:35.8

1

2

3

4

5

6

19

20

21

22

3x6 =

3x4 =

4x8 =

2x4 //

3x6 =

5x6 ||

3.3-9

0-5-15

3.00 | 12

0-7-15

1178#/-917#

7-7-4

7-7-4

14-9-12

7-2-8

21-9-0

6-11-4

1215#/-952#

Plate Offsets (X,Y)--

[1:0-0-0,0-0-14], [6:0-4-5,Edge]

LOADING (psf)

TCLL 30.0

TCDL 15.0

BCLL 0.0

BCDL 10.0

SPACING-

Plate Grip DOL 1.33

Lumber DOL 1.33

Rep Stress Incr YES

Code FBC2020/TPI2014

CSI.

TC 0.97

BC 0.83

WB 0.28

Matrix-AS

DEFL.

Vert(LL) 0.30

Vert(CT) -0.49

Horz(CT) 0.09

in (loc)

7-9

7-9

6

l/defl

>858

>534

n/a

L/d

360

180

n/a

PLATES

MT20

GRIP

244/190

Weight: 89 lb

FT = 0%

LUMBER-

TOP CHORD 2x4 SP No.2

BOT CHORD 2x4 SP No.2

WEBS 2x4 SP No.3

SLIDER Right 2x4 SP No.3 2-0-0

BRACING-

TOP CHORD

BOT CHORD

Structural wood sheathing directly applied.

Rigid ceiling directly applied.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS.

(lb/size) 1=1178/0-8-0 (min. 0-1-8), 6=1215/0-8-0 (min. 0-1-8)

Max Horz 1=15(LC 4)

Max Uplift1=-917(LC 4), 6=-952(LC 4)

FORCES.

(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-19=-3255/2521, 2-19=-3188/2532, 2-20=-2836/2209, 3-20=-2780/2217, 3-21=-2503/2015, 4-21=-2547/2008, 4-22=-2750/2204, 5-22=-2777/2196, 5-6=-470/320

BOT CHORD 1-9=-2375/3093, 8-9=-1622/2137, 7-8=-1622/2137, 6-7=-2020/2626

WEBS 2-9=-565/554, 3-9=-424/782, 3-7=-177/491, 4-7=-339/339

NOTES- (7-8)

1) Unbalanced roof live loads have been considered for this design.

2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 8-2-8, Exterior(2R) 8-2-8 to 14-2-8, Interior(1) 14-2-8 to 18-9-0, Exterior(2E) 18-9-0 to 21-9-0; Lumber DOL=1.60 plate grip DOL=1.60

3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.

4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 917 lb uplift at joint 1 and 952 lb uplift at joint 6.

6) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.

7) All truss to truss connection by TCI are on the Truss Placement plan.

8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S)


Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	T22	COMMON	1	1	Job Reference (optional)


Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:01 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-4C9okzW1WnhKJWhsN2sdZV6BWQMRqgYv9f7W9gz9LLm



Scale = 1:47.5



-0-1-8	7-7-4	14-9-12	22-5-0	22-6-8
0-1-8	7-7-4	7-2-8	7-7-4	0-1-8
Plate Offsets (X,Y)-- [1:0-1-11,0-0-4], [14:0-2-0,0-1-0], [15:0-2-0,0-0-8]				

LOADING (psf)	SPACING-		CSI.		DEFL.	in (loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.99		Vert(LL)	0.41 10-12	>650	360	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.85		Vert(CT)	-0.51 10-12	>530	180	MT20HS	187/143
BCLL 0.0	Rep Stress Incr	YES	WB 0.27		Horz(CT)	0.10 7	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-AS						Weight: 104 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.1	TOP CHORD Structural wood sheathing directly applied.
BOT CHORD 2x4 SP No.1 *Except*	BOT CHORD Rigid ceiling directly applied.
B1: 2x4 SP No.2	
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
OTHERS 2x4 SP No.3	

REACTIONS. (lb/size) 3=1354/0-8-0 (min. 0-1-11), 14=0/Mechanical, 15=0/Mechanical, 7=1525/0-8-0 (min. 0-1-14)
Max Horz 3=159(LC 9), 15=-186(LC 4)
Max Uplift 3=-1420(LC 4), 7=-1626(LC 4)
Max Grav 3=1427(LC 5), 7=1609(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-22=-3475/3324, 4-22=-3467/3336, 4-23=-3110/2941, 5-23=-3091/2948, 5-24=-2990/2843, 6-24=-3005/2836, 6-7=-3336/3192
BOT CHORD 3-12=-3200/3215, 11-12=-2270/2210, 10-11=-2270/2210, 7-10=-3050/3071
WEBS 5-10=-404/650, 6-10=-489/610, 5-12=-534/756, 4-12=-550/675

- NOTES-** (9-10)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Part. Encl., GCpi=0.55; C-C Exterior(2E) -1-6-4 to 1-5-12, Interior(1) 1-5-12 to 8-2-8, Exterior(2R) 8-2-8 to 14-2-8, Interior(1) 14-2-8 to 22-5-0, Exterior(2E) 22-5-0 to 25-5-15; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1420 lb uplift at joint 3 and 1626 lb uplift at joint 7.
 - 8) This truss design requires that a minimum of 7/16" structural wood sheathing be applied directly to the top chord and 1/2" gypsum sheetrock be applied directly to the bottom chord.
 - 9) All truss to truss connection by TCI are on the Truss Placement plan.
 - 10) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V2	Valley	4	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:05 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-yzPlaKaXa0Bmn7?ecuwZkLH6x1wcmYiV4H5klRz9LLi



Scale = 1:6.4

		2-0-0							
		2-0-0							
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.			PLATES	GRIP	
	Plate Grip DOL	0.90		in	(loc)	l/defl			L/d
	Plate Metal DOL	0.90		22#	22#				
	Lumber DOL	0.90		Horz(CT)	0.00				
	Rep Stress Incr	YES							
TCLL 30.0	Code FBC2020/TPI2014		TC 0.00	Vert(LL)	n/a	Weight: 6 lb FT = 0%			
TCDL 15.0			BC 0.00	Vert(CT)	n/a				
BCLL 0.0			WB 0.00	Horz(CT)	n/a				
BCDL 10.0			Matrix-P						

LUMBER-
BOT CHORD 2x8 SP No.2

BRACING-
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=11/2-0-0 (min. 0-1-8), 1=11/2-0-0 (min. 0-1-8)
Max Grav 2=22(LC 3), 1=22(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES- (4-5)
- 1) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) All truss to truss connection by TCI are on the Truss Placement plan.
 - 5) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V2A	GABLE	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:07 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-uMW3_0bo6dRU1R80kJz1pmMSQrc2ESCoYbaqNJz9LLg



		2'-0'-0		2'-0'-0						
LOADING (psf)	SPACING-		CSI.	DEFL.		PLATES	GRIP			
	Plate Grip DOL			in (loc) l/defl L/d						
	Plate Metal DOL			Vert(LL) n/a - n/a 999						
	Lumber DOL			Vert(CT) n/a - n/a 999						
	Rep Stress Incr			Horz(CT) 0.00 n/a n/a						
TCLL 30.0	Code FBC2020/TPI2014		TC 0.00	22#0#		22#0#				
TCDL 15.0			BC 0.01			Weight: 5 lb				
BCLL 0.0			WB 0.00			FT = 0%				
BCDL 10.0			Matrix-P							

LUMBER-
BOT CHORD 2x6 SP No.2

BRACING-
BOT CHORD Rigid ceiling directly applied or 10'-0'-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=11/2'-0'-0 (min. 0'-1'-8), 1=11/2'-0'-0 (min. 0'-1'-8)
Max Grav 2=22(LC 3), 1=22(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES- (4-5)
- 1) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) All truss to truss connection by TCI are on the Truss Placement plan.
 - 5) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V4	GABLE	2	1	Job Reference (optional)


Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:08 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-MY4RCMcQsxZKeajCH1UGLzudAEy1zvRxmEJOvmz9LLf



Scale = 1:7.6



		43#10#		43#10#						
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP	
	Plate Grip DOL	0.90		Vert(LL)	n/a	-	n/a			999
	Plate Metal DOL	0.90		Vert(CT)	n/a	-	n/a			999
	Lumber DOL	0.90		Horz(CT)	0.00		n/a			
	Rep Stress Incr	YES								
TCLL 30.0		Code FBC2020/TPI2014		TC 0.00				Weight: 9 lb FT = 0%		
TCDL 15.0				BC 0.02						
BCLL 0.0				WB 0.00						
BCDL 10.0			Matrix-P							

LUMBER-
BOT CHORD 2x6 SP No.2

BRACING-
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=22/4-0-0 (min. 0-1-8), 1=22/4-0-0 (min. 0-1-8)
Max Grav 2=43(LC 3), 1=43(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (4-5)
- 1) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) All truss to truss connection by TCI are on the Truss Placement plan.
 - 5) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V4A	Valley	4	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:10 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-JxCBd2dgOYp2uutbPRWkRO_t82cHRpxEEYoU_ez9LLd



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.35	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.10	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	0.00	-	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-P					Weight: 12 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=163/4-0-0 (min. 0-1-8), 3=163/4-0-0 (min. 0-1-8)
Max Horz 1=176(LC 4)
Max Uplift1=-205(LC 4), 3=-264(LC 4)
Max Grav 1=163(LC 5), 3=186(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-156/278

- NOTES-** (7-8)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCdL=5.0psf; BCdL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 205 lb uplift at joint 1 and 264 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V4B	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:11 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-n7mZqOel9sxvV2Snz91zzcW3DSyqAGBNTCY2W5z9LLc



LOADING (psf)	SPACING-	CSL	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 1.33	TC 0.27	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.08	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr YES	WB 0.00	Horz(CT)	0.00	-	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-P					Weight: 11 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3	BRACING- TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
--	--

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=147/4-0-0 (min. 0-1-8), 3=147/4-0-0 (min. 0-1-8)
Max Horz 1=119(LC 4)
Max Uplift1=-197(LC 4), 3=-226(LC 4)
Max Grav 1=152(LC 5), 3=163(LC 5)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-** (7-8)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 1 and 226 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V4C	VALLEY	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL 8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:13 2025 Page 1
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-jWuKF3gYhTBdlMcA4aR21cTvFfDe9hgwW19azz9LLa



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc)	L/defl L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 0.90	TC 0.00	Vert(LL) n/a -	n/a 999		
TCDL 15.0	Plate Metal DOL 0.90	BC 0.02	Vert(CT) n/a -	n/a 999		
BCLL 0.0	Lumber DOL 0.90	WB 0.00	Horz(CT) 0.00	n/a n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-P			Weight: 9 lb	FT = 0%
	Code FBC2020/TPI2014					

LUMBER- BOT CHORD 2x6 SP No.2	BRACING- BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
---	---

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=21/4-0-0 (min. 0-1-8), 1=21/4-0-0 (min. 0-1-8)
Max Grav 2=43(LC 3), 1=43(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES- (4-5)

- 1) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 2) Gable requires continuous bottom chord bearing.
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) All truss to truss connection by TCI are on the Truss Placement plan.
- 5) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V6	VALLEY	3	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:14 2025 Page 1

ID: GLN6EJBZ1GCD23RDL_tAxzKvJz-BiRiSPhBSnKUMWBMeHgbE8Sufx_Ncxq9Ami7Pz9LLZ




Plate Offsets (X,Y)-- [1:0-3-12,Edge], [2:0-2-13,0-0-4], [3:0-2-8,0-1-0]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.78		Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.31		Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00		Horz(CT)	0.00		n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-P							Weight: 19 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.1 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3	BRACING- TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
--	--

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=273/6-0-0 (min. 0-1-8), 3=273/6-0-0 (min. 0-1-8)
Max Horz 1=288(LC 4)
Max Uplift1=-334(LC 4), 3=-430(LC 4)
Max Grav 1=273(LC 1), 3=305(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-255/455

- NOTES-** (7-8)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 334 lb uplift at joint 1 and 430 lb uplift at joint 3.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V6A	Valley	1	1	Job Reference (optional)

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V7	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:17 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-ch7r5Rj3lil3DzvxJQ8NDtm5Dt?3awgGr8?Mjkz9LLW



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.30	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.09	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.19	Horz(CT)	0.00	-	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-P					Weight: 23 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=151/6-8-0 (min. 0-1-8), 4=67/6-8-0 (min. 0-1-8), 5=400/6-8-0 (min. 0-1-8)
Max Horz 1=317(LC 4)
Max Uplift1=-125(LC 4), 4=-103(LC 4), 5=-611(LC 4)
Max Grav 1=151(LC 1), 4=73(LC 5), 5=436(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-256/113
WEBS 2-5=-363/647

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 125 lb uplift at joint 1, 103 lb uplift at joint 4 and 611 lb uplift at joint 5.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V8	Valley	2	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:19 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-YgFbW7kJHJynTH3KRqArlisPqgc52tAZISUTodz9LLU




Plate Offsets (X,Y)-- [1:0-1-12,Edge], [2:0-3-0,Edge], [3:0-6-4,Edge]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.42	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.44	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-P						Weight: 21 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.
Rigid ceiling directly applied or 6-5-13 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=310/8-0-0 (min. 0-1-8), 3=310/8-0-0 (min. 0-1-8)
Max Uplift1=-406(LC 4), 3=-406(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-547/897, 2-3=-547/897
BOT CHORD 1-3=-810/507

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 406 lb uplift at joint 1 and 406 lb uplift at joint 3.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V8A	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:20 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-0spzjSlx2d4d4ReW_Yi4rVObo41NnHHiX6D0K3z9LLT



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 1.33	TC 0.34	Vert(LL) n/a - n/a 999	MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.11	Vert(CT) n/a - n/a 999		
BCLL 0.0	Rep Stress Incr YES	WB 0.20	Horz(CT) 0.00 n/a n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-P		Weight: 25 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=160/8-0-0 (min. 0-1-8), 4=111/8-0-0 (min. 0-1-8), 5=462/8-0-0 (min. 0-1-8)
Max Horz 1=268(LC 4)
Max Uplift1=-152(LC 4), 4=-153(LC 4), 5=-634(LC 4)
Max Grav 1=160(LC 1), 4=113(LC 5), 5=469(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-5=-385/676

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCCL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 152 lb uplift at joint 1, 153 lb uplift at joint 4 and 634 lb uplift at joint 5.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V8B	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:22 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-yFwk88nCZEKLKkov6zkYwwUy3uiDFBs?_Qi7Pyz9LLR



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.29	Vert(LL)	n/a	-	n/a	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.09	Vert(CT)	n/a	-	n/a		
BCLL 0.0	Rep Stress Incr	YES	WB 0.20	Horz(CT)	-0.00	5	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-P					Weight: 29 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 8-0-0.
(lb) - Max Horz 1=327(LC 4)
Max Uplift All uplift 100 lb or less at joint(s) 5 except 1=-112(LC 4), 6=-208(LC 4), 7=-621(LC 4)
Max Grav All reactions 250 lb or less at joint(s) 1, 5, 6 except 7=422(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-8=-253/81
WEBS 2-7=-349/658

- NOTES-** (8-9)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 0-10-13 to 3-10-13, Exterior(2R) 3-10-13 to 6-8-0, Exterior(2E) 6-8-0 to 7-10-4; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Provide adequate drainage to prevent water ponding.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 5 except (jt=lb) 1=112, 6=208, 7=621.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V8C	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:23 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-QRU6LUnqKYSCxuN5ggFnS805oHzz_h98D4SgxOz9LLQ




Plate Offsets (X,Y)-- [1:0-1-9,Edge], [2:0-3-0,Edge], [3:0-6-9,Edge]

LOADING (psf)	SPACING-		CSI.	DEFL.	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.42	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.44	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.00	Horz(CT)	-0.01	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-P						Weight: 21 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2

BRACING-
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.
Rigid ceiling directly applied or 6-5-6 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=311/8-0-9 (min. 0-1-8), 3=311/8-0-9 (min. 0-1-8)
Max Uplift1=-405(LC 4), 3=-405(LC 4)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-554/904, 2-3=-554/904
BOT CHORD 1-3=-818/514

- NOTES-** (7-8)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E); Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=405, 3=405.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V10	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL 8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:25 2025 Page 1
ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-NqcsmA4s9iwBCXUn5HFYZ6Rd5jxSYDRhOxn?Hz9LLO



LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc)	L/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL 1.33	TC 0.40	Vert(LL) n/a	- n/a	999	MT20	244/190
TCDL 15.0	Lumber DOL 1.33	BC 0.15	Vert(CT) n/a	- n/a	999		
BCLL 0.0	Rep Stress Incr YES	WB 0.22	Horz(CT) -0.00	6 n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014	Matrix-S				Weight: 39 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3	BRACING- TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals. BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.
--	--

REACTIONS. All bearings 10-0-0.
(lb) - Max Horz 1=322(LC 4)
Max Uplift All uplift 100 lb or less at joint(s) 6 except 1=-156(LC 4), 8=-180(LC 4), 7=-146(LC 4), 9=-733(LC 4)
Max Grav All reactions 250 lb or less at joint(s) 1, 6, 8, 7 except 9=509(LC 9)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-9=-400/742

NOTES- (8-9)

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCdL=5.0psf; BCdL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 0-10-13 to 3-10-13, Interior(1) 3-10-13 to 4-10-9, Exterior(2R) 4-10-9 to 7-10-9, Exterior(2E) 7-10-9 to 9-10-4; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 4) Provide adequate drainage to prevent water ponding.
- 5) Gable requires continuous bottom chord bearing.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6 except (jt=lb)
1=156, 8=180, 7=146, 9=733.
- 8) All truss to truss connection by TCI are on the Truss Placement plan.
- 9) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V10A	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:27 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-JCkdBsRkOmyeQVgsvWKjd_BlwvPwwSfk8iQu49z9LLM



LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.48	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.18	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.22	Horz(CT)	-0.00	4	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 33 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.
WEBS 2x4 SP No.3	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=208/10'-0" (min. 0'-1"-8), 4=160/10'-0" (min. 0'-1"-8), 5=586/10'-0" (min. 0'-1"-8)
Max Horz 1=327(LC 4)
Max Uplift1=-175(LC 4), 4=-240(LC 4), 5=-721(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-133/258
WEBS 2-5=-467/751

- NOTES-** (7-8)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 1-2-3 to 4-2-3, Interior(1) 4-2-3 to 5-7-5, Exterior(2R) 5-7-5 to 9-10-4; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=175, 4=240, 5=721.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V12	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:28 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-nPI?PCrz944V2f2SDry9Bjv6lkNfv_tNM9Rccz9LLL



LOADING (psf)	SPACING-	2'-0"-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.51	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.23	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.22	Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 34 lb	FT = 0%

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2	TOP CHORD Structural wood sheathing directly applied or 6'-0" oc purlins.
BOT CHORD 2x4 SP No.2	BOT CHORD Rigid ceiling directly applied or 10'-0" oc bracing.
WEBS 2x4 SP No.3	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=224/12'-0"-0 (min. 0'-1'-8), 3=224/12'-0"-0 (min. 0'-1'-8), 4=612/12'-0"-0 (min. 0'-1'-8)
Max Uplift1=-270(LC 4), 3=-270(LC 4), 4=-739(LC 4)
Max Grav 1=234(LC 9), 3=234(LC 10), 4=612(LC 1)


FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-459/734

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 1-2-3 to 4-2-3, Exterior(2R) 4-2-3 to 7-9-13, Exterior(2E) 7-9-13 to 10-9-13; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb)
1=270, 3=270, 4=739.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V12C	VALLEY	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL 8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:30 2025 Page 1
ID: GLN6EJBZ1GCD23RDL tAxzKvJz-jnPttDhhLDHzPRAetQFcpGg6Ps7pUAqgeYhUz9LLJ

[illegible]

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.
		MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS.	(lb/size) 1=223/12-0-0 (min. 0-1-8), 3=223/12-0-0 (min. 0-1-8), 4=611/12-0-0 (min. 0-1-8) Max Uplift1=-269(LC 4), 3=-269(LC 4), 4=-738(LC 4) Max Grav 1=233(LC 9), 3=233(LC 10), 4=611(LC 1)
-------------------	--

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=458/733

NOTES- (7-8)

- 1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDD=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 1-2-6 to 4-2-6, Exterior(2R) 4-2-6 to 7-9-10, Exterior(2E) 7-9-10 to 10-9-10; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
- 4) Gable requires continuous bottom chord bearing.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb)
1=269, 3=269, 4=738.
- 7) All truss to truss connection by TCI are on the Truss Placement plan.
- 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V16	Valley	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:31 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-B_z71DurS?T4v7_d8MOfnqLKLWhQsE7K3JO6Dwz9LLI




Plate Offsets (X,Y)-- [2:0-4-0,0-2-8]

LOADING (psf)	SPACING-		CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	2-0-0	TC 0.90		Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.47		Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.26		Horz(CT)	0.00	3	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S							Weight: 47 lb	FT = 0%

LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 OTHERS 2x4 SP No.3	BRACING- TOP CHORD BOT CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.
--	---	---

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=317/16-0-0 (min. 0-1-12), 3=317/16-0-0 (min. 0-1-12), 4=866/16-0-0 (min. 0-1-12)
Max Uplift1=-327(LC 4), 3=-327(LC 4), 4=-857(LC 4)
Max Grav 1=331(LC 9), 3=331(LC 10), 4=866(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-650/864

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 1-2-3 to 4-2-3, Interior(1) 4-2-3 to 5-0-0, Exterior(2R) 5-0-0 to 11-0-0, Interior(1) 11-0-0 to 11-9-13, Exterior(2E) 11-9-13 to 14-9-13; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=327, 3=327, 4=857.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V16C	VALLEY	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:33 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-8M5uSvv5_cjn8Q80FnR7sFRhuJNwK8edWdtClpz9LLG



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL	30.0	Plate Grip DOL	1.33	TC	0.89	Vert(LL)	n/a	-	n/a	999	MT20	244/190	
TCDL	15.0	Lumber DOL	1.33	BC	0.47	Vert(CT)	n/a	-	n/a	999			
BCLL	0.0	Rep Stress Incr	YES	WB	0.26	Horz(CT)	0.00	3	n/a	n/a			
BCDL	10.0	Code FBC2020/TPI2014		Matrix-S									
												Weight: 47 lb	FT = 0%

LUMBER-				BRACING-			
TOP CHORD	2x4 SP No.2			TOP CHORD	Structural wood sheathing directly applied or 2-2-0 oc purlins. Rigid ceiling directly applied or 10-0-0 oc bracing.		
BOT CHORD	2x4 SP No.2			BOT CHORD			
WEBS	2x4 SP No.3				MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.		

REACTIONS. (lb/size) 1=316/16-0-0 (min. 0-1-12), 3=316/16-0-0 (min. 0-1-12), 4=865/16-0-0 (min. 0-1-12)
Max Uplift1=-326(LC 4), 3=-326(LC 4), 4=-857(LC 4)
Max Grav 1=330(LC 9), 3=330(LC 10), 4=865(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-4=-649/863

- NOTES-** (7-8)
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 1-2-6 to 4-2-6, Interior(1) 4-2-6 to 5-0-0, Exterior(2R) 5-0-0 to 11-0-0, Interior(1) 11-0-0 to 11-9-10, Exterior(2E) 11-9-10 to 14-9-10; Lumber DOL=1.60 plate grip DOL=1.60
 - Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - Gable requires continuous bottom chord bearing.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb)
1=326, 3=326, 4=857.
 - All truss to truss connection by TCI are on the Truss Placement plan.
 - ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard


LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	12715 ROLLING ROAD DR, PINECREST, FL.
12715	V20C	VALLEY	1	1	Job Reference (optional)

Trusscorp Int., 9590 NW 89 AVE, Medley, FL

8.820 s Dec 4 2024 MiTek Industries, Inc. Thu Jun 5 12:45:36 2025 Page 1

ID: _GLN6EJBZ1GCD23RDL_tAxzKvJz-Yxn04xy_GX5M?usbwv_qUit3KHXT9XXx3Cb5su8z9LLD



Scale = 1:31.5




Plate Offsets (X,Y)-- [4:0-0-0,0-0-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 30.0	Plate Grip DOL	1.33	TC 0.37	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL 15.0	Lumber DOL	1.33	BC 0.18	Vert(CT)	n/a	-	n/a	999		
BCLL 0.0	Rep Stress Incr	YES	WB 0.16	Horz(CT)	0.00	5	n/a	n/a		
BCDL 10.0	Code FBC2020/TPI2014		Matrix-S						Weight: 62 lb	FT = 0%

LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD
BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.
Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 20-0-0.
(lb) - Max Uplift All uplift 100 lb or less at joint(s) except 1=-175(LC 4), 5=-175(LC 4), 9=-497(LC 4), 8=-280(LC 4), 6=-497(LC 4)
Max Grav All reactions 250 lb or less at joint(s) 1, 5 except 9=589(LC 9), 8=360(LC 1), 6=589(LC 10)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 2-9=-473/526, 3-8=-296/329, 4-6=-473/526

- NOTES-** (7-8)
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=175mph (3-second gust) Vasd=136mph; HVHZ; TCDL=5.0psf; BCDL=5.0psf; h=28ft; Cat. II; Exp C; Encl., GCpi=0.18; C-C Exterior(2E) 1-2-6 to 4-2-6, Interior(1) 4-2-6 to 7-0-0, Exterior(2R) 7-0-0 to 13-0-0, Interior(1) 13-0-0 to 15-9-10, Exterior(2E) 15-9-10 to 18-9-10; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Building Designer / Project engineer responsible for verifying applied roof live load shown covers rain loading requirements specific to the use of this truss component.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 175 lb uplift at joint 1, 175 lb uplift at joint 5, 497 lb uplift at joint 9, 280 lb uplift at joint 8 and 497 lb uplift at joint 6.
 - 7) All truss to truss connection by TCI are on the Truss Placement plan.
 - 8) ARMANDO R. PEREZ PE. # 28026 Ph: (305) 882-8826

LOAD CASE(S) Standard

Certificate of Competency

Manufacturer or Fabricator
of Construction Materials,
Products or Assemblies



Miami-Dade County, Florida
Department of Regulatory and
Economic Resources
11805 S.W. 26 Street, Room 208
Miami, Florida 33175-2474
Tel (786) 315-2590 Fax (786) 315-2599

Certification No. 24-0903.06

The Department of Regulatory and Economic Resources hereby certifies that **Trusscorp International, Inc.** located at **9590 NW 89th Avenue, Miami, FL 33178** complies with the requirements of Article IV, Chapter 8 of the Code of Miami-Dade County as a manufacturer and/or fabricator of **Wood Trusses.**

Certification Date: 10/1/2024
Certification Expires: 9/30/2025

A handwritten signature in blue ink that reads "Americo Segura".

Americo Segura, M.S., C.G.C.
Quality Assurance Unit Supervisor
Product Control Section

THIS CERTIFICATE DOES NOT ENTITLE HOLDER TO CONTRACT FOR ERECTION OR INSTALATION. WHERE SEVERAL PLANTS ARE OWNED BY THE SAME COMPANY A SEPARATE CERTIFICATE OF COMPLIANCE SHALL BE REQUIRED FOR EACH PLANT. THIS CERTIFICATE SHALL BE REVOKED IF THE HOLDER FAILS TO MEET THE CODE OF POLICY REQUIREMENTS COVERING THIS PRODUCT.

**Product Approval**
USER: Public User[Product Approval Menu](#) > [Product or Application Search](#) > [Application List](#) > **Application Detail**OFFICE OF THE
SECRETARY

FL #	FL17232-R11	
Application Type	Revision	
Code Version	2023	
Application Status	Approved	
	*Approved by DBPR. Approvals by DBPR shall be reviewed and ratified by the POC and/or the Commission if necessary.	
Comments		
Archived	☐	
Product Manufacturer	MiTek Inc.	
Address/Phone/Email	16023 Swingley Ridge Road Chesterfield, MO 63017 (800) 328-5934 bpr@mii.com	
Authorized Signature	Erin Walden bpr@mii.com	
Technical Representative	Erin M. Walden	
Address/Phone/Email	16023 Swingley Ridge Road Chesterfield, MO 63017 (952) 898-8635 ewalden@mii.com	
Quality Assurance Representative	Erin M. Walden	
Address/Phone/Email	16023 Swingley Ridge Road Chesterfield, MO 63017 (952) 898-8635 ewalden@mii.com	
Category	Structural Components	
Subcategory	Wood Connectors	
Compliance Method	Evaluation Report from a Product Evaluation Entity	
Evaluation Entity	ICC Evaluation Service, LLC	
Quality Assurance Entity	ICC-ES Evaluation Service, LLC	
Quality Assurance Contract Expiration Date	10/31/2026	
Validated By	ICC Evaluation Service, LLC.	
Certificate of Independence	FL17232_R11_COI_ICC-ES Certification of Independence for Evaluation 2024 (1).pdf	
Referenced Standard and Year (of Standard)	Standard	Year
	ANSI/AWC NDS	2018
	ASTM D7147	2011
Equivalence of Product Standards Certified By		
Sections from the Code		

Product Approval Method

Method 1 Option C

Date Submitted

01/15/2025

Date Validated

01/17/2025

Date Pending FBC Approval

Date Approved

01/20/2025

Summary of Products

Go to Page



Page 1 / 2

FL #	Model, Number or Name	Description
17232.1	CLPBF	Butterfly Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.2	HD26, HD24-2, HD34, HD44	Face Mount Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.3	HD28, HD210, HD212, HD214, HD216, HD26-2, HD28-2, HD210-2, HD212-2, HD214-2, HD216-2, HD26-3, HD28-3, HD210-3, HD212-3, HD214-3, HD216-3, HD28-4, HD210-4, HD36, HD38, HD310, HD312, HD314, HD316, HD38-2, HD310-2, HD312-2, HD46, HD48	Face Mount Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.4	HD410, HD412, HD414, HD416, HD418, HD66, HD68, HD610, HD612, HD614, HD616, HD86, HD88, HD810, HD812, HD814, HD816, HD1770, HD17925, HD17112, HD1714, HD27925, HD27112, HD2714, HD32105, HD3212, HD5112, HD51135	Face Mount Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.5	HD5210, HD5212, HD5214, HD5216, HD62117, Hd71117, HD7100, HD7120, HD7140, HD7160, HD7180, HD77117, HD83117, HD95117	Face Mount Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf

17232.6	HDQ179IF, HDQ17112IF, HDQ1714IF, HD310IF, HDQ210-2IF, HDQ410IF, HDQ412IF, HDQ210-3IF, HDQ5210IF, HDQ5212IF, HDQ610IF, HDQ612IF	Inverted Flange Face Mount Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.7	 HUS26, HUS28, HUS210, HUS175, HUS177, HUS179, HUS24-2, HUS26-2, HUS28-2, HUS210-2, HUS212-2, HUS46, HUS48, HUS410, HUS412	Slant Nail Joist Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.8	IHF15925, IHF15112, IHF1514, IHF16925, IHF16112, IHF1614, IHF17925, IHF17112, IHF1714, IHF1716, IHF20925, IHF20112, IHF2014, IHF23925, IHF23112, IHF2314, IHF2316, IHF2318, IHF25925, IHF25112, IHF2514, IHF2516, IHF26925, IHF26112, IHF2614, IHF2616	Joist Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.9	IHF15925-2, IHF15112-2, IHF16925-2, IHF16112-2, IHF35925, IHF35112, IHF3514, IHF3516, IHF3518, IHF20925-2, IHF20112-2, IHF2014-2, IHF23925-2, IHF25925-2, IHF25112-2	Joist Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.10	IHFL15925, IHFL15112, IHFL17925, IHFL17112, IHFL1714, IHFL1716, IHFL20925, IHFL20112, IHFL2014, IHFL2016, IHFL23925, IHFL23112, IHFL2314, IHFL2316, IHFL25925, IHFL25112, IHFL2514, IHFL2516, IHFL35925, IHFL35112, IHFL3514, IHFL3516	Joist Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.11	JL24, JL26	Standard Joist Hangers
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf

17232.12	JL24-IF	Inverted Flange Joist Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.13	JL26-IF, JL28-IF, JL210-IF	Inverted Flange Joist Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.14	JL28, JL210	Standard Joist Hangers
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.15	JN26-2, JN28-2, JN26E, JN28E, JN210E	Power Nail Hangers
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.16	JUS24, JUS24-2, JUS24-3, JUS44	Slant Nail Joist Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.17	JUS26, JUS28, JUS210, JUS36, JUS38, JUS310, JUS26-2, JUS28-2, JUS210-2, JUS214-2, JUS46, JUS48, JUS410, JUS412, JUS414, JUS26-3, JUS28-3, JUS210-3, JUS212-3, JUS214-3	Slant Nail Joist Hanger
		
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.18	LGU325, LGU363, LGU525, MGU363, MGU525, MGU550, MGU562, MGU700, HGU363, HGU525, HGU550, HGU562, HGU700, HGU725, HGU900	Girder Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.19	MUS26, MUS28	Slant Nail Joist Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf

Product Approval Method

Method 1 Option C

Date Submitted

01/15/2025

Date Validated

01/17/2025

Date Pending FBC Approval

Date Approved

01/20/2025

Summary of Products

Go to Page



Page 2 / 2

FL #	Model, Number or Name	Description
17232.21	SUH26, SUH28, SUH210, SUH214, SUH1710, SUH1714, SUH26R, SUR28R, SUH210R, SUH214R, SUH2310, SUH2314, SUH36, SUH310, SUH314, SUH2610, SUH2614, SUH26-2, SUH28-2, SUH210-2, SUH214-2	Joist Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445 rev Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445 rev Dec24.pdf
17232.22	SUH46, SUH48, SUH410, SUH414, SUH46R, SUH410R, SUH28-3, SUH210-3, SUH2310-2, SUH2314-2, SUH310-2, SUH66, SUH610, SUH66R, SUH610R	Joist Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445 rev Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445 rev Dec24.pdf
17232.23	THD26, THD28, THD210, THD175, THD177, THD179, THD26-2, THD28-2, THD210-2, THD210-3, THD210-4, THD46, THD48, THD410, THD412, THD414, THD610, THD612, THD614, THD7210	Face Mount Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445 rev Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445 rev Dec24.pdf
17232.24	THDH26, THDH28, THDH210, THDH27925, THDH27112, THDH2714, THDH26-2, THDH28-2, THDH210-2, THDH212-2, THDH214-2, THDH3210, THDH3212, THDH46, THDH48, THDH410, THDH412, THDH414	Face Mount Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445 rev Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445 rev Dec24.pdf
17232.25	THDH26-3, THDH28-3, THDH210-3, THDH212-3, THDH214-3, THDH5210, THDH5212, THDH5214, THDH610, THDH612, THDH614, THDH26-4, THDH28-4, THDH6710, THDH6712,	Face Mount Hanger

	THDH6714, THDH7210, THDH7212, THDH7214	
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.26	THDHQ26-2, THDHQ26-3, THDHQ26-4, THDHQ28-2, THDHQ28-3, THDHQ28-4, THDHQ210-2, THDHQ210-3, THDHQ210-4, THDHQ46, THDHQ48, THDHQ410	Girder Truss Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.27	THF15925, THF15112, THF15140, THF16925, THF16112, THF16140, THF17925, THF17112, THF17140, THF20925, THF20112, THF20140, THF17157, THF20157, THF23925, THF23100, THF23118, THF23140, THF23160, THF25925, THF25112, THF25120, THF25130, THF25140, THF25160	Face Mount Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.28	THF15925-2, THF15112-2, THF15140-2, THF16925-2, THF16112-2, THF16140-2, THF17157-2, THF20925-2, THF20112-2, THF20140-2, THF23180, THF23925-2, THF23118-2, THF23140-2, THF23160-2, THF25925-2, THF25112-2, THF25140-2, THF25160-2, THF35165	Face Mount Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.29	THF26925, THF26112, THF26140, THF26160, THF35925, THF35112, THF35140, THF35157	Face Mount Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17232_R11_AE_ESR-3445_rev_Dec24.pdf
17232.30	THFI1795, THFI17118, THFI1714, THFI1716, THFI2095, THFI20118, THFI2014, THFI2016, THFI2395, THFI23118, THFI2314, THFI2316, THFI25925, THFI2595, THFI25118, THFI2514, THFI2516, THFI3595, THFI35118, THFI3514, THFI3516	Fact Mount Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A		Installation Instructions FL17232_R11_II_ESR-3445_rev_Dec24.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party:

ICC-ES Evaluation Report

ESR-3445

Reissued October 2024

Revised December 2024

Subject to renewal October 2026

This report also contains:

- [City of LA Supplement](#)

- [FL Supplement w/ HVHZ](#)

ICC-ES Evaluation Reports are not to be construed as representing aesthetics or any other attributes not specifically addressed, nor are they to be construed as an endorsement of the subject of the report or a recommendation for its use. There is no warranty by ICC Evaluation Service, LLC, express or implied, as to any finding or other matter in this report, or as to any product covered by the report.

Copyright © 2024 ICC Evaluation Service, LLC. All rights reserved.

DIVISION: 06 00 00— WOOD, PLASTICS AND COMPOSITES Section: 06 05 23— Wood, Plastic, and Composite Fastenings	REPORT HOLDER: MITEK INC. 	EVALUATION SUBJECT: MITEK® FACE MOUNT HANGERS FOR WOOD FRAMED CONSTRUCTION	
--	--	--	---

1.0 EVALUATION SCOPE

Compliance with the following codes:

- 2024, 2021, 2018, 2015 and 2012 [International Building Code® \(IBC\)](#)
- 2024, 2021, 2018, 2015 and 2012 [International Residential Code® \(IRC\)](#)

Property evaluated:

Structural

2.0 USES

The MiTek Face Mount Hangers for Wood Framed Construction described in this report (see [Table 19](#) for complete listing) are used for connecting wood framing members in accordance with Section 2304.10.4 of the 2024 and 2021 IBC, Section 2304.10.3 of the 2018 and 2015 IBC and Section 2304.9.3 of the 2012 IBC). The connectors may also be used in structures regulated under the IRC when an engineered design is submitted to, and approved by, the code official, in accordance with Section R301.1.3 of the IRC.

3.0 DESCRIPTION

3.1 CLPBF Butterfly Hanger:

The CLPBF Butterfly Hanger is a face-mount hanger with triangular header flanges having prepunched nail holes for joist-to-header or truss-to-truss connections. The CLPBF Butterfly Hanger is cold-formed from No. 18 gage steel and is prepunched for 10d common nails into the header and 10d-by-1¹/₂-inch nails into the joist. See [Table 1](#) and [Figure 1](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.2 HD Face Mount Hanger:

The HD Face Mount Hanger is designed to support headers, joists and trusses. The HD Face Mount Hanger is cold-formed from No. 14 gage steel; and is prepunched for 16d common nails into the supporting member, and either 16d common, 10d common or 10d-by-1¹/₂-inch nails into the supported member. See [Table 2](#) and [Figure 2](#) for product dimensions, fastener schedule, allowable loads, and typical installation details. The HD, THD, THF and THFI offer increased allowable download and/or uplift values by installing additional nails into the diamond holes. Minimum ('min') load values require the installation of the specified nails into all round

holes of the hanger to support the corresponding allowable loads. Maximum ('max') load values require the installation of the specified nails into all round and all diamond holes of the hanger to support the increased loads. Interpolation is not allowed between the min-max allowable load values and nail count.

3.3 HUS Slant Nail Joist Hanger:

The HUS Slant Nail Joist Hanger is designed to provide double shear nailing for joist/truss-to-beam connections. The HUS Slant Nail Joist Hanger is cold-formed from No. 14 gage or No. 16 gage steel and is prepunched for 16d common nails into both the joist and the header. See [Table 3](#) and [Figure 3](#) for product dimensions, fastener schedule, allowable loads, and typical installation details.

3.4 JL Standard Joist Hangers:

The JL Standard Joist Hangers are designed as face mount hangers for connecting nominal dimension lumber to headers, beams or girders. The JL hangers are cold-formed from No. 20 gage steel. The hangers are prepunched for 16d common or 10d common nails into the header, and 10d-by-1¹/₂-inch nails into the joist. See [Table 4](#) and [Figure 4](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.5 JN and JNE Power Nail Hangers:

JN and JNE Joist Hangers are designed to support one- and two-ply nominally 2-by-6 and 2-by-8 dimension lumber joists. The JN joist hangers are cold-formed from No. 18 gage steel and have a seat depth of 1⁵/₈ inches (41 mm). The JNE joist hangers are cold-formed from No. 20 gage steel and have a seat depth of 2 inches (51 mm). JN and JNE joist hangers are not prepunched for nails. See [Table 5](#) and [Figure 5](#) for product dimensions, required fastener schedule, allowable loads, and a typical installation detail.

3.6 JUS Slant Nail Joist Hanger:

The JUS Slant Nail Joist Hanger is designed for face-mount applications to provide double shear nailing for joist/truss-to-beam connections. The JUS Slant Nail Joist Hanger is cold-formed from No. 18 gage steel and is prepunched for either 10d common or 16d common nails into both the joist and the header. See [Table 6](#) and [Figure 6](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.7 SUH Joist Hanger:

The SUH Joist Hanger is designed as a face-mount hanger to support nominal dimension lumber joists. The SUH Joist Hanger is cold-formed from No. 16 gage steel. The SUH Joist Hanger has prongs in the header flanges to temporarily position the hanger on the header. The hanger is prepunched for 10d common or 16d common nails into the header and 10d-by-1¹/₂, 10d common, or 16d common nails into the joist. See [Table 7](#) and [Figure 7](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.8 THD Face Mount Hanger:

The THD Face Mount Hanger is designed to support metal-plate-connected wood trusses and can also support LVL, LSL and PSL members. The THD Face Mount Hanger is cold-formed from either No. 12 gage, No. 14 gage, or No. 16 gage steel; and is prepunched for 16d common nails into the header, and either 10d common or 10d-by-1¹/₂-inch nails into the joist. See [Table 8](#) and [Figure 8](#) for product dimensions, required fastener schedule, allowable loads, and a typical installation detail.

3.9 THDH Face Mount Hanger:

The THDH Face Mount Hanger is designed as a hanger for metal-plate-connected wood trusses and can also support LVL, LSL and PSL members. The THDH Face Mount Hanger is cold-formed from No. 12 gage steel and is prepunched for 16d common nails. See [Table 9](#) and [Figure 9](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.10 THF Face Mount Hanger:

The THF Face Mount Hanger is designed to provide lateral top chord support for I-joist-to-header applications. The supporting header may be wood I-joists, LVL, LSL, PSL, or solid sawn lumber. The THF Face Mount Hanger is cold-formed from either No. 18 gage, No. 16 gage, or No. 12 gage steel; and is prepunched for 10d common nails into the header, and either 10d common or 10d-by-1¹/₂-inch nails into the joist. See [Table 10](#) and [Figure 10](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.11 THFI Face Mount Hanger:

The THFI Face Mount Hanger is designed to provide lateral top chord support for I-joist-to-header applications with the added benefit of having six locking prongs in the hanger seat. The supporting header may be wood I-joists, LVL, LSL, PSL, or solid sawn lumber. The locking prongs provide a consistent uplift capacity for I-joists of all bottom flange thicknesses without the need of hanger-to-joist nails. The THFI also has a patented self-supporting top tab that securely grips to the header and holds the hanger in place without needing manual

assistance while fasteners are installed. The THFI Face Mount Hanger is cold formed from No. 18 gage steel and is prepunched for 10d common nails into the header. See [Table 11](#) and [Figure 11](#) for product dimensions, fastener schedule, allowable loads and a typical installation detail.

3.12 LGU/MGU/HGU Girder Hanger:

The LGU/MGU/HGU Girder Hangers are designed as face mount hangers for attaching glulam beams to glulam headers. Header fasteners are located high on the side flanges to allow a deeper supported member to be attached top flush to a shallower supporting member. The LGU/MGU/HGU Girder Hangers are cold formed from either No. 10 gage or No. 7 gage steel and are prepunched for 1/4-inch-diameter MiTek WS Series WS3 (3-inch-length) wood screws. The MiTek WS Series wood screws are proprietary screws described in [ESR-2761](#) and are shipped with the hangers. The LGU/MGU/HGU Girder Hangers can also be used to attach LVL, LSL and PSL beams and headers together. See [Table 12](#) and [Figure 12](#) for product dimensions, fastener schedule, allowable loads and a typical installation detail.

3.13 THDHQ Girder Truss Hanger:

The THDHQ Girder Truss Hangers are designed as face mount hangers for attaching multi-ply metal plated wooded girder trusses together. The THDHQ hangers are cold formed from No. 12 gage steel and are prepunched for 1/4-inch-diameter MiTek WS Series WS3 (3-inch-length), WS45 (4 1/2-inch-length) or WS6 (6-inch-length) wood screws. The MiTek WS Series wood screws are proprietary screws described in [ESR-2761](#) and are shipped with the THDHQ hangers. The THDHQ hangers can also be used to connect LVL, LSL and PSL beams and headers together. See [Table 13](#) and [Figure 13](#) for product dimensions, fastener schedule, allowable loads and a typical installation detail.

3.14 IHF Face Mount Hanger:

The IHF Face Mount Hanger is designed to resist the gravity and uplift loads from wood I-joists. Sized specifically for wood I-joists, the sides of the IHF Face Mount Hanger provide lateral support to the I-joist top flange. The IHF Face Mount hanger is intended to support wood I-joists with flanges manufactured from structural composite lumber (SCL). Design values for the IHF Face Mount Hanger and I-joist flange property requirements are provided in [Table 14](#). The supporting header may be wood I-joist, LVL, LSL, PSL, or solid sawn lumber. The IHF Face Mount Hanger is cold-formed from No. 16 gage steel, and is prepunched for either 10d common or 16d common nails installed into the header and 10d-by-1 1/2-inch nails installed into the joist flanges. Diamond holes in the hanger flanges for hanger-to-header nailing provide for customizable (MIN/MAX) fastening to match the allowable download capacity needed as indicated in [Table 14](#). The IHF Face Mount Hanger dimensions and typical installations are shown in [Figure 14](#).

3.15 IHFL Face Mount Hanger:

The IHFL Face Mount Hanger is designed to resist the gravity and uplift loads from wood I-joists. Sized specifically for wood I-joists, the sides of the IHFL Face Mount Hanger provide lateral support to the I-joist top flange. The IHFL Face Mount Hanger is intended to support wood I-joists with flanges manufactured from sawn lumber or structural composite lumber (SCL). Design values for the IHFL Face Mount Hanger and I-joist flange property requirements are provided in [Table 15](#). The supporting header may be wood I-joist, LVL, LSL, PSL, or solid sawn lumber. The IHFL Face Mount Hanger is cold-formed from No. 18 gage steel, and is prepunched for 10d common nails installed into the header. Uplift resistance is provided by six Seat Cleat[®] prongs that lock the bottom flange of the I-joist to the hanger, providing a consistent uplift capacity for I-joist of all bottom flange thicknesses without the installation of hanger-to-joist nails. Additional uplift capacity is provided when two joist nails are installed into the joist bottom flange (see [Table 15](#) Footnote 6). Diamond holes in the hanger flanges for hanger-to-header nailing provide for customizable (MIN/MAX) fastening to match the allowable download capacity needed as indicated in [Table 15](#). The IHFL Face Mount Hanger dimensions and typical installation are shown in [Figure 15](#).

3.16 HDQIF Inverted Flange Face Mount Hangers:

The HDQIF Face Mount Inverted Flange Hanger is designed to support headers, joists, and trusses. The HDQIF Face Mount Hanger is cold-formed from No. 14 gage steel; and is prepunched for 1/4-inch-by-3-inch WS3 wood screws into supporting member, and either 1/4-inch-by-1 1/2-inch WS15 wood screws or 1/4-inch-by-3-inch MiTek WS3 wood screws into the supported member. WS Series wood screws are proprietary screws described in [ESR-2761](#) and are shipped with the hangers. See [Table 16](#) and [Figure 16](#) for product dimensions, fastener schedule, allowable loads and a typical installation detail.

3.17 JLIF-TZ Inverted Flange Face Mount Hangers:

The JLIF-TZ Inverted Flange Joist Hanger is designed as a face-mount hanger to support joists of nominal lumber dimensions. The JLIF-TZ is cold-formed from No. 18 gage steel; and is prepunched for 10d or 16d common nails into the header and 10d-by-1 1/2-inch nails into the joist. See [Table 17](#) and [Figure 17](#) for product dimensions, fastener schedule, allowable loads and a typical installation detail.

3.18 MUS Slant Nail Face Mount Joist Hangers:

The MUS Slant Nail Joist Hanger is designed for face-mount applications to provide double shear nailing for joist/truss-to-beam connections. The MUS Slant Nail Joist Hanger is cold-formed from No. 18 gage steel and is prepunched for 10d common nails into both the header and the joist. See [Table 18](#) and [Figure 18](#) for product dimensions, fastener schedule, allowable loads and a typical installation detail.

3.19 Materials:

3.19.1 Steel: The specific types of steel and corrosion protection for each product are described in [Table 19](#) of this report. Minimum steel base-steel thicknesses for the different gages are shown in the following table:

GAGE NO.	MINIMUM BASE-STEEL THICKNESS (inch)
20	0.033
18	0.044
16	0.055
14	0.070
12	0.099

For SI: 1 inch = 25.4 mm.

3.19.2 Wood: Wood members must be sawn lumber or structural glued laminated timber with a minimum specific gravity of 0.50, or approved structural engineered lumber (structural composite lumber, alternative strand lumber, or prefabricated wood I-joists) with a minimum equivalent specific gravity of 0.50, unless otherwise noted in the applicable table within this report. Wood members must have a moisture content not exceeding 19 percent (16 percent for structural glued laminated timber and structural engineered lumber products, except as noted in Section 4.1). For connectors installed with nails, the thickness of each wood member must be sufficient such that the specified fasteners do not protrude through the opposite side of the member, unless otherwise permitted in the applicable table within this report. Wood members that are structural engineered lumber must be recognized in, and used in accordance with, a current evaluation report. Refer to Section 3.19.4 for issues related to treated wood.

3.19.3 Fasteners: Required fastener types and sizes for use with the connectors described in this report are specified in this section and [Tables 1](#) through [18](#). Nails used for connectors described in this report must be bright or hot-dipped galvanized carbon steel nails complying with material requirements, physical properties, tolerances, workmanship, protective coating and finishes, and packaging and package marking requirements specified in ASTM F1667; and must have lengths, diameters and bending yield strengths as shown in the following table:

FASTENER DESIGNATION	FASTENER LENGTH (inches)	SHANK DIAMETER (inch)	MINIMUM REQUIRED F_{yb} (psi)
P-nail ¹	1.375	0.105	100,000
10d x 1 1/2	1.5	0.148	90,000
10d Common	3.0	0.148	90,000
16d Common	3.5	0.162	90,000

For SI: 1 inch = 25.4 mm, 1 psi = 6.895 kPa.

¹The fastener designation "P-nail" refers to power-driven nails described in [ESR-1539](#). The fastener must have a minimum diameter, length, and bending yield strength as specified in this table.

Alternatively, nails of other materials or finishes may be used when they are recognized in an ICC-ES evaluation report as having bending yield strength and withdrawal capacity equal to or better than those of a bright carbon steel of the same nominal diameter.

MiTek WS Series screws used for LGU/MGU/HGU and THDHQ hangers are described in [ESR-2761](#).

3.19.4 Use in Treated Wood: Connectors used in contact with preservative-treated or fire-retardant-treated wood must comply with Section 2304.10.6 of the 2024 and 2021 IBC (Section 2304.10.5 of the 2018 and 2015 IBC, and Section 2304.9.5 of the 2012 IBC) and Section R304.3 of the 2024 IRC (Section R317.3 of the 2021, 2018, 2015 and 2012 IRC). The lumber treater or the report holder (MiTek), or both, should be contacted for recommendations on the appropriate level of corrosion resistance to specify for the connectors. Fasteners used in contact with preservative-treated or fire-retardant-treated wood must be hot-dipped galvanized carbon steel nails. Alternatively, nails of other materials and finishes may be used when they are recognized in an ICC-ES evaluation report for use in the applicable treated lumber and have equivalent or greater capacities as those required in this report.

4.0 DESIGN AND INSTALLATION

4.1 Design:

The allowable load capacities in [Tables 1](#) through [18](#) are based on allowable stress design. The use of the allowable load values for the products listed in [Table 19](#) of this report must comply with all applicable requirements and conditions specified in this report. Tabulated allowable loads are for normal load duration and/or short load duration, based on load duration factors, C_D , in accordance with Section 11.3.2 of the *National Design Specification[®] for Wood Construction* (NDS) for the 2024, 2021, 2018 and 2015 IBC and IRC (Section 10.3.2 of the NDS for the 2012 IBC and IRC), as indicated in [Tables 1](#) through [18](#) of this report. No further increases are permitted for load durations other than those specified. Tabulated allowable loads are for connections in wood seasoned to a maximum moisture content of 19 percent (16 percent for structural glued laminated timber and structural engineered lumber products) or less, used under continuously dry conditions and where sustained temperatures are limited to 100°F (37.8°C) or less. When connectors are installed in wood having a moisture content greater than 19 percent (16 percent for engineered wood products), or where the in-service moisture content is expected to exceed this value, the applicable wet service factor, C_M , must be applied. Unless otherwise noted in the tables of this report, the applicable wet service factor, C_M , is as specified in the NDS for lateral loading of dowel-type fasteners. When connectors are installed in wood that will experience sustained exposure to temperatures exceeding 100°F (37.8°C), the allowable loads in this evaluation report must be adjusted by the temperature factor, C_t , specified in Section 11.3.4 of the NDS for the 2024, 2021, 2018 and 2015 IBC and IRC (Section 10.3.4 of the NDS for the 2012 IBC and IRC). Connected wood members must be checked for load-carrying capacity at the connection in accordance with NDS Section 11.1.2 for the 2024, 2021, 2018 and 2015 IBC and IRC (Section 10.1.2 of the NDS for the 2012 IBC and IRC).

4.2 Installation:

Installation of the connectors must be in accordance with this evaluation report and the manufacturer's published installation instructions.

4.3 Special Inspection:

4.3.1 Main Wind Force-Resisting Systems under the IBC: Periodic special inspection must be conducted for components within the main windforce-resisting system, where required in accordance with Sections 1704.2 and 1705.12 of the 2024 and 2021 IBC (Sections 1704.2 and 1705.11 of the 2018 and 2015 IBC and Section 1705.10 of the 2012 IBC).

4.3.2 Seismic Force-Resisting Systems under the IBC: Periodic special inspection must be conducted for components within the seismic force-resisting system, where required in accordance with Sections 1704.2 and 1705.13 of the 2024 and 2021 IBC (Sections 1704.2 and 1705.12 of the 2018 and 2015 IBC and Section 1705.11 of the 2012 IBC).

4.3.3 Installations under the IRC: Special inspections are normally not required for connectors used in structures regulated under the IRC. However, for components and systems requiring an engineered design in accordance with IRC Section R301, periodic special inspection requirements and exemptions must be in accordance with Sections 4.3.1 and 4.3.2 of this report.

5.0 CONDITIONS OF USE:

The MiTek Face Mount Hangers described in this report comply with, or are suitable alternatives to what is specified in, those codes listed in Section 1.0 of this report, subject to the following conditions:

- 5.1** The connectors must be manufactured, identified and installed in accordance with this report and the manufacturer's published installation instructions. A copy of the manufacturer's published installation instructions must be available at the jobsite at all times during installation. In the event of a conflict between this report and the manufacturer's published installation instructions, this report governs.
- 5.2** Calculations showing compliance with this report must be submitted to the code official. The calculations must be prepared by a registered design professional where required by the statutes of the jurisdiction in which the project is to be constructed.
- 5.3** Connected wood members and fasteners must comply with Sections 3.19.2 and 3.19.3, respectively.
- 5.4** Adjustment factors, noted in Section 4.1 of this report and the applicable codes, must be considered where applicable.
- 5.5** Use of connectors and fasteners with preservative-treated or fire-retardant-treated lumber must be in accordance with Section 3.19.4.
- 5.6** The connectors are manufactured under an approved quality control program with inspections by ICC-ES.

6.0 EVIDENCE SUBMITTED

Data in accordance with the [ICC-ES Acceptance Criteria for Joist Hangers and Similar Devices \(AC13\)](#), approved October 2018 (editorially revised February 2024).

7.0 IDENTIFICATION

- 7.1 The connectors described in this report are identified by the product model (stock) number, the number of the ICC-ES index evaluation report for MiTek ([ESR-2685](#)), and by one or more of the following designations: MiTek, USP or USP Structural Connectors.
- 7.2 The report holder's contact information is the following:

MITEK INC.
16023 SWINGLEY RIDGE ROAD
CHESTERFIELD, MISSOURI 63017
(800) 328-5934
www.mitek-us.com

TABLE 1—CLPBF BUTTERFLY HANGER ALLOWABLE LOADS^{1,2,3,4}

STOCK NO.	JOIST WIDTH (in.)	STEEL GA.	DIMENSIONS			FASTENER SCHEDULE				ALLOWABLE LOADS (lbs)			
			W	H	D	Header		Joist		Download			Uplift
						Qty	Type	Qty	Type	C _D =1.0	C _D =1.15	C _D =1.25	C _D =1.60
CLPBF	1½	18	1 ⁹ / ₁₆	2½	2½	12	10d Common	6	10d x 1½	1,340	1,340	1,340	195

For SI: 1 inch = 25.4 mm, 1 lb. = 4.45 N.

¹Allowable loads have been adjusted for load duration factors, C_D, as shown, in accordance with the NDS. The allowable loads do not apply to loads of other durations, and are not permitted to be adjusted for other load durations. See Sections 4.1 and 4.2 for additional design and installation requirements.

²See Section 3.19.3 for required fastener dimensions and mechanical properties.

³Allowable loads shown are for installations in wood members complying with Section 3.19.2. Wood members must also have a minimum reference compression perpendicular to grain design value, F_{c-perp}, of 625 psi (4.31 MPa).

⁴CLPBF hangers provide torsional resistance, up to a maximum joist depth of 3.5 inches (88.9 mm), where torsional resistance is defined as a moment not less than 75 pounds (334 N) times the depth of the joist, at which the lateral movement of the top or bottom of the joist with respect to the vertical position of the joist is 0.125 inch (3.2 mm).




FIGURE 1—CLPBF BUTTERFLY HANGER

TABLE 3—HUS SLANT NAIL JOIST HANGER ALLOWABLE LOADS^{1,2,3,4,6}

STOCKNO.	STEEL GAGE	DIMENSIONS (in.)				FASTENER SCHEDULE				ALLOWABLE DESIGN LOADS (lbs)			
		W	H	D	A	Header		Joist ⁵		Download			Uplift
						Qty	Type	Qty	Type	C _D = 1.0	C _D = 1.15	C _D = 1.25	
HUS26	16	1 ⁵ / ₈	5 ⁷ / ₁₆	3	2	14	16d Common	6	16d Common	2,760	3,140	3,400	2,045
HUS28	16	1 ⁵ / ₈	7 ³ / ₁₆	3	2	22	16d Common	8	16d Common	4,170	4,745	5,125	2,990
HUS210	16	1 ⁵ / ₈	9 ³ / ₁₆	3	2	30	16d Common	10	16d Common	5,455	5,825	6,060	4,110
HUS175	16	1 ¹³ / ₁₆	5 ³ / ₈	3	2	14	16d Common	6	16d Common	2,760	3,140	3,400	2,045
HUS177	16	1 ¹³ / ₁₆	7 ¹ / ₈	3	2	22	16d Common	8	16d Common	4,170	4,745	5,125	2,990
HUS179	16	1 ¹³ / ₁₆	9 ¹ / ₈	3	2	30	16d Common	10	16d Common	5,580	6,060	6,060	4,110
HUS24-2	14	3 ¹ / ₈	3 ⁷ / ₁₆	2	1	4	16d Common	2	16d Common	850	965	1,040	765
HUS26-2	14	3 ¹ / ₈	5 ¹ / ₄	2	1	4	16d Common	4	16d Common	1,085	1,235	1,330	1,170
HUS28-2	14	3 ¹ / ₈	7 ¹ / ₈	2	1	6	16d Common	6	16d Common	1,625	1,850	1,880	2,420
HUS210-2	14	3 ¹ / ₈	9 ¹ / ₈	2	1	8	16d Common	8	16d Common	2,170	2,465	2,660	2,420
HUS212-2	14	3 ¹ / ₈	11 ¹ / ₈	2	1	10	16d Common	10	16d Common	2,710	3,080	3,325	3,615
HUS46	14	3 ⁵ / ₈	5	2	1	4	16d Common	4	16d Common	1,085	1,235	1,330	1,170
HUS48	14	3 ⁵ / ₈	7	2	1	6	16d Common	6	16d Common	1,625	1,850	1,880	2,420
HUS410	14	3 ⁵ / ₈	8 ⁷ / ₈	2	1	8	16d Common	8	16d Common	2,170	2,465	2,660	2,420
HUS412	14	3 ⁵ / ₈	10 ⁷ / ₈	2	1	10	16d Common	10	16d Common	2,710	3,080	3,325	3,615

For SI: 1 inch = 25.4 mm, 1 lbf = 4.45 N.

¹Allowable loads have been adjusted for load duration factors, C_D, as shown, in accordance with the NDS. The allowable loads do not apply to loads of other durations, and are not permitted to be adjusted for other load durations. See Sections 4.1 and 4.2 for additional design and installation requirements.

²Allowable loads shown are for installations in wood members complying with Section 3.19.2. Wood members must also have a minimum reference compression perpendicular to grain design value, F_{C-perp}, of 625 psi (4.31 MPa).

³See Section 3.19.3 for required fastener dimensions and mechanical properties.

⁴HUS hangers provide torsional resistance, where torsional resistance is defined as a moment not less than 75 pounds (334 N) times the depth of the joist, at which the lateral movement of the top or bottom of the joist with respect to the vertical position of the joist is 0.125 inch (3.2 mm).

⁵Joist nails must be driven horizontally into the joist at an angle of 30° to 45° degrees from normal, such that they penetrate through the joist and into the header.

⁶HUS-IF inverted flange hangers are available in widths of 2¹/₄ inches or greater at the same design loads as corresponding HUS models.




FIGURE 3—HUS SLANT NAIL JOIST HANGER

TABLE 6—JUS SLANT NAIL JOIST HANGER ALLOWABLE LOADS^{1,2,3,4}

STOCK NO.	STEEL GAGE	DIMENSIONS (in.)				FASTENER SCHEDULE				ALLOWABLE DESIGN LOADS (lbs)			
		W	H	D	A	Header		Joist		Download			Uplift
						Qty	Type	Qty	Type	C _D = 1.0	C _D = 1.15	C _D = 1.25	C _D = 1.6
JUS24	18	1 ⁹ / ₁₆	3 ¹ / ₈	1 ³ / ₄	1	4	10d Common	2	10d Common	675	775	835	660
JUS26	18	1 ⁹ / ₁₆	4 ¹³ / ₁₆	1 ³ / ₄	1	4	10d Common	4	10d Common	870	1,000	1,080	1,050
JUS28	18	1 ⁹ / ₁₆	6 ⁵ / ₈	1 ³ / ₄	1	6	10d Common	4	10d Common	1,110	1,270	1,375	1,050
JUS210	18	1 ⁹ / ₁₆	7 ³ / ₄	1 ³ / ₄	1	8	10d Common	4	10d Common	1,350	1,545	1,670	1,050
JUS36	18	2 ⁹ / ₁₆	5 ¹ / ₄	2	1	4	16d Common	4	16d Common	1,040	1,185	1,290	1,270
JUS38	18	2 ⁹ / ₁₆	6 ³ / ₄	2	1	6	16d Common	4	16d Common	1,325	1,510	1,645	1,270
JUS310	18	2 ⁹ / ₁₆	9 ¹ / ₈	2	1	8	16d Common	6	16d Common	1,845	2,105	2,290	2,345
JUS24-2	18	3 ¹ / ₈	3 ⁷ / ₁₆	2	1	4	16d Common	2	16d Common	805	900	900	660
JUS26-2	18	3 ¹ / ₈	5 ¹ / ₄	2	1	4	16d Common	4	16d Common	1,040	1,185	1,290	1,270
JUS28-2	18	3 ¹ / ₈	7 ¹ / ₈	2	1	6	16d Common	4	16d Common	1,325	1,510	1,645	1,270
JUS210-2	18	3 ¹ / ₈	9 ¹ / ₈	2	1	8	16d Common	6	16d Common	1,845	2,105	2,290	2,345
JUS214-2	18	3 ¹ / ₈	13 ¹ / ₈	2	1	12	16d Common	6	16d Common	2,420	2,755	2,830	2,345
JUS44	18	3 ⁵ / ₈	3 ¹ / ₄	2	1	4	16d Common	2	16d Common	780	780	780	660
JUS46	18	3 ⁵ / ₈	5	2	1	4	16d Common	4	16d Common	1,040	1,185	1,290	1,270
JUS48	18	3 ⁵ / ₈	6 ⁷ / ₈	2	1	6	16d Common	4	16d Common	1,325	1,510	1,645	1,270
JUS410	18	3 ⁵ / ₈	8 ⁷ / ₈	2	1	8	16d Common	6	16d Common	1,845	2,105	2,290	2,345
JUS412	18	3 ⁵ / ₈	10 ⁷ / ₈	2	1	10	16d Common	6	16d Common	2,130	2,405	2,405	2,345
JUS414	18	3 ⁵ / ₈	12 ⁷ / ₈	2	1	12	16d Common	6	16d Common	2,405	2,405	2,405	2,345
JUS24-3	18	4 ⁵ / ₈	2 ³ / ₄	2	1	4	16d Common	2	16d Common	805	900	900	660
JUS26-3	18	4 ⁵ / ₈	4 ¹ / ₂	2	1	4	16d Common	4	16d Common	1,040	1,185	1,290	1,270
JUS28-3	18	4 ⁵ / ₈	6 ³ / ₈	2	1	6	16d Common	4	16d Common	1,325	1,510	1,645	1,270
JUS210-3	18	4 ⁵ / ₈	8 ³ / ₈	2	1	8	16d Common	6	16d Common	1,845	2,105	2,290	2,345
JUS212-3	18	4 ⁵ / ₈	10 ³ / ₈	2	1	10	16d Common	6	16d Common	2,130	2,405	2,405	2,345
JUS214-3	18	4 ⁵ / ₈	12 ³ / ₈	2	1	12	16d Common	6	16d Common	2,405	2,405	2,405	2,345

For SI: 1 inch = 25.4 mm, 1 lbf = 4.45 N.

¹Allowable loads have been adjusted for load duration factors, C_D, as shown, in accordance with the NDS. The allowable loads do not apply to loads of other durations, and are not permitted to be adjusted for other load durations. See Sections 4.1 and 4.2 for additional design and installation requirements.

²Allowable loads shown are for installations in wood members complying with Section 3.19.2. Wood members must also have a minimum reference compression perpendicular to grain design value, F_{c-perp}, of 625 psi (4.31 MPa).

³See Section 3.19.3 for required fastener dimensions and mechanical properties.

⁴JUS hangers provide torsional resistance, up to a maximum joist depth of H + 1.0 inch (H + 25.4 mm) where torsional resistance is defined as a moment not less than 75 pounds (334 N) times the depth of the joist, at which the lateral movement of the top or bottom of the joist with respect to the vertical position of the joist is 0.125 inch (3.2 mm).

⁵Joist nails must be driven horizontally into the joist at an angle of 30- to 45-degrees from normal, such that they penetrate through the joist and into the header.




FIGURE 6—JUS SLANT NAIL JOIST HANGER

TABLE 9—THDH FACE MOUNT HANGER ALLOWABLE LOADS^{1,2,3,4}

STOCK NO.	STEEL GAGE	DIMENSIONS (in.)			FASTENER SCHEDULE				ALLOWABLE LOADS (lbs)			
		W	H	D	Header		Joist		Download			Uplift
					Qty	Type	Qty	Type	C _D = 1.0	C _D = 1.15	C _D = 1.25	
THDH26	12	1 ⁵ / ₈	5 ⁷ / ₁₆	5	20	16d Common	8	16d Common	4,375	4,895	5,180	2,805
THDH28	12	1 ⁵ / ₈	7 ³ / ₁₆	5	36	16d Common	12	16d Common	7,595	8,175	8,175	4,345
THDH210	12	1 ⁵ / ₈	9 ³ / ₁₆	5	46	16d Common	16	16d Common	9,310	9,710	9,710	5,290
THDH27925	12	2 ³ / ₄	9 ¹ / ₈	4	46	16d Common	12	16d Common	9,020	9,020	9,020	4,345
THDH27112	12	2 ³ / ₄	10 ⁷ / ₈	4	56	16d Common	14	16d Common	9,710	9,710	9,710	4,345
THDH2714	12	2 ³ / ₄	12 ¹ / ₄	4	66	16d Common	16	16d Common	11,185	11,325	11,325	5,290
THDH26-2	12	3 ³ / ₁₆	5 ³ / ₈	4	20	16d Common	8	16d Common	4,375	4,895	5,180	2,805
THDH28-2	12	3 ³ / ₁₆	7 ¹ / ₈	4	36	16d Common	10	16d Common	7,360	8,175	8,175	3,000
THDH210-2	12	3 ³ / ₁₆	9 ¹ / ₈	4	46	16d Common	12	16d Common	9,020	9,020	9,020	4,345
THDH212-2	12	3 ³ / ₈	10 ¹ / ₂	4	56	16d Common	14	16d Common	9,710	9,710	9,710	4,345
THDH214-2	12	3 ³ / ₈	12 ¹ / ₄	4	66	16d Common	16	16d Common	11,325	11,325	11,325	5,290
THDH3210	12	3 ³ / ₁₆	9 ³ / ₈	4	46	16d Common	12	16d Common	9,020	9,020	9,020	4,345
THDH3212	12	3 ³ / ₁₆	10 ⁵ / ₈	4	56	16d Common	14	16d Common	9,710	9,710	9,710	5,290
THDH46	12	3 ³ / ₁₆	5 ³ / ₈	4	20	16d Common	8	16d Common	4,375	4,895	5,180	2,805
THDH48	12	3 ³ / ₁₆	7 ¹ / ₈	4	36	16d Common	10	16d Common	7,360	8,175	8,175	3,000
THDH410	12	3 ³ / ₁₆	9 ¹ / ₈	4	46	16d Common	12	16d Common	9,020	9,020	9,020	4,345
THDH412	12	3 ³ / ₁₆	10 ¹ / ₂	4	56	16d Common	14	16d Common	9,710	9,710	9,710	5,290
THDH414	12	3 ³ / ₁₆	13 ¹ / ₁₆	4	66	16d Common	16	16d Common	11,325	11,325	11,325	5,305
THDH26-3	12	5 ¹ / ₈	5 ⁷ / ₁₆	4	20	16d Common	8	16d Common	4,375	4,895	5,180	2,805
THDH28-3	12	5 ¹ / ₈	7 ³ / ₁₆	4	36	16d Common	12	16d Common	7,595	8,175	8,175	4,345
THDH210-3	12	5 ¹ / ₈	9 ³ / ₁₆	4	46	16d Common	16	16d Common	9,710	9,710	9,710	5,290
THDH212-3	12	5 ¹ / ₈	11 ³ / ₁₆	4	56	16d Common	20	16d Common	9,530	9,530	9,530	5,290
THDH214-3	12	5 ¹ / ₈	13 ³ / ₁₆	4	66	16d Common	22	16d Common	11,325	11,325	11,325	5,305
THDH5210	12	5 ³ / ₈	9 ¹ / ₈	4	46	16d Common	16	16d Common	9,710	9,710	9,710	5,290
THDH5212	12	5 ³ / ₈	11 ¹ / ₈	4	56	16d Common	20	16d Common	9,530	9,530	9,530	5,290
THDH5214	12	5 ³ / ₈	13 ¹ / ₈	4	66	16d Common	22	16d Common	11,325	11,325	11,325	5,305
THDH610	12	5 ¹ / ₂	9	4	46	16d Common	16	16d Common	9,020	9,020	9,020	5,290
THDH612	12	5 ¹ / ₂	11	4	56	16d Common	20	16d Common	9,530	9,530	9,530	5,290
THDH614	12	5 ¹ / ₂	13	4	66	16d Common	22	16d Common	11,325	11,325	11,325	5,305
THDH26-4	12	6 ³ / ₁₆	5 ⁷ / ₁₆	4	20	16d Common	8	16d Common	4,375	4,895	5,180	2,805
THDH28-4	12	6 ³ / ₁₆	7 ⁹ / ₁₆	4	36	16d Common	12	16d Common	7,595	8,175	8,175	4,345
THDH6710	12	6 ⁷ / ₈	8 ¹³ / ₁₆	4	46	16d Common	12	16d Common	9,020	9,020	9,020	4,345
THDH6712	12	6 ⁷ / ₈	10 ¹³ / ₁₆	4	56	16d Common	14	16d Common	9,020	9,020	9,020	5,290
THDH6714	12	6 ⁷ / ₈	12 ¹³ / ₁₆	4	66	16d Common	16	16d Common	11,325	11,325	11,325	5,305
THDH7210	12	7 ¹ / ₄	9	4	46	16d Common	12	16d Common	9,020	9,020	9,020	4,345
THDH7212	12	7 ¹ / ₄	10 ¹ / ₂	4	56	16d Common	14	16d Common	9,020	9,020	9,020	5,290
THDH7214	12	7 ¹ / ₄	12 ¹ / ₄	4	66	16d Common	16	16d Common	11,325	11,325	11,325	5,305

For **SI**: 1 inch = 25.4 mm, 1 lbf = 4.45 N.

¹Allowable loads have been adjusted for load duration factors, C_D, as shown, in accordance with the NDS. The allowable loads do not apply to loads of other durations, and are not permitted to be adjusted for other load durations. See Sections 4.1 and 4.2 for additional design and installation requirements.

²Allowable loads shown are for installations in wood members complying with Section 3.19.2. Wood members must also have a minimum reference compression perpendicular to grain design value, F_{c-perp}, of 625 psi (4.31 MPa).

³See Section 3.19.3 for required fastener dimensions and mechanical properties.

⁴THDH hangers provide torsional resistance, up to a maximum joist depth of H + 1.0 inch (H + 25.4 mm) where torsional resistance is defined as a moment not less than 75 pounds (334 N) times the depth of the joist, at which the lateral movement of the top or bottom of the joist with respect to the vertical position of the joist is 0.125 inch (3.2 mm).

⁵Joist nails must be driven horizontally into the joist at an angle of 30- to 45-degrees from normal, such that they penetrate through the joist, and into the header.



FIGURE 9—THDH FACE MOUNT HANGER

TABLE 19—STEEL TYPE, STRENGTH AND CORROSION RESISTANCE

Product	Steel	Coating ¹
CLPBF Butterfly Hanger	ASTM A653, SS designation, Grade 40	G90
HD Face Mount Hanger	ASTM A653, SS designation, Grade 40	G90
HUS Slant Nail Joist Hanger	ASTM A653, SS designation, Grade 40	G90, G185
JL Standard Joist Hanger	ASTM A653, SS designation, Grade 40	G90
JN Power Nail Hanger	ASTM A653, SS designation, Grade 40	G90
JNE Power Nail Hanger	ASTM A653, SS designation, Grade 40	G90
JUS Slant Nail Joist Hanger	ASTM A653, SS designation, Grade 40	G90, G185
SUH Joist Hanger	ASTM A653, SS designation, Grade 40	G90
THD Face Mount Hanger	ASTM A653, SS designation, Grade 40	G90, G185
THDH Face Mount Hanger	ASTM A653, SS designation, Grade 40	G90, G185
THF Face Mount Hanger	ASTM A653, SS designation, Grade 40	G90
THFI Face Mount Hanger	ASTM A653, SS designation, Grade 40	G90
LGU/MGU/HGU Girder Hanger	ASTM A653, SS designation, Grade 40	G90
THDHQ Girder Truss Hanger	ASTM A653, SS designation, Grade 40	G90
IHF Face Mount Hanger	ASTM A653, SS designation, Grade 40	G90
IHFL Face Mount Hanger	ASTM A653, SS designation, Grade 40	G90
HDQIF Inverted Flange Face Mount Hangers	ASTM A653, SS designation, Grade 40	G90
JLIF-TZ Inverted Flange Face Mount Hangers	ASTM A653, SS designation, Grade 40	G185
MUS Slant Nail Face Mount Joist Hangers	ASTM A653, SS designation, Grade 40	G90

¹Corrosion protection is a zinc coating in accordance with ASTM A653.

ICC-ES Evaluation Report

ESR-3445 City of LA Supplement

Reissued October 2024

Revised December 2024

This report is subject to renewal October 2026.

www.icc-es.org | (800) 423-6587 | (562) 699-0543

A Subsidiary of the International Code Council®

DIVISION: 06 00 00—WOOD, PLASTICS AND COMPOSITES
Section: 06 05 23—Wood, Plastic, and Composite Fastenings

REPORT HOLDER:

MITEK® INC.

EVALUATION SUBJECT:

MITEK® FACE MOUNT HANGERS FOR WOOD FRAMED CONSTRUCTION

1.0 REPORT PURPOSE AND SCOPE

Purpose:

The purpose of this evaluation report supplement is to indicate that MiTek face mount hangers for wood framed construction, described in ICC-ES evaluation report [ESR-3445](#), have also been evaluated for compliance with the codes noted below as adopted by the Los Angeles Department of Building and Safety (LADBS).

Applicable code editions:

- 2023 *City of Los Angeles Building Code* ([LABC](#))
- 2023 *City of Los Angeles Residential Code* ([LARC](#))

2.0 CONCLUSIONS

The MiTek face mount hangers for wood framed construction, described in Sections 2.0 through 7.0 of the evaluation report [ESR-3445](#), comply with the LABC Chapter 23, and the LARC, and are subject to the conditions of use described in this supplement.

3.0 CONDITIONS OF USE

The MiTek face mount hangers for wood framed construction, described in this evaluation report supplement must comply with all of the following conditions:

- All applicable sections in the evaluation report [ESR-3445](#).
- The design, installation, conditions of use and identification are in accordance with the 2021 *International Building Code*® (IBC) provisions noted in the evaluation report [ESR-3445](#).
- The design, installation and inspection are in accordance with additional requirements of LABC Chapters 16 and 17, as applicable.
- The supported end of joist or beam must be within 1/4-inch from the supporting member.
- Solid blocking must be required for all joist hangers supporting roof joists having one end twisted more than one-half degree per foot of length relative to the other end, except as specifically noted in the evaluation report.
- Under the LARC, an engineered design in accordance with LARC Section R301.1.3 must be submitted.

This evaluation report supplement expires concurrently with the evaluation report ESR-3445, reissued October 2024 and revised December 2024.

DIVISION: 06 00 00—WOOD, PLASTICS AND COMPOSITES

Section: 06 05 23—Wood, Plastic, and Composite Fastenings

REPORT HOLDER:

MITEK®, INC.

EVALUATION SUBJECT:

MITEK® FACE MOUNT HANGERS FOR WOOD FRAMED CONSTRUCTION

1.0 REPORT PURPOSE AND SCOPE

Purpose:

The purpose of this evaluation report supplement is to indicate that MiTek face mount hangers for wood framed construction, described in ICC-ES evaluation report ESR-3445, have also been evaluated for compliance with the codes noted below.

Applicable code editions:

- 2023 Florida Building Code—Building
- 2023 Florida Building Code—Residential

2.0 CONCLUSIONS

The MiTek face mount hangers for wood wood framed construction, described in Sections 2.0 through 7.0 of the evaluation report ESR-3445, comply with the *Florida Building Code—Building* and the *Florida Building Code—Residential*. The design requirements must be determined in accordance with the *Florida Building Code—Building* or the *Florida Building Code—Residential*, as applicable. The installation requirements noted in the evaluation report ESR-3445 for the 2021 *International Building Code*® meet the requirements of the *Florida Building Code—Building* or the *Florida Building Code—Residential*, as applicable.

Use of the MiTek face mount hangers for wood framed construction has also been found to be in compliance with the High-Velocity Hurricane Zone (HVHZ) provisions of the *Florida Building Code—Building* and the *Florida Building Code—Residential* with the following condition:

- a) For connections subject to uplift, the connection must be designed for no less than 700 pounds (3114 N).

For products falling under Florida Rule 61G20-3, verification that the report holder's quality assurance program is audited by a quality assurance entity approved by the Florida Building Commission for the type of inspections being conducted is the responsibility of an approved validation entity (or the code official, when the report holder does not possess an approval by the Commission).

This evaluation report supplement expires concurrently with the evaluation report ESR-3445, reissued October 2024 and revised December 2024.



Product Approval
USER: Public User

[Product Approval Menu](#) > [Product or Application Search](#) > [Application List](#) > **Application Detail**

► OFFICE OF THE
SECRETARY

FL #

FL17236-R10

Application Type

Revision

Code Version

2023

Application Status

Approved

*Approved by DBPR. Approvals by DBPR shall be reviewed and ratified by the POC and/or the Commission if necessary.

Comments

Archived



Product Manufacturer

MiTek Inc.

Address/Phone/Email

16023 Swingley Ridge Road
Chesterfield, MO 63017
(800) 328-5934
bpr@mii.com

Authorized Signature

Erin Walden
bpr@mii.com

Technical Representative

Erin M. Walden

Address/Phone/Email

16023 Swingley Ridge Road
Chesterfield, MO 63017
(952) 898-8635
ewalden@mii.com

Quality Assurance Representative

Erin M. Walden

Address/Phone/Email

16023 Swingley Ridge Road
Chesterfield, MO 63017
(952) 898-8635
ewalden@mii.com

Category

Structural Components

Subcategory

Wood Connectors

Compliance Method

Evaluation Report from a Product Evaluation Entity

Evaluation Entity

ICC Evaluation Service, LLC

Quality Assurance Entity

ICC-ES Evaluation Service, LLC

Quality Assurance Contract Expiration Date

10/31/2026

Validated By

ICC Evaluation Service, LLC.

Certificate of Independence

[FL17236_R10_COI_ICC-ES Certification of Independence for Evaluation 2024 \(1\).pdf](#)

Referenced Standard and Year (of Standard)

Standard

Year

ANSI/AWC NDS

2018

ASTM D7147

2011

Equivalence of Product Standards
Certified By

Sections from the Code

Product Approval Method

Method 1 Option C

Date Submitted

10/24/2024

Date Validated

10/24/2024

Date Pending FBC Approval

Date Approved

10/26/2024

Summary of Products

FL #	Model, Number or Name	Description
17236.1	BN264, BN284	BN Breakfast Nook Hanger
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.2	DSC4L/R, LDSC4L/R	DSC/LDSC Drag Strut Connector
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.3	FTC1, FTC1F, FTC2, FTC2F	FTC Floor Truss Clip
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.4	FTC32	FTC Floor Truss Clip
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.5	GT2T2B, GT2T2BH, GT2T3B, GT2T4B, GT2T6B, GT2T6BH, GT2T8B, GT3T3B, GT3T3BH, GT3T4B, GT3T4BH, GT3T6B, GT3T6BH, GT3T8B, GT3T8BH, GT4T4B, GT4T4BH, GT4T6B, GT4T6BH, GT4T8B, GT5T8BH	GT Girder Truss Hanger
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.6	HCPRS	HCPRS Hurricane/Seismic Anchor
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.7	HGA10	HGA Hurricane Gusset Angle
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC



Impact Resistant: N/A Design Pressure: N/A Other:		Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.8	HHCP2	HHCP Hurricane/Seismic Anchor
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.9	HHCP4	HHCP Hurricane/Seismic Anchor
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.10	HJC26, HJC28	HJC Hip/Jack Connector
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.11	RT3A, RT4, RT5, RT6, RT7, RT7A, RT7AT, RT10, RT15	RT Hurricane Tie
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.12	RT8A, RT16-2, RT16A, RT16AR, RT20	RT Hurricane Tie
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.13	SBP4, SBP6	SBP Supplementary Bearing Plate
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.14	STC24, STC26, STC28	STC Scissor Truss Clip
Limits of Use Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf
17236.15	TSP	TSP Stud Plate Tie
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: N/A Design Pressure: N/A Other:		Installation Instructions FL17236_R10_II_ESR-3448_Oct_2024.pdf Verified By: ICC Evaluation Service, LLC Created by Independent Third Party: Evaluation Reports FL17236_R10_AE_ESR-3448_Oct_2024.pdf

ICC-ES Evaluation Report

ESR-3448

Reissued October 2024

This report also contains:

- [City of LA Supplement](#)

Subject to renewal October 2026

- [FL Supplement w/ HVHZ](#)

ICC-ES Evaluation Reports are not to be construed as representing aesthetics or any other attributes not specifically addressed, nor are they to be construed as an endorsement of the subject of the report or a recommendation for its use. There is no warranty by ICC Evaluation Service, LLC, express or implied, as to any finding or other matter in this report, or as to any product covered by the report.

Copyright © 2024 ICC Evaluation Service, LLC. All rights reserved.

DIVISION: 06 00 00— WOOD, PLASTICS AND COMPOSITES Section: 06 05 23— Wood, Plastic, and Composite Fastenings	REPORT HOLDER: MITEK® INC. ADDITIONAL LISTEE: THE HOME DEPOT MiTek®	EVALUATION SUBJECT: MITEK TRUSS CONNECTORS FOR WOOD-FRAMED CONSTRUCTION	
--	---	--	---

1.0 EVALUATION SCOPE

Compliance with the following codes:

- 2024, 2021, 2018, 2015 and 2012 [International Building Code® \(IBC\)](#)
- 2024, 2021, 2018, 2015 and 2012 [International Residential Code® \(IRC\)](#)

Property evaluated:

Structural

2.0 USES

The MiTek structural connectors described in this report (see Table 14 for a complete listing) are used to connect wood framing members in accordance with Section 2304.10.4 of the 2024 and 2021 IBC (Section 2304.10.3 of the 2018 and 2015 IBC and Section 2304.9.3 of the 2012 IBC). The connectors may also be used in structures regulated under the IRC when an engineered design is submitted to, and approved by, the code official, in accordance with Section R301.1.3 of the IRC.

3.0 DESCRIPTION

3.1 BN Breakfast Nook Hanger:

The BN Breakfast Nook Hanger is designed to connect four sets of mono-trusses or other wood-framing members in the traditional “breakfast nook” configuration. The hanger is cold-formed from No. 14 gage steel, and is prepunched for installation with 10d common nails into the header and 10d by 1½-inch-long nails into the joist. The hanger joints are factory-welded with ⅛-inch (3.2 mm) fillet welds. See [Table 1](#) and [Figure 1](#) for product dimensions, fastener schedule, allowable loads, and typical installation details.

3.2 LDSC4 and DSC4 Drag Strut Connectors:

The LDSC4 and DSC4 Drag Strut Connectors are designed to tie wooden truss chord members to the top plates in a wall system. The connectors are fabricated from No. 14 gage or No. 3 gage hot-rolled steel. The DSC4 is prepunched with holes for installation with MiTek Pro Series WS3 wood screws, which are provided with the device. The LDSC4 Drag Strut is prepunched for installation with 10d by 1½-inch-long nails. See [Table 2](#) and [Figure 2](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.3 FTC Floor Truss Clip:

The FTC Floor Truss Clip is designed to transfer vertical loads between two floor trusses having single-ply chords or double-ply chords to allow the two trusses to act as a single floor girder truss. The clip is cold-formed from 18 gage steel, and is prepunched for 10d common or 10d by 1½-inch-long nails. See [Table 3](#) and [Figure 3](#) for product dimensions, fastener schedule, allowable loads, and typical installation details.

3.4 GT Girder Truss Hanger:

The GT girder truss hanger is designed to hang girder trusses off of other girder trusses or other wood supporting members. The U-shaped portion of the hanger is fabricated from No. 7 gage hot-rolled steel plate, and is factory welded to the back plate, which is fabricated from No. 3 gage hot-rolled steel plate. The U-shaped portion of the hanger is prepunched for installation with 16d common nails, and the back plate of the hanger is provided with holes allowing the installation of either ¾-inch- or 1-inch-diameter (19.1 or 25.4 mm) bolts. See [Tables 4A](#) and [4B](#) for product dimensions and required fasteners, [Table 4B](#) for allowable loads, and [Figure 4](#) for a typical installation detail.

3.5 HCPRS Hurricane/Seismic Anchor:

The HCPRS Hurricane/Seismic Anchor is designed to tie trusses and rafters to top plates for the purpose of resisting uplift, lateral and transverse loads. The anchor is cold-formed from No. 18 gage steel, and is prepunched for installation with 8d common or 8d by 1½-inch-long nails. See [Table 5](#) and [Figure 5](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.6 HGA10 Hurricane Gusset Angle:

The HGA10 Hurricane Gusset Angle is a connector designed to connect trusses, joists, or rafters to top plates. The connector is cold-formed from No. 14 gage steel, and is prepunched for installation with MiTek Pro Series WS3 or WS15 wood screws, which are supplied with the device. See [Table 6](#) and [Figure 6](#) for product dimensions, fastener schedule, allowable loads, and typical installation details.

3.7 HHCP Hurricane/Seismic Anchor:

The HHCP Hurricane/Seismic Anchors are designed to connect hip rafters or trusses to wall top plates, such that the rafter or truss bisects the 90-degree angle between the two intersecting wall planes. The HHCP2 anchor is cold-formed from No. 18 gage steel, and is prepunched for installation with 10d by 1½-inch-long nails. The HHCP4 anchor is cold-formed from No. 16 gage steel and is prepunched for installation with 10d common nails. See [Table 7](#) and [Figure 7](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.8 HJC Hip/Jack Connectors:

The HJC Hip/Jack Connectors are designed to support single-ply hip and jack trusses from double-ply girder trusses. The hip truss is installed at 45 degrees with respect to the jack truss. The HJC series connectors are cold-formed from No. 12 gage steel, and are prepunched for installation with 16d common nails to be installed into the supporting truss or girder bottom chord and 10d common nails for nailing into the hip and jack members. See [Table 8](#) and [Figure 8](#) for product dimensions, fastener schedule, allowable loads, and typical installation details.

3.9 RT Hurricane Tie:

The RT Hurricane Ties are designed to connect roof rafters and trusses to their supporting construction. All RT series connectors, except the RT10 and the RT20, connect roof rafters or trusses to the top plate. The RT10 and RT20 connect the rafter or truss to both the top plate and the vertical wall stud below. RT connectors are fabricated from No. 18 or No. 16 gage steel, and are prepunched for installation with 8d common, 8d by 1½-inch-long, 10d common or 10d by 1½-inch-long nails. See [Table 9](#) and [Figure 9](#) for product dimensions, fastener schedule, allowable loads, and typical installation details.

3.10 SBP Supplementary Bearing Plate:

The SBP supplementary bearing plate is used to connect rafters and trusses to the top plate, to resist uplift loads, as well as in-plane horizontal loads parallel and perpendicular to the top plate. The SBP supplementary bearing plate is provided as a two-piece installation (one on each side of the member being supported). The SBP plate is cold-formed from No. 16 gage steel, and is prepunched for installation with 10d common nails into the plate and either 10d common nails or 10d by 1½-inch-long nails into the truss. See [Table 10](#) and [Figure 10](#) for product dimensions, fastener schedules, allowable loads, and a typical installation detail.

3.11 STC Scissor Truss Clip:

The STC Scissor Truss Clip is designed to connect a single-ply scissor truss to nominally 2-by-4, 2-by-6 or 2-by-8 wall top plates. The connector is cold-formed from No. 12 gage steel, and has prepunched horizontal nail slots for horizontal adjustment of the scissor truss, and prepunched flanges for installation with 10d by

1½-inch-long nails into wall top plates. See [Table 11](#) and [Figure 11](#) for product dimensions, fastener schedule, allowable loads, and a typical installation detail.

3.12 TSP Stud Plate Tie:

The TSP Stud Plate Tie is designed to connect a single or double top plate or sill plate to a wall stud, and can also be used for connecting a roof rafter or truss to the top plate of a supporting wall. Optional diamond nail holes allow for various uplift capacities for single or double plate installation conditions. Single top plate or sill plate applications require the installation of the specified nails into all round holes of the connector. Double top plate to stud connections and truss/rafter to double top plate connections (rafter tie application) require the installation of the specified nails into all round and all diamond holes of the connector to support the increased loads. TSP connectors are fabricated from No. 16 gage steel and are prepunched for installation with 10d by 1½-inch-long or 10d common nails. See [Tables 12A](#), [12B](#) and [Figure 12](#) for product dimensions, fastener schedules, allowable loads, and typical installation details.

3.13 Materials:

3.13.1 Steel: The specific types of steel and corrosion protection for each product are described in [Table 13](#) of this evaluation report. Minimum base-steel thicknesses for the different gages are shown in the following table:

GAGE NO.	MINIMUM BASE-STEEL THICKNESS (inch)
18	0.044
16	0.055
14	0.070
12	0.099
7	0.171
3	0.240

For SI: 1 inch = 25.4 mm.

3.13.2 Wood: Wood members must be sawn lumber or structural glued laminated timber (glulam) with a minimum specific gravity of 0.50, or approved structural composite lumber (SCL) with a minimum equivalent specific gravity of 0.50, unless otherwise noted in the applicable table within this report. Wood members must have a moisture content not exceeding 19 percent (16 percent for glulam and SCL), except as noted in Section 4.1. For connectors installed with nails in compliance with Section 3.13.3.2, or MiTek Pro Series WS wood screws, in compliance with Section 3.13.3.3, the thickness of each wood member must be sufficient such that the specified fasteners do not protrude through the opposite side of the member, unless otherwise permitted in the applicable table within this report. Refer to Section 3.13.4 for issues related to treated wood.

3.13.3 Fasteners: Required fastener types and sizes for use with the MiTek connectors described in this evaluation report are specified in Sections 3.13.3.1 through 3.13.3.3 and in [Tables 1](#) through [12](#).

3.13.3.1 Bolts: At a minimum, bolts must comply with ASTM A36 or ASTM A307, and must have a minimum bending yield strength of 45,000 psi (310 MPa). Bolt diameters must be as specified in the applicable tables of this evaluation report.

3.13.3.2 Nails: Nails used for connectors described in this report must be bright or hot-dipped galvanized carbon steel nails complying with material requirements, physical properties, tolerances, workmanship, protective coating and finishes, and packaging and package marking requirements specified in ASTM F1667; and must have lengths, diameters and bending yield strengths, F_{yb} , as shown in the following table:

FASTENER DESIGNATION	FASTENER LENGTH (inches)	SHANK DIAMETER (inch)	MINIMUM REQUIRED F_{yb} (psi)
8d - 1½	1.5	0.131	100,000
8d common	2.5	0.131	100,000
10d common	3.0	0.148	90,000
10d - 1½	1.5	0.148	90,000
16d common	3.5	0.162	90,000

For SI: 1 inch = 25.4 mm, 1 psi = 6,895 Pa.

Alternatively, nails of other materials or finishes may be used when they are recognized in an ICC-ES evaluation report as having bending yield strength and withdrawal capacity equal to or better than those of a bright carbon steel of the same nominal diameter.

3.13.3.3 MiTek Pro Series Wood Screws: The WS wood screws used with the HGA and DSC connectors must be MiTek Pro Series WS3 and WS15 wood screws, as described in [ESR-2761](#). The appropriate size of WS series wood screw must be used, as indicated in the applicable tables of this evaluation report.

3.13.4 Use in Treated Wood: Connectors used in contact with preservative-treated or fire-retardant-treated wood must comply with Section 2304.10.6 of the 2024 and 2021 IBC (Section 2304.10.5 of the 2018 and 2015 IBC and Section 2304.9.5 of the 2012 IBC) and Section R304.3 of the 2024 IRC (Section R317.3 of the 2021, 2018, 2015 and 2012 IRC). The lumber treater or the holder of this report (MiTek USA, Inc.), or both, should be contacted for recommendations on the appropriate level of corrosion resistance for the connectors and fasteners as well as the connection capacities of the fasteners used with the specific proprietary preservative-treated or fire-retardant-treated lumber. Nails must be hot-dipped galvanized carbon steel nails. Alternatively, nails of other materials and finishes may be used when they are recognized in an ICC-ES evaluation report for use in the applicable treated lumber and have equivalent or greater capacities as those required in this report.

4.0 DESIGN AND INSTALLATION

4.1 Design:

The allowable loads given in [Tables 1](#) through [12](#) are based on allowable stress design. The use of the allowable loads for the products listed in [Table 13](#) must comply with all applicable requirements and conditions specified in this evaluation report. The tabulated allowable loads are for normal load duration and/or short load duration, based on load duration factors, C_D , in accordance with Section 11.3.2 of the 2024, 2018 and 2015 *National Design Specification® for Wood Construction* (NDS), as indicated in [Tables 1](#) through [12](#) of this evaluation report (Section 10.3.2 of the 2012 NDS for the 2012 IBC and IRC). No further increases are permitted for load durations other than those specified. The tabulated allowable loads are for connections in wood used under continuously dry conditions where the maximum moisture content in wood is 19 percent (16 percent for SCL) or less, and sustained temperatures are limited to 100°F (37.8°C) or less. When connectors are installed in wood having a moisture content greater than 19 percent (16 percent for SCL), or where the in-service moisture content in wood is expected to exceed this value, the applicable wet service factor, C_M , for dowel-type fasteners must be applied, unless otherwise noted in the tables of this report. When connectors are installed in wood that will experience sustained exposure to temperatures exceeding 100°F (37.8°C), the allowable loads in this evaluation report must be adjusted by the temperature factor, C_t , specified in the NDS. The group action factor, C_g , in the NDS, has been accounted for, in the tabulated allowable loads, where applicable. For connectors installed with bolts, minimum edge distances and end distances within the wood members must be met, such that the geometry factor, C_A , is 1.0, in accordance with 2024, 2018 and 2015 NDS Section 12.5.1 (2012 NDS Section 11.5.1 for the 2012 IBC and IRC). Connected wood members must be checked for load-carrying capacity at the connection in accordance with 2024, 2018 and 2015 NDS Section 11.1.2 (2012 NDS Section 10.1.2 for the 2012 IBC and IRC).

4.2 Installation:

Installation of the MiTek connectors must be in accordance with this evaluation report and the manufacturer's published installation instructions. Bolts must be installed in accordance with 2024, 2018 and 2015 NDS Section 12.1.3 (2012 NDS Section 11.1.3 for the 2012 IBC and IRC). MiTek Pro Series wood screws must be installed in accordance with [ESR-2761](#).

4.3 Special Inspection:

4.3.1 Main Wind-Force-Resisting System under the IBC: Periodic special inspection must be conducted for components within the main wind-force-resisting system, where required in accordance with Sections 1704.2 and 1705.12 of the 2024 and 2021 IBC (Sections 1704.2 and 1705.11 of the 2018 and 2015 IBC, or Sections 1704.2 and 1705.10 of the 2012 IBC) as applicable.

4.3.2 Seismic-Force-Resisting System under the IBC: Periodic special inspection must be conducted for components within the seismic-force-resisting system, where required, in accordance with Sections 1704.2 and 1705.13 of the 2024 and 2021 IBC (Sections 1704.2 and 1705.12 of the 2018 and 2015 IBC, or Sections 1704.2 and 1705.11 of the 2012 IBC) as applicable.

4.3.3 Installation under the IRC: Special inspections are normally not required for connectors used in structures regulated under the IRC. However, for components and systems requiring an engineered design in accordance with IRC Section R301, periodic special inspection requirements and exemptions must be in accordance with Sections 4.3.1 and 4.3.2 of this report.

5.0 CONDITIONS OF USE:

The MiTek connectors described in this report comply with, or are suitable alternatives to what is specified in, those codes listed in Section 1.0 of this report, subject to the following conditions:

- 5.1 The connectors must be manufactured, identified, designed, and installed in accordance with this report and the manufacturer's published installation instructions. A copy of the manufacturer's published installation instructions must be available at the jobsite at all times during installation. In the event of a conflict between this report and the manufacturer's published installation instructions, this report governs.
- 5.2 Calculations showing compliance with this report must be submitted to the code official. The calculations must be prepared by a registered design professional where required by the statutes of the jurisdiction in which the project is to be constructed.
- 5.3 Connected wood members and fasteners must comply with Sections 3.13.2 and 3.13.3, respectively.
- 5.4 Adjustment factors, noted in Section 4.1 of this report and the applicable codes, must be considered where applicable.
- 5.5 Use of connectors and fasteners with preservative-treated or fire-retardant-treated lumber must be in accordance with Section 3.13.4.
- 5.6 Factory-welded connectors identified in [Table 14](#) are manufactured at the designated facilities under an approved quality control program with inspections by ICC-ES.

6.0 EVIDENCE SUBMITTED

Data in accordance with the [ICC-ES Acceptance Criteria for Joist Hangers and Similar Devices \(AC13\)](#), dated October 2018 (editorially revised February 2024).

7.0 IDENTIFICATION

- 7.1 The connectors described in this report are identified by the product model (stock) number, the number of the ICC-ES index evaluation report for MiTek ([ESR-2685](#)), and by one or more of the following designations: MiTek, USP, or Structural Connectors.

- 7.2 The report holder's contact information is the following:

MITEK[®] INC.
16023 SWINGLEY RIDGE ROAD
CHESTERFIELD, MISSOURI 63017
(800) 328-5934
www.mitek-us.com
uspcustomerservice@mii.com

- 7.3 The Additional Listee's contact information is the following:

THE HOME DEPOT
2455 PACES FERRY ROAD SE
ATLANTA, GEORGIA 30339
(678) 216-8204
www.homedepot.com

TABLE 8—HJC HIP/JACK CONNECTOR ALLOWABLE LOADS^{1,2,3}

STOCK NO.	STEEL GAGE	DIMENSIONS (in.)			FASTENER SCHEDULE				ALLOWABLE LOADS (lbs)		
		W	H	D	Carrying Truss		Carried Trusses		Download ⁴		Uplift ⁵
					Qty.	Type	Qty.	Hip			
HJC26	12	6	5 ³ / ₈	3 ¹ / ₄	16	16d common	7	5	C _D =1.0	C _D =1.15	C _D =1.25
HJC28	12	6	7 ¹ / ₈	3 ¹ / ₄	20	16d common	8	6	2,750	3,055	3,265
									3,385	3,385	3,385
											2,345
											2,345

For SI: 1 inch = 25.4 mm, 1 lb = 4.45 N, 1 psi = 6,895 Pa.

¹Allowable loads have been adjusted for load duration factors, C_D, as shown, in accordance with the NDS. The allowable loads do not apply to loads of other durations, and are not permitted to be adjusted for other load durations. See Sections 4.1 and 4.2 for additional design and installation requirements.

²Allowable loads are for installations in wood members complying with Section 3.13.2. Wood members must also have a minimum reference compression perpendicular to grain design value, F_{C-perp}, of 625 psi (4.31 MPa).

³See Section 3.13.3 for required fastener dimensions and mechanical properties.

⁴Allowable download is the total allowable download for the hip and jack trusses combined, and assume that 75% of the total load is distributed to the hip truss and 25% is distributed to the jack truss.

⁵Allowable uplift loads on the HJC26 and HJC28 are the total allowable uplift loads for the hip and jack trusses combined, and assume that 75% of the total load is distributed to the hip truss and 25% is distributed to the jack truss.




FIGURE 8—HJC AND HTHJ HIP JACK CONNECTOR

DIVISION: 06 00 00—WOOD, PLASTICS AND COMPOSITES
Section: 06 05 23—Wood, Plastic, and Composite Fastenings

REPORT HOLDER:

MITEK® INC.

EVALUATION SUBJECT:

MITEK TRUSS CONNECTORS FOR WOOD-FRAMED CONSTRUCTION

1.0 REPORT PURPOSE AND SCOPE**Purpose:**

The purpose of this evaluation report supplement is to indicate that MiTek truss connectors for wood-framed construction, described in ICC-ES evaluation report [ESR-3448](#), have also been evaluated for compliance with the codes noted below as adopted by the Los Angeles Department of Building and Safety (LADBS).

Applicable code editions:

- 2023 *City of Los Angeles Building Code* ([LABC](#))
- 2023 *City of Los Angeles Residential Code* ([LARC](#))

2.0 CONCLUSIONS

The MiTek truss connectors for wood-framed construction, described in Sections 2.0 through 7.0 of the evaluation report [ESR-3448](#), comply with the LABC Chapter 23, and the LARC, and are subjected to the conditions of use described in this supplement.

3.0 CONDITIONS OF USE

MiTek truss connectors for wood-framed construction, described in this evaluation report supplement must comply with all of the following conditions:

- All applicable sections in the evaluation report [ESR-3448](#).
- The design, installation, conditions of use and identification are in accordance with the 2021 *International Building Code*® (IBC) provisions noted in the evaluation report [ESR-3448](#).
- The design, installation and inspection are in accordance with additional requirements of LABC Chapters 16 and 17, as applicable.
- Allowable loads in tables are for the wood fastening devices and their fasteners. The connected member shall be checked for capacity (which may govern).
- The supported end of joist or beam must be within 1/4-inch from the supporting member.
- Solid blocking must be required for all joist hangers supporting roof joists having one end twisted more than one-half degree per foot of length relative to the other end, except as specifically noted in the evaluation report [ESR-3448](#).
- Under the LARC, an engineered design in accordance with LARC Section R301.1.3 must be submitted.

This supplement expires concurrently with the evaluation report ESR-3448, reissued October 2024.

DIVISION: 06 00 00—WOOD, PLASTICS AND COMPOSITES
Section: 06 05 23—Wood, Plastic, and Composite Fastenings

REPORT HOLDER:

MITEK® INC.

EVALUATION SUBJECT:

MITEK TRUSS CONNECTORS FOR WOOD-FRAMED CONSTRUCTION

1.0 REPORT PURPOSE AND SCOPE**Purpose:**

The purpose of this evaluation report supplement is to indicate that the MiTek Truss Connectors for Wood-Framed Construction, described in ICC-ES evaluation report ESR-3448, have also been evaluated for compliance with the codes noted below.

Applicable code editions:

- 2023 and 2020 *Florida Building Code—Building*
- 2023 and 2020 *Florida Building Code—Residential*

2.0 CONCLUSIONS

The MiTek Truss Connectors for Wood-Framed Construction, described in Sections 2.0 through 7.0 of the evaluation report ESR-3448, comply with the *Florida Building Code—Building*, and the *Florida Building Code—Residential*. The design requirements shall be determined in accordance with the *Florida Building Code—Building* or the *Florida Building Code—Residential*, as applicable. The installation requirements noted in ICC-ES evaluation report ESR-3448 for the 2021 and 2018 *International Building Code*® meet the requirements of the *Florida Building Code—Building* or the *Florida Building Code—Residential*, as applicable.

Use of the MiTek truss connectors for wood-framed construction has also been found to be in compliance with the High-Velocity Hurricane Zone provisions of the *Florida Building Code—Building*, and the *Florida Building Code—Residential* with the following condition:

- a) For connections subject to uplift, the connection must be designed for no less than 700 pounds (3114 N).

For products falling under Florida Rule 61G20-3, verification that the report holder's quality assurance program is audited by a quality assurance entity approved by the Florida Building Commission for the type of inspections being conducted is the responsibility of an approved validation entity (or the code official when the report holder does not possess an approval by the Commission).

This supplement expires concurrently with the evaluation report, reissued October 2024.



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
Miami, Florida 33175-2474
T (786) 315-2590 F (786) 315-2599
www.miamidade.gov/economy

Nu-Vue Industries, Inc.
1055 East 29th Street
Hialeah, Florida 33013

SCOPE: This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series NVSNP, NV/NVTH, NVTHS, NVHC, NVSTA and NVHTA Steel Wood Connectors

APPROVAL DOCUMENT: Drawing No. **JA-1958.1-22**, titled "NOA No. 20-0526.05 Revision", sheets 1 through 5 of 5, dated 01/18/2023, prepared by Javad Ahmad PE, Inc., signed and sealed by Javad Ahmad, P.E. on 04/11/2023, bearing the Miami-Dade County Product Control revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: None

LABELING: A permanent mark with the manufacturer's name, acronym or logo is to be located on each unit. A permanent label with the manufacturer's name or logo, city, state, model/series, and the statement reading 'Miami-Dade County Product Control Approved' is to be located on each packaging carton.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **revises NOA # 20-0526.05** and consists of this page 1 and evidence pages E-1, E-2, E-3 and E-4, as well as approval document mentioned above.

The submitted documentation was reviewed by Ca

P.E.



NOA No. 23-0210.01
Expiration Date: July 30, 2025
Approval Date: May 11, 2023
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOAs

A. DRAWINGS “Submitted under NOA #15-0507.03”

1. Drawing No. NU-5, titled “Skewed Nail Plate, NV358 & NV458 with Double NVTH Straps, NVTH/NVTHS Anchors & NVHC Hurricane Clips and NVSTA & NVHTA Heavy Duty Anchors with Seat”, sheets 1 through 4 of 4, dated 04/15/2015, prepared by Nu-Vue Industries, Inc., signed and sealed by Vipin N. Tolat, P.E.

B. TESTS “Submitted under NOA # 04-0510.03”

Test reports on wood connectors per ASTM D1761 by Product Testing, Inc., signed and sealed by C. R. Caudel, P.E.

	<u>Report No.</u>	<u>Wood Connector</u>	<u>Direction</u>	<u>Date</u>
1.	PT # 03-4482	NVSNP3	Downward	09/15/03
2.	PT # 03-4625	NVHCL/R	Up& Sideways	01/21/04
3.	PT # 04-4641	NVSTA-24H	Up& Sideways	03/17/04
4.	PT # 04-4698	NVTH24	Up& Sideways	04/15/04
5.	PT # 03-4590	NVTH26/NV458	Sideways	12/31/03
6.	PT # 04-4642	NVHTA-24H	Up& Sideways	03/22/04
7.	PT # 03-4543	NVTH20/NV358	Up& Sideways	12/19/03

C. CALCULATIONS “Submitted under NOA # 09-0721.05”

1. Report of Design Capacities, dated 06/30/2009, sheets 1 through 12 of 12, prepared, signed and sealed by Vipin N. Tolat, P.E.

“Submitted under NOA # 04-0510.03”

2. Report of Design Capacities dated 04/27/2004, sheet 1 through 12, prepared, signed and sealed by Vipin N. Tolat, P.E.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENT “Submitted under NOA #15-0507.03”

1. Statement letter of code conformance to 2010 and 5th (2014) edition of the FBC, issued by Vipin N. Tolat, P.E., dated 04/29/2015, signed and sealed by Vipin N. Tolat, P.E.

“Submitted under NOA # 09-0721.05”

2. Statement letter of code conformance, no financial interest and no change of product, issued, signed and sealed by Vipin N. Tolat, P.E.



Car
Product
N
Expiration Date: July 30, 2023
Approval Date: May 11, 2023

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

2. EVIDENCE SUBMITTED UNDER NOA # 17-0802.07

A. DRAWINGS

1. Drawing No. NU-5, titled “Skewed Nail Plate, NV358 & NV458 with Double NVTH Straps, NVTH/NVTHS Anchors & NVHC Hurricane Clips and NVSTA & NVHTA Heavy Duty Anchors with Seat”, sheets 1 through 4 of 4, dated 07/17/2017, prepared by Nu-Vue Industries, Inc., signed and sealed by Vipin N. Tolat, P.E.

B. TESTS

1. None.

C. CALCULATIONS

1. None.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENT

1. Statement letter of code conformance to the 5th Edition (2014) and 6th Edition (2017) FBC, issued by Vipin N. Tolat, P.E., dated 07/25/2017, signed and sealed by Vipin N. Tolat, P.E.

Pro

Expir
Approval Date: May 11, 2020

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

3. EVIDENCE SUBMITTED UNDER NOA # 20-0526.05

A. DRAWINGS

1. Drawing No. NU-5, titled “Skewed Nail Plate, NV358 & NV458 with Double NVTH Straps, NVTH/NVTHS Anchors & NVHC Hurricane Clips and NVSTA & NVHTA Heavy Duty Anchors with Seat”, sheets 1 through 4 of 4, dated 06/25/2020, prepared by Nu-Vue Industries, Inc., signed and sealed by Vipin N. Tolat, P.E.

B. TESTS

1. Verification calculations for compliance with the ASTM D7147-05 and ASTM D7147-11, prepared by Vipin N. Tolat, P.E. dated 05/18/2020, signed and sealed by Vipin N. Tolat, P.E.

C. CALCULATIONS

1. None.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENT

1. Statement letter of code conformance to the 6th Edition (2017) and the 7th Edition (2020) FBC and of no financial interest, issued by Vipin N. Tolat, P.E., dated 06/25/2020, signed and sealed by Vipin N. Tolat, P.E.

Pro

Expir
Appr

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

4. NEW EVIDENCE SUBMITTED

A. DRAWINGS

1. Drawing No. **JA-1958.1-22**, titled “NOA No. 20-0526.05 Revision”, sheets 1 through 5 of 5, dated 01/18/2023, prepared by Javad Ahmad PE, Inc., signed and sealed by Javad Ahmad, P.E. on 04/11/2023.

B. TESTS

1. None.

C. CALCULATIONS

1. Allowable loads calculations, prepared by Javad Ahmad PE, Inc., dated 04/11/2023, signed and sealed by Javad Ahmad, P.E.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENT


1. Statement letter of code conformance to the 7th Edition (2020) of the FBC and of no financial interest, issued by Javad Ahmad PE, Inc., dated 02/03/2023, signed and sealed by Javad Ahmad, P.E.

Pro


Expira
Appro

1055 EAST 29TH HIALEAH, FL 33013, TEL. 305-694-0397


18G SEATS WITH 14G NVTH STRAPS




HEAVY DUTY ANCHORS WITH 14G
DOUBLE NVTH STRAPS



SKEWED NAIL PLATE



HURRICANE CLIPS



TRUSS ANCHORS AND RIVETED TRUSS ANCHORS

MATERIAL

1. **WOOD**
WOOD MEMBERS MUST BE S.P. NO. 1, SPECIFIC GRAVITY 0.55 OR AN APPROVED MEMBER WITH AN EQUIVALENT GRADE. DESIGN LOADS FOR OTHER SPECIES SHALL BE ADJUSTED PER NDS 2018. WOOD MEMBERS SHALL HAVE A MOISTURE CONTENT NOT EXCEEDING 19 PERCENT (16 PERCENT FOR STRUCTURAL ENGINEERED LUMBER). WOOD MEMBERS MUST BE USED UNDER CONTINUOUSLY DRY CONDITIONS AND WHERE SUSTAINED TEMPERATURES ARE LIMITED TO 100° F.
2. **PRESERVATIVE AND FIRE RETARDANT WOOD**
CONNECTORS OR FASTENERS USED IN CONTACT WITH PRESERVATIVE-TREATED AND FIRE-RETARDANT-TREATED WOOD SHALL BE IN ACCORDANCE WITH SECTION 2304.10.5.
3. **NAIL**
NAILS SHALL MEET THE REQUIREMENTS IN TABLE AND THE REQUIREMENTS SPECIFIED IN ASTM F 1667.
4. **GFCMU MASONRY**
MATERIAL AND QUALITY OF MASONRY CONSTRUCTION MUST COMPLY WITH THE APPLICABLE SECTIONS OF CBC 2020. MINIMUM CONCRETE OR GROUT COMPRESSIVE STRENGTH SHALL BE 1500 PSI. CONCRETE MASONRY SHALL COMPLY WITH ASTM C90
5. **CONCRETE**
MINIMUM CONCRETE COMPRESSIVE STRENGTH SHALL BE 2500 PSI.
6. **STEEL**
CONNECTOR STEEL SHALL CONFORM TO ASTM A653 SS GRADE 33, MIN. YIELD 33 KSI, MIN. TENSILE STRENGTH 45 KSI AND MIN. GALVANIZED COATING OF G 60 PER ASTM A653.

GENERAL NOTES:

1. ALLOWABLE LOADS AND ALL FASTENERS ARE BASED ON NATIONAL DESIGN SPECIFICATIONS (NDS) FOR WOOD CONSTRUCTION 2018.
2. DESIGN LOADS ARE BASED ON SOUTHERN YELLOW PINE WOOD SPECIES WITH A SPECIFIC GRAVITY OF 0.55. ALLOWABLE LOADS FOR OTHER SPECIES OR CONDITIONS MUST BE ADJUSTED ACCORDING TO NDS 2018.
3. THIS CATALOG REFLECTS DESIGN CHANGES AND DESIGN ADJUSTMENTS TO SOME NU-VUE PRODUCTS. THE TABLES AND NOTES IN THIS CATALOG SUPERCEDE ALL PREVIOUS DOCUMENTS. NU-VUE RESERVES THE RIGHT TO CHANGE DESIGN SPECIFICATIONS WITHOUT NOTICE AND IS NOT LIABLE FOR SUCH CHANGES.
4. DESIGN LOADS DO NOT INCLUDE 33% INCREASE FOR STEEL AND CONCRETE.
5. ALLOWABLE UPLIFT LOADS HAVE BEEN ADJUSTED FOR LOAD DURATION FACTOR CD OF 1.6. APPLICABLE TO WIND AND EARTHQUAKE LOAD PER NDS 2018.
6. DESIGN CONFORMS TO 2020 EDITION OF FLORIDA BUILDING CODE.
7. COMBINED LOAD OF UPLIFT, L1 AND L2 SHALL SATISFY THE FOLLOWING EQUATION.
$$\frac{\text{ACTUAL UPLIFT}}{\text{ALLOWABLE UPLIFT}} + \frac{\text{ACTUAL L1}}{\text{ALLOWABLE L1}} + \frac{\text{ACTUAL L2}}{\text{ALLOWABLE L2}} \leq 1.0$$
8. ALL TESTS HAVE BEEN CONDUCTED IN ACCORDANCE WITH ASTM D-1761.
9. THE DESIGN LOADS LISTED ARE BASED ON THE LEAST VALUE OF THE FOLLOWING:
 1. THE LOWEST ULTIMATE LOAD DIVIDED BY THREE.
 2. THE LOWEST LOAD PRODUCING 1/8" DEFLECTION.
 3. CALCULATIONS BASED ON NDS, AISI AND OTHER APPLICABLE CODES.

REFERENCES:


1. AISC 360-16
2. AISI S100-16
3. FBC 2020
4. ACI 318-19

PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0210.01

Expir **07/30/2025**

By _____
Miami

Product Control



JAVAD AHMAD P.E. inc

8800 NW 23rd St, Miami FL

33172



Ph: (305) 424-8001

support@ja-pe.com

CONSULTING • STRUCTURAL DESIGN • FACADES • BUILDING ENVELOPE • SYSTEM DESIGN • PRODUCT APPROVALS

DATE:	18/01/2023	REVISION				CLIENT : NU-VUE INDUSTRIES, INC
AS INDICATED		No.	DATE	BY	DESCRIPTION	
BY:	BVS					PROJECT : NOA NO. 20-0526.05 REVISION
BY:	BS					
DRAWING NO.						
DA-1958.1-22						

NVSNP3



NVSNP3
INSTALLATION


TABLE 1
SKEWED NAIL PLATE

PRODUCT CODE	STEEL GAUGE	FASTENERS	ALLOWABLE LOADS (lbs.)	
		EACH END	GRAVITY	UPLIFT
NVSNP3	16	(6) 8d X 1-1/2"	570	570

NOTES:

- SEE GENERAL NOTES, SHEET 1.
- USE 6 NAIL HOLES IN EACH FLANGE.
- DO NOT BEND NAIL PLATE MORE THAN ONCE.
- SUPPORTING MEMBER SHALL BE IN THE ACUTE ANGLE SIDE WITH OTHER FLANGE BEHIND THE END OF SUPPORTED MEMBER (SEE SKETCH).

PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0210.01
Expir 07/30/2025
By *[Signature]*
Miam oduct Control





JAVAD AHMAD PE, inc
8800 NW 23rd St, Miami FL
33172
Ph: (305) 424-8001
support@ja-pe.com

CLIENT :		PROJECT :	
NU-VUE INDUSTRIES, INC		NOA NO. 20-0526.05 REVISION	
REVISION		DESCRIPTION	
No.	DATE	BY	DESCRIPTION
1	18/01/2023	AS INDICATED	BVS
2			BS
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			


NV358 & NV458

TABLE 2
NV358 - 14G DOUBLE NVTH STRAPS WITH 2 PLY 18G SEAT

ASSEMBLY PRODUCT CODE	14G STRAP PRODUCT CODE	DIMENSION H (in.)	TOTAL NO. OF FASTENERS IN 2 STRAPS 10d X 3"	TOTAL NO. OF FASTENERS IN SEAT 10d X 3"	ALLOWABLE LOADS (lbs.)		
					UPLIFT	L1	L2
NV358-12	NVTH16	12	8	8	2245	1961	1839
NV358-14	NVTH18	14	10	8	2525	2206	2068
NV358-16	NVTH20	16	12	8	2806	2452	2298
NV358-20	NVTH24	20	14	8	3086	2697	2528
NV358-22	NVTH26	22	16	8	3367	2942	2758
NV358-24	NVTH28	24					
NV358-26	NVTH30	26					
NV358-32	NVTH36	32					
NV358-44	NVTH48	44					



14G NVTH



SIDE VIEW





TABLE 3
NV458 - 14G DOUBLE NVTH STRAPS WITH 3 PLY 18G SEAT

ASSEMBLY PRODUCT CODE	14G STRAP PRODUCT CODE	DIMENSION H (in.)	TOTAL NO. OF FASTENERS IN 2 STRAPS 10d X 3"	TOTAL NO. OF FASTENERS IN SEAT 10d X 3"	ALLOWABLE LOADS (lbs.)		
					UPLIFT	L1	L2
NV458-12	NVTH16	12	8	8	2245	2783	2078
NV458-14	NVTH18	14	10	8	2525	3131	2338
NV458-16	NVTH20	16	12	8	2806	3479	2597
NV458-20	NVTH24	20	14	8	3086	3827	2857
NV458-22	NVTH26	22	16	8	3367	4175	3117
NV458-24	NVTH28	24					
NV458-26	NVTH30	26					
NV458-32	NVTH36	32					
NV458-44	NVTH48	44					




NV358 & NV458
18G SEAT DETAIL

NOTES:

1. MINIMUM 4\"/>
2. NAILS ARE NECESSARY IN STRAPS AND SEAT TO ACHIEVE DESIGN LOADS.
3. NAILS THROUGH CHORDS SHALL NOT FORCE THE TRUSS PLATE ON THE OPPOSITE SIDE.
4. FOR GENERAL NOTES, SEE SHEET 1.

PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0210.01
Expir 07/30/2025
By  oduct Control




JAVAD AHMAD PE, inc
8800 NW 23rd St, Miami FL
33172
Ph: (305) 424-8001
support@ja-pe.com

CLIENT :		NU-VUE INDUSTRIES, INC	
PROJECT :		NOA NO. 20-0528.05 REVISION	
REVISION	DESCRIPTION	BY	DATE
	No.		
date:	18/01/2023	AS INDICATED	BVS
scale:			BS
by:			
check:			
drawing no.	JA-1958.1-22		

NVHCR/L & NVTH / NVTHS


TABLE 4
HURRICANE CLIPS

PRODUCT CODE	DESCRIPTION	GAUGE	FASTNERS 10d X 1-1/2"		ALLOWABLE LOADS (lbs)		
			HEADER	JOIST	UPLIFT	L1	L2
NVHCR	HURRICANE CLIP - RIGHT	18	6	6	525	253	333
NVHCL	HURRICANE CLIP - LEFT	18	6	6	525	253	333




NVTHS

NVTH



TYPICAL NVTH/NVTHS INSTALLATION



CROSS-SECTION


NOTES:

1. SEE GENERAL NOTES, SHEET 1.
2. FOR UPLIFT, USE TWO CLIPS, ONE ON EACH SIDE TO COMPLY WITH SECTION 2321.7 OF THE FBC


TABLE 5
TRUSS ANCHORS NVTH & RIVETED TRUSS ANCHORS WITH SEAT NVTHS

PRODUCT CODE		H	GAUGE	
		LENGTH(IN)	SEAT	STRAP
NVTH-16	NVTHS-212	12	18	14
NVTH-18	NVTHS-214	14	18	14
NVTH-20	NVTHS-216	16	18	14
NVTH-22	NVTHS-218	18	18	14
NVTH-24	NVTHS-220	20	18	14
NVTH-26	NVTHS-222	22	18	14
NVTH-28	NVTHS-224	24	18	14
NVTH-30	NVTHS-226	26	18	14
NVTH-36	NVTHS-232	32	18	14
NVTH-48	NVTHS-244	44	18	14


NO. OF FASTNERS IN EACH STRAP 10d x1-1/2"	MAXIMUM UPLIFT LOADS (lbs)		
	UPLIFT	L1	L2
5	1032	560	525
6	1222	671	630
7	1275	783	735
8	1329	783	735
9	1383	783	735
10	1437	783	735
11	1490	783	735
12	1544	783	735
13	1598	783	735



TYPICAL NVHCR/L INSTALLATION




NVTH, NVTHS FRONT VIEW



PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0210.01

Expir **07/30/2025**

By
Miami **Product Control**



JAVAD AHMAD PE, inc

8800 NW 23rd St, Miami FL

33172

Ph: (305) 424-8001

support@ja-pe.com

• CONSULTING • STRUCTURAL DESIGN • FACADES • BUILDING ENVELOPE • SYSTEM DESIGN • PRODUCT APPROVALS

CLIENT:

NU-VUE INDUSTRIES, INC.

PROJECT:

REVISION

BY	DESCRIPTION
----	-------------

DATE _____

No.

Date:	18/01/2022
-------	------------

10/17/2021 AS

INDICATED

1. Author: 2. Title: 3. Journal: 4. Year: 5. Volume: 6. Issue: 7. Pages: 8. Abstract: 9. Keywords: 10. References: 11. Notes: 12. Comments: 13. Conclusion: 14. Summary: 15. References: 16. Notes: 17. Comments: 18. Conclusion: 19. Summary: 20. References: 21. Notes: 22. Comments: 23. Conclusion: 24. Summary: 25. References: 26. Notes: 27. Comments: 28. Conclusion: 29. Summary: 30. References: 31. Notes: 32. Comments: 33. Conclusion: 34. Summary: 35. References: 36. Notes: 37. Comments: 38. Conclusion: 39. Summary: 40. References: 41. Notes: 42. Comments: 43. Conclusion: 44. Summary: 45. References: 46. Notes: 47. Comments: 48. Conclusion: 49. Summary: 50. References: 51. Notes: 52. Comments: 53. Conclusion: 54. Summary: 55. References: 56. Notes: 57. Comments: 58. Conclusion: 59. Summary: 60. References: 61. Notes: 62. Comments: 63. Conclusion: 64. Summary: 65. References: 66. Notes: 67. Comments: 68. Conclusion: 69. Summary: 70. References: 71. Notes: 72. Comments: 73. Conclusion: 74. Summary: 75. References: 76. Notes: 77. Comments: 78. Conclusion: 79. Summary: 80. References: 81. Notes: 82. Comments: 83. Conclusion: 84. Summary: 85. References: 86. Notes: 87. Comments: 88. Conclusion: 89. Summary: 90. References: 91. Notes: 92. Comments: 93. Conclusion: 94. Summary: 95. References: 96. Notes: 97. Comments: 98. Conclusion: 99. Summary: 100. References: 101. Notes: 102. Comments: 103. Conclusion: 104. Summary: 105. References: 106. Notes: 107. Comments: 108. Conclusion: 109. Summary: 110. References: 111. Notes: 112. Comments: 113. Conclusion: 114. Summary: 115. References: 116. Notes: 117. Comments: 118. Conclusion: 119. Summary: 120. References: 121. Notes: 122. Comments: 123. Conclusion: 124. Summary: 125. References: 126. Notes: 127. Comments: 128. Conclusion: 129. Summary: 130. References: 131. Notes: 132. Comments: 133. Conclusion: 134. Summary: 135. References: 136. Notes: 137. Comments: 138. Conclusion: 139. Summary: 140. References: 141. Notes: 142. Comments: 143. Conclusion: 144. Summary: 145. References: 146. Notes: 147. Comments: 148. Conclusion: 149. Summary: 150. References: 151. Notes: 152. Comments: 153. Conclusion: 154. Summary: 155. References: 156. Notes: 157. Comments: 158. Conclusion: 159. Summary: 160. References: 161. Notes: 162. Comments: 163. Conclusion: 164. Summary: 165. References: 166. Notes: 167. Comments: 168. Conclusion: 169. Summary: 170. References: 171. Notes: 172. Comments: 173. Conclusion: 174. Summary: 175. References: 176. Notes: 177. Comments: 178. Conclusion: 179. Summary: 180. References: 181. Notes: 182. Comments: 183. Conclusion: 184. Summary: 185. References: 186. Notes: 187. Comments: 188. Conclusion: 189. Summary: 190. References: 191. Notes: 192. Comments: 193. Conclusion: 194. Summary: 195. References: 196. Notes: 197. Comments: 198. Conclusion: 199. Summary: 200. References: 201. Notes: 202. Comments: 203. Conclusion: 204. Summary: 205. References: 206. Notes: 207. Comments: 208. Conclusion: 209. Summary: 210. References: 211. Notes: 212. Comments: 213. Conclusion: 214. Summary: 215. References: 216. Notes: 217. Comments: 218. Conclusion: 219. Summary: 220. References: 221. Notes: 222. Comments: 223. Conclusion: 224. Summary: 225. References: 226. Notes: 227. Comments: 228. Conclusion: 229. Summary: 230. References: 231. Notes: 232. Comments: 233. Conclusion: 234. Summary: 235. References: 236. Notes: 237. Comments: 238. Conclusion: 239. Summary: 240. References: 241. Notes: 242. Comments: 243. Conclusion: 244. Summary: 245. References: 246. Notes: 247. Comments: 248. Conclusion: 249. Summary: 250. References: 251. Notes: 252. Comments: 253. Conclusion: 254. Summary: 255. References: 256. Notes: 257. Comments: 258. Conclusion: 259. Summary: 260. References: 261. Notes: 262. Comments:

ON CIVILIAN



DRAWING NO.


NVSTA & NVHTA

TABLE 6


NVSTA - HEAVY DUTY ANCHORS WITH 14G NVTH STRAPS AND 1 PLY 20G SEAT

ASSEMBLY PRODUCT CODE	14G STRAP PRODUCT CODE	DIMENSION H (in.)	TOTAL NO. OF FASTENERS IN STRAP 10d X 1-1/2"	TOTAL NO. OF FASTENERS IN 20 GA. SEAT 10d X 1-1/2"	ALLOWABLE LOADS (lbs.)		
					UPLIFT*	L1*	L2*
NVSTA-12H	NVTH16	12	5	6	1308	700	1049
NVSTA-14H	NVTH18	14	6	6	1426	760	1144
NVSTA-16H	NVTH20	16	7	6	1545	823	1239
NVSTA-20H	NVTH24	20	8	6	1664	887	1335
NVSTA-22H	NVTH26	22	9	6	1783	950	1430
NVSTA-24H	NVTH28	24					
NVSTA-26H	NVTH30	26					
NVSTA-32H	NVTH36	32					
NVSTA-44H	NVTH48	44					








NVHTA WITH 14G DOUBLE
NVTH STRAP



NVSTA WITH 14G SINGLE NVTH STRAP



NVSTA
12H TO 44H INSTALLATION




NVHTA
12H TO 44H INSTALLATION


TABLE 7

NVHTA - HEAVY DUTY ANCHORS WITH 14G DOUBLE NVTH STRAPS AND 1 PLY 20G SEAT

ASSEMBLY PRODUCT CODE	14G STRAP PRODUCT CODE	DIMENSION H (in.)	TOTAL NO. OF FASTENERS IN STRAP 10d X 1-1/2"	TOTAL NO. OF FASTENERS IN 20 GA. SEAT 10d X 1-1/2"	ALLOWABLE LOADS (lbs.)			
					UPLIFT*	UPLIFT**	L1*	L2*
NVHTA-12H	NVTH16	12	10	6	1772	2078	1050	1450
NVHTA-14H	NVTH18	14	12	6	1994	2338	1181	1631
NVHTA-16H	NVTH20	16	14	6	2215	2598	1312	1812
NVHTA-20H	NVTH24	20	16	6	2437	2858	1444	1994
NVHTA-22H	NVTH26	22	18	6	2658	3117	1575	2175
NVHTA-24H	NVTH28	24						
NVHTA-26H	NVTH30	26						
NVHTA-32H	NVTH36	32						
NVHTA-44H	NVTH48	44						




14G NVTH
FRONT VIEW



SIDE VIEW
20 GA. SEAT

NOTES:

1. SEE GENERAL NOTES, SHEET 1.
2. NAILS ARE NECESSARY IN STRAPS AND SEAT TO ACHIEVE DESIGN LOADS.
3. NAILS THROUGH CHORDS SHALL NOT FORCE THE TRUSS PLATE.
4. **FOR HIGHER UPLIFT LOADS, CONCRETE SHALL BE 3000PSI.
5. *BASED ON MINIMUM 2500 PSI CONCRETE.




20 GA. SEAT

PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 23-0210.01

Expir e **07/30/2025**

By
Miami Product Control



JAVAD AHMAD PE, inc

8800 NW 23rd St, Miami FL

33172

Ph: (305) 424-8001

support@ja-pe.com

CONSULTING • STRUCTURAL DESIGN • FACADES • BUILDING ENVELOPE • SYSTEM DESIGN • PRODUCT APPROVALS

CLIENT:

NU-VUE INDUSTRIES, INC.

PROJECT:

NOA NO. 20-0526.05 REVISION

REVISION

DESCRIPTION

10.1101/2017.05.01.132111v1 [v1; not certified by peer review] (2017)

[illegible]

18/01/2023

AS	10/01/2020
----	------------

INDICATED	
P/S	

mc	
----	--

DRAWING NO. 1A-1958 1-22

WEB BRACING RECOMMENDATIONS

BRACE BAY SIZE	MAXIMUM TRUSS WEB FORCE (lbs.) (See note 7)									
	24" O.C.				48" O.C.				72" O.C.	
	BRACING MATERIAL TYPE				BRACING MATERIAL TYPE				BRACING MATERIAL TYPE	
	A	B	C	D	A	B	C	D	C	D
10'-0"	1610	1886	1886	2829						
12'-0"	1342	1572	1572	2358		3143	3143	4715	4715	7074
14'-0"	1180	1347	1347	2021						
16'-0"	1006	1179	1179	1758		2358	2358	3530		
18'-0"	894	1045	1045	1572					3143	4715
20'-0"	805	943	943	1414		1886	1886	2829		


* Bay size shall be measured in between the centers of pairs of diagonals.

TYPE	BRACING MATERIALS	GENERAL NOTES
A	1 X 4 END, 4S SP OR 1 X 4 #2 SFRS (DF, HF, SPF)	GENERAL NOTES 1. DIAGONAL BRACING IS REQUIRED TO TRANSFER THE CUMULATIVE LATERAL BRACE FORCE INTO THE ROOF AND/OR CEILING DIAPHRAGM. THE DIAPHRAGM IS TO BE DESIGNED BY A QUALIFIED PROFESSIONAL. 2. THESE CALCULATIONS ARE BASED ON LATERAL BRACE CARRYING 25% OF THE WEB FORCE. 3. DIAGONAL BRACING MATERIAL MUST BE SAME SIZE AND GRADE OR BETTER, AS THE LATERAL BRACE MATERIAL, AND SHALL BE INSTALLED IN SUCH A MANNER THAT IT INTERSECTS WEB MEMBERS AT APPROX. 45 DEGREES AND SHALL BE NAILED AT EACH END AND EACH INTERMEDIATE TRUSS WITH 2-6d (0.131" x 1 1/2") NAILS FOR 2-4 BRACES, 2-10d (0.131" x 3") NAILS FOR 2-6 BRACES, AND 2-10d (0.131" x 3") NAILS FOR 2-8 BRACES. 4. CONNECT LATERAL BRACE TO EACH TRUSS WITH 2-6d (0.131" x 1 1/2") NAILS FOR 1st LATERAL BRACE, 2-10d (0.131" x 3") NAILS FOR 2nd and 3rd LATERAL BRACE, AND 2-10d (0.131" x 3") NAILS FOR 4th LATERAL BRACE. 5. LATERAL BRACE SHOULD BE CONTINUOUS AND SHOULD OVERLAP AT LEAST ONE TRUSS SPACE FOR CONTINUITY. 6. FOR ADDITIONAL GUIDANCE REGARDING DESIGN AND INSTALLATION OF BRACING, CONSULT DSR-99 TEMPORARY BRACING OF METAL PLATE CONNECTED WOOD TRUSSES AND SOBS 1 GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING & BRACING OF METAL PLATE CONNECTED WOOD TRUSSES, JOINTLY PRODUCED BY WOOD TRUSS COUNCIL OF AMERICA AND TRUSS PLATE INSTITUTE. www.woodtruss.org and trussplate.org 7. REFER TO SPECIFIC TRUSS DESIGN DRAWING FOR WEB MEMBER FORCE. 8. TABULATED VALUES ARE BASED ON A DCL = 1.16
B	2 X 3 #3, STD, CONST (SPF, DF, HF, OR SP)	
C	2 X 4 #3, STD, CONST (SPF, DF, HF, OR SP)	
D	2 X 6 #3 OR BETTER (SPF, DF, HF, OR SP)	

FOR STABILIZERS:

FOR A SPACING OF 24" O.C. ONLY, MITER "STABILIZER" TRUSS BRACING SYSTEMS CAN BE SUBSTITUTED FOR TYPE A, B, C AND D BRACING MATERIAL. DIAGONAL BRACING FOR STABILIZERS ARE TO BE PROVIDED AT BAY SIZE INDICATED ABOVE. WHERE DIAPHRAGM BRACING IS REQUIRED AT PITCH BREAKS, STABILIZERS MAY BE REPLACED WITH WOOD BLOCKING. SEE "STABILIZER" TRUSS BRACING INSTALLATION GUIDE AND PRODUCT SPECIFICATION.

DIAGONAL BRACE



This information is provided as a recommendation to assist in the selection of permanent bracing of the individual truss web members. Additional bracing may still be required for the stability of the overall roof system. The method shown here is just one method that can be used to provide stability against web buckling.

ARMANDO R. PEREZ
 PE. # 28026
 1811 SW 33 CT
 MIAMI, FL 33145
 (305) 213-7443

DATE 9/19/16

L-BRACE DETAIL

Nailing Pattern

L-Brace size	Nail Size	Nail Spacing
1x4 or 6	10d	8" o.c.
2x4, 6, or 8	16d	8" o.c.

Note: Nail along entire length of L-Brace
(On Two-Ply's Nail to Both Plies)

Note: L-Bracing to be used when continuous lateral bracing is impractical. L-brace must cover 90% of web length.

L-Brace Size for One-Ply Truss

Specified Continuous Rows of Lateral Bracing

Web Size	1	2
2x3 or 2x4	1x4	***
2x6	1x6	***
2x8	2x8	***


*** DIRECT SUBSTITUTION NOT APPLICABLE

L-Brace Size for Two-Ply Truss

Specified Continuous Rows of Lateral Bracing

Web Size	1	2
2x3 or 2x4	2x4	***
2x6	2x6	***
2x8	2x8	***

*** DIRECT SUBSTITUTION NOT APPLICABLE



L-Brace must be same species grade (or better) as web member.

ARMANDO R. PEREZ
PE. # 28026
1811 SW 33 CT
MIAMI, FL 33145
(305) 213-7443

DATE 9/19/16

TRUSSED VALLEY SET DETAIL

ARMANDO PEREZ PE 28026

(TYPICAL)

Page 1 of 1

GABLE END, COMMON TRUSS
OR GIRDER TRUSS

NOTE: VALLEY STUD SPACING NOT
TO EXCEED 48" O.C. SPACING


VALLEY TRUSS TYPICAL
(24" O.C.)

BASE TRUSSES
TYPICAL (24" O.C.)

VALLEY TRUSS TYPICAL
(24" O.C.)
MAXIMUM

SEE TRUSS PLAN

1. INSTALL BASE TRUSSES.
2. APPLY SHEATHING TO TOP CHORD OF SUPPORTING TRUSSES. VALLEY TRUSSES MAY PROVIDE BRACING IF SHEATHING IS NOT APPLIED. BASE TRUSSES MUST BE DESIGNED FOR PURLIN SPACING EQUIVALENT TO VALLEY TRUSS SPACING (NOT TO EXCEED 24" O.C.).
3. INSTALL VALLEY TRUSSES (24" O.C. MAXIMUM) AND SECURE TO BASE TRUSSES AS PER DETAIL A, B, OR C BELOW.
4. BRACE VALLEY WEBS IN ACCORDANCE WITH THE INDIVIDUAL DESIGN DRAWINGS.



TOE - NAIL VALLEY TO
BASE TRUSS W/
(2) 16d TOE NAILS

ATTACH 2x4 CONTINUOUS NO.2 SPF
TO THE FACE OF THE ROOF W/ TWO
16d (.131" x 3.5") NAILS INTO EACH
TRUSS BELOW

SEE TRUSS PLAN FOR
LOADS

ATTACH 2x4 CONTINUOUS NO.2 SPF
BLOCK TO THE FACE OF THE ROOF W/
(2) 16d (.131" x 3.5") NAILS INTO EACH
TRUSS BELOW. EACH TRUSS BELOW
MUST HAVE A BLOCK ATTACHED TO IT.

TOE - NAIL VALLEY TO
BASE TRUSS W/
(2) 16d TOE NAILS

DETAIL A
(GREATER THAN 3/12 PITCH)

DETAIL B
(3/12 PITCH OR LESS)

ATTACH BEVELED 2x4 CONTINUOUS
NO.2 SPF TO THE FACE OF THE ROOF
W/ TWO 16d (.131" x 3.5") NAILS INTO
EACH TRUSS BELOW

ATTACH VALLEY TO
BEVELED 2x4 W/
(2) 16d TOE NAILS

DETAIL C
(GREATER THAN 3/12 PITCH
LESS THAN 12/12 PITCH)

TOE - NAIL VALLEY TO
BASE TRUSS W/
(2) 16d TOE NAILS

ARMANDO R. PEREZ PE28026

786-255-4344 DATE 9/13/2013

1811 S W33 CORNER MEADOWS 33145

