



AL-FAROOQ CORP

CONSULTING ENGINEERS & PROD

SHOP DRAWING / SUBMITTAL REVIEW

☒ APPROVED ☐ APPROVED WITH CHANGES NOTED
☐ REVISE AND RESUBMIT ☐ REJECTED: _____

SUBMITTAL WAS REVIEWED FOR DESIGN CONFORMITY AND GENERAL CONFORMANCE TO CONTRACT DOCUMENTS ONLY. THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING AND CORRELATING DIMENSIONS AT JOB SITES FOR TOLERANCES, CLEARANCES, QUANTITIES, FABRICATION PROCESSES AND TECHNIQUES OF CONSTRUCTION, COORDINATION OF HIS WORK WITH OTHER TRADES AND FULL COMPLIANCE WITH THE CONTRACT DOCUMENTS.

BY Julio Pulido DATE 08-04-25

NOVUS ARCHETYPE, LLC
12721 SW 30 ST
MIAMI, FL 33175

PRODUCT APPROVAL EVALUATION RULE CHAPTER #61G20-3 • METHOD 1 OPTION D

FL 21899

Date: 07/13/2023

Detailed Product Description:

Manufacturer: EGS INTERNATIONAL, LLC

Manufacturer Address: 3133 SW 25TH STREET. PEMBROKE PARK, FL 33009

Model Name: RAMPART SERIES 5500 ALUMINUM WINDOW WALL SYSTEM

Maximum Load: +100 PSF, -100 PSF (Large Missile Impact)

Installation Drawings # W16-66

This product complies with the High Velocity Hurricane Zone (HVHZ) testing requirements.					
For maximum sizes, combination of span vs loads and anchor type refer to installation drawings.					
Comparative analysis used ☒ Yes ☐ No					
Mandatory Tests (Tested in accordance with AAMA 501/101/I.S.2/NAFS/TAS 202)					
TEST	DESCRIPTION	TEST LOCATION	TEST REPORT DATE	TEST REPORT #	TEST SEALED BY
ASTM E283	Air Infiltration Leakage	Architectural Testing	02/14/2017	G3802.01-450-18	Joseph A. Reed, PE
ASTM E331 or ASTM 547 & TAS 202	Water Penetration	Architectural Testing	02/14/2017	G3802.01-450-18	Joseph A. Reed, PE
ASTM E330 & TAS 202	Uniform Static Air Pressure	Architectural Testing	02/14/2017	G3802.01-450-18	Joseph A. Reed, PE
Supplemental Tests (Tested in accordance with TAS-201 and TAS-203)					
TEST	DESCRIPTION	TEST LOCATION	TEST REPORT DATE	TEST REPORT #	TEST SEALED BY
FBC 1626.2 (TAS 201 & 203) ANSI Z97.1	Large Missile Impact & Cyclic	Architectural Testing	02/14/2017	G3802.01-450-18	Joseph A. Reed, PE
Under the limitations of the attached installation drawings, to the best of my knowledge and ability, the above product conforms to the requirements of the 2023 Florida Building Code.					
Evaluation Report Engineer: Jalal Farooq Al-Farooq Corporation			PE # 81223 EB # 3538		
			 Sealed: 7/12/2023		